

Proposed Final 2018 Amendment to the 2002 Gore Mountain Unit Management Plan and Final Generic Environmental Impact Statement



March 2018

Lead Agency and Prepared by:

The Olympic Regional Development Authority 2634 Main Street, Lake Placid, New York 12946 (518) 302-5332

Contact: Robert W. Hammond

and

Gore Mountain Ski Center 793 Peaceful Valley Road, North Creek, New York 12853 (518) 251- 2411

Contact: Emily Stanton

In cooperation with:

The NYS Department of Environmental Conservation and in consultation with:

The Adirondack Park Agency Ray Brook, New York 12977

Private Consultants:

The LA Group, Landscape Architecture and Engineering, P.C. 40 Long Alley, Saratoga Springs, New York 12866 (518) 587-8100

Contact: Kevin Franke

Date of Acceptance of DGEIS: January 3, 2018
Date of Public Hearing: January 24, 2018
Date of Close of Comment Period: February 9, 2018
Date of Acceptance of FGEIS:

Submitted: February 26, 2018

EXECUTIVE SUMMARY

I. INTRODUCTION

This 2018 Unit Management Plan (UMP) Amendment has been prepared in accordance with the Adirondack Park State Land Master Plan (APSLMP or SLMP), addresses changes to the 2002 UMP and the 2005 UMP Amendment thereto, and adds several new management actions. This 2018 UMP Amendment lists and reviews the status of the 1995, 2002 and 2005 management actions and identifies those management actions that have been completed, those which are pending, and those that are modified or abandoned within this 2018 UMP Amendment. Previous UMP documents are incorporated by reference into this document.

Since the completion of the last UMP Amendment, Gore Mountain has received recognition from the Ski Industry and the press for, not only its quality skiing experience, but also for its environmental stewardship. In May 2016, Gore Mountain was awarded the esteemed Golden Eagle for Overall Environmental Excellence by a ski area from the National Ski Areas Association. The Golden Eagle is the industry's most prestigious award for sustainability and Gore's broad range of environmental stewardship across several areas of its operation was integral to its win.



Gore Mountain successfully demonstrated that a growing resort¹ can at the same time be sustainable. Projects that contributed to this award were Gore's contracting of two 25-year solar power purchasing agreements, strategic trail modifications to increase uphill operational efficiency, energy-saving snowmaking, creative repurposing of buildings, the redevelopment of historic trails, various education efforts and Gore's increased provision of locally sourced food.

II. 2018 UMP AMENDMENT MANAGEMENT ACTIONS

New management actions are identified and analyzed in this 2018 UMP Amendment. The potential environmental impacts and the attendant proposed mitigation measures for any new or modified management actions are also identified and discussed. The potential impacts and

¹ Gore's acreage and uphill capacity have increased 131 percent and 142 percent respectively over the past 20 years.

the identified mitigation measures for the previously approved UMP management actions remain in effect and will not be repeated here, but are incorporated by reference.

The following lists the New Management Actions that are the subject of this UMP Amendment and that can be undertaken after the UMP Amendment is adopted. See **Figure** ES-1, 2018 Master Plan (South) and **Figure** ES-2, 2018 Master Plan (North).

Trail Construction and Trail Widening

- Construct a new trail at Burnt Ridge that connects to the Base Lodge via the lower portion of Echo
- Construct a new trail adjacent to the Ski Bowl to replace the existing Half 'N Half glade.
- Widen the bottom of Echo as it turns toward the base area
- Widen some sections of Twister
- Widen Sunway and other green trails served by Lift 3

Lifts

 Add a new triple or quad chair (Lift 9B) from Northwoods Lodge up Lower Sunway to just past the bend in Lower Sunway

Vehicular Access and Parking

 Modify the 1995-approved shuttle lane separated from and independent of main traffic route and circulation route and parking

Buildings

- Expand the NYSEF building
- Reconfigure the 1995-approved maintenance complex to locate groomer garage and fueling station adjacent to Sunway trail

Snowmaking

- Enlarge the snowmaking reservoir
- Install a new 24 inch gravity water line from the snowmaking reservoir to the pump house

Mountain Biking


Construct a single-track bike trail loop for Town trail at the top of Little Gore


Hiking

Develop a hiking center based out of the Northwoods Lodge.

Requests for Land Reclassifications

Request a land reclassification from Wild Forest to Intensive Use and from Intensive Use
to Wilderness which could allow the historic Rabbit Pond Trail to be used as a trail, if
authorized in a subsequent UMP.





Final Generic Environmental Impact Statement

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law.

© the LA Group 2017

Development Authority

2634 Main Street Lake Placid, New York 12946

Figure ES-2

(Note: The Adirondack Park Agency (APA) cannot find that a UMP Amendment proposing management actions on lands to be reclassified conforms to the Adirondack Park State Land Master Plan (APSLMP) before the land is reclassified. First, the Agency must receive a request to reclassify, accompanied by a UMP for the proposed Intensive Use lands. The Agency must follow SEQRA regulations regarding public notice and comment and must hold hearings inside and outside the Adirondack Park on the request to reclassify, pursuant to the APSLMP. After notice, comment and hearings, the reclassification proposals would be presented to the Agency for a recommendation to the Governor for approval of the classification. The process culminates in the Governor's action on that recommendation. This UMP Amendment does not assume that a reclassification request will be approved and does not authorize any actions on lands requested to be reclassified, based on a proposed future classification. The actual request for reclassification and a UMP Amendment for those actions on the lands proposed for reclassification would be presented separately from this UMP Amendment. Discussion of actions on those lands in this UMP is conceptual only, and those actions cannot be authorized by this UMP Amendment.)

These management actions are discussed in the context of existing resources, facilities and use (Section 3) and ORDA's Management and Policy relating to the Gore Mountain Intensive Use Area (Section 3). The management actions themselves are described in detail in Section 4.

An introductory section (Section 1) first gives an overview of project purpose, a general facility description, the history of the ski area, a description of the UMP/GEIS process and a summary update of the status of actions contained in previous UMPs.

III. <u>SEQRA PROCESS</u>

ORDA, as the Agency responsible for undertaking the actions in this 2018 UMP Amendment/FGEIS, completed a New York State Environmental Quality Review Act (SEQRA) Full Environmental Assessment Form (FEAF)Parts 1, 2, and 3 (See Appendix 1). Based on the analysis in Part 3 of the FEAF, ORDA determined that the Project may result in one or more significant adverse impacts on the environment and this Environmental Impact Statement (EIS) must be prepared to further assess the impacts and possible mitigation and to explore alternatives to avoid or reduce these impacts.

The SEQRA aspects of this document are presented as a Generic Environmental Impact Statement (GEIS). A Generic EIS may be used to assess the environmental effects of a sequence of actions contemplated by a single agency or an entire program or plan having wide application (6NYCRR 617.10(a)(2) and (4)). They differ from a site specific EIS in that it applies to a group of common and related activities which have similar or related impacts. It is the intent of this GEIS to provide sufficient, site-specific information for all aspects of this UMP Amendment. In conformance with SEQRA, these related actions are being considered in this FGEIS. No additional SEQRA analyses are anticipated to be required for any management action in this UMP, provided that such actions are carried out in accordance with the recommendations of this document. Conceptual actions are subject to future SEQRA

analyses should they be pursued in the future.

A preliminary version of the UMP Draft Amendment/DGEIS was provided to NYSDEC and to the APA for their review on December 8, 2017. Comments from these agencies were received by ORDA, and ORDA revised the preliminary document accordingly. ORDA then declared that document to be complete for public review on January 3, 2018. Notice of ORDA's acceptance of the DGEIS, establishment of the public comment period, and directions for accessing the Public Draft UMP Amendment/DGEIS were published in the January 10, 2018 issue of the Environmental Notice Bulletin. The Public Draft UMP Amendment/DGEIS was presented to the APA at their January 11, 2018 Agency meeting.

The Draft 2018 UMP Amendment/DGEIS was open for public comment until February 9, 2018 including a SEQRA public hearing held at 7:00 PM on January 24, 2018 at the Gore Mountain Base Lodge. Responses were prepared to comments received at the public hearing and to written comments submitted during the public comment period. A transcript of the public hearing, copies of written comments and responses to comments are included in this FGEIS. Also included in this FGEIS is an errata section that summarizes the changes that were made to the DGEIS when preparing this FGEIS.

Part 3 of the FEAF identified those topics for which additional information was required within the GEIS. Primary concerns include steep slope soil erosion and water quality, water quality impacts associated with enlargement of the snowmaking reservoir, and potential impacts to the Bicknell's thrush, a species of special concern in New York State. Potential impacts and mitigation measures for these topics and a range of other topics are discussed in detail in Section 5 of this UMP/FGEIS.

Section 6 considers alternatives to the new management actions including alternative trail improvements, lift configurations, parking and circulation and appurtenances.

ORDA is currently contemplating simultaneous improvements on Town of Johnsburg owned lands at the North Creek Ski Bowl, outside of the Intensive Use Area. Because these actions are not within the Intensive Use Area, they are not covered within this UMP Amendment. Instead, these actions will be subject to APA review under section 814 of the Adirondack Park Agency Act and also subject to review under SEQRA. In order to make the requisite assessment of cumulative impacts, this UMP Amendment/GEIS is accompanied by two companion documents which will be referred to as Part B and Part C (Part A being the UMP/GEIS). Part B is the Ski Bowl Notice of Intent to the APA required under section 814 and accompanying SEQRA documentation. Part C is a cumulative impact assessment of the actions proposed within the Intensive Use Area and the actions proposed at the Ski Bowl.

IV. CONFORMANCE WITH THE APSLMP

It is stated in Section I of the APSLMP that "In accordance with statutory mandate, all [unit management] plans will conform to the guidelines and criteria set forth in the master plan"

The following is from the Intensive Use Area portion of Section 2 of the APSLMP, and includes descriptions of how this UMP Amendment conforms to the stated guidelines.

Guidelines for Management and Use

Basic Guidelines

1. The primary management guideline for Intensive Use Areas will be to provide the public opportunities for family group camping, developed swimming and boating, downhill skiing, cross country skiing under competitive or developed conditions on improved cross country ski trails, visitor information and similar outdoor recreational pursuits in a setting and on a scale that are in harmony with the relatively wild and undeveloped character of the Adirondack Park.

The Gore Mountain Intensive Use Area will continue to provide opportunities for downhill skiing, cross-country skiing and similar outdoor recreational pursuits.

There are no new management actions in this UMP Amendment that change the current setting or scale of the facilities at Gore Mountain. One ski lift will be slightly relocated and replaced while another lift will be added in the same general area to provide better service on the beginner ski terrain low on the mountain. Selective trail widening will occur on the trails served by these lifts. A single new ski trail is proposed to be constructed in between existing ski trails in order to provide a connection between Burnt Ridge and the Base Area during those times when the Echo trail is being used for ski racing and is not available for public use. Selective trail widening on the Twister trail is limited in nature and is intended to provide a more uniform trail width along its length.

2. All intensive use facilities should be located, designed and managed so as to blend with the Adirondack environment and to have the minimum adverse impact possible on surrounding state lands and nearby private holdings. They will not be situated where they will aggravate problems on lands already subject to or threatened by overuse, such as the eastern portion of the High Peaks Wilderness, the Pharaoh Lake Wilderness or the St. Regis Canoe Area or where they will have a negative impact on competing private facilities. Such facilities will be adjacent to or serviceable from existing public road systems or water bodies open to motorboat use within the Park.

All of the new management actions proposed in this UMP Amendment, and that can take place after the adoption of this UMP Amendment, are located low on the mountain where they will not cause a visual impact (see UMP section V.C.I). All actions are located in the interior of the Intensive Use Area removed from adjoining State and private lands. This UMP amendment is not proposing any significant enlargement of the ski area, so there is no potential for adversely affecting lands subject or threatened by overuse or competing private facilities.

- 3. Construction and development activities in Intensive Use Areas will:
 - -- avoid material alteration of wetlands;

Impacts to wetlands have been avoided (see UMP section V.A.5).

-- minimize extensive topographic alterations;

No extensive topographic alterations are proposed (see UMP section V.A.3).

-- limit vegetative clearing;

Vegetative clearing has been limited and it is well within the limits established by Article 14 of the NYS Constitution (see UMP section V.B.1 and Appendix 5). and,

- -- preserve the scenic, natural and open space resources of the Intensive Use Area. See items 1 and 2 above.
- 4. Day use areas will not provide for overnight camping or other overnight accommodations for the public.

No overnight accommodations, camping or otherwise, are proposed.

5. Priority should be given to the rehabilitation and modernization of existing Intensive Use Areas and the complete development of partially developed existing Intensive Use Areas before the construction of new facilities is considered.

The actions contained in this UMP amendment are for the improvement and modernization of the existing Gore Mountain Intensive Use Area.

6. Additions to the intensive use category should come either from new acquisitions or from the reclassification of appropriate wild forest areas, and only in exceptional circumstances from wilderness, primitive or canoe areas.

This UMP amendment suggests land reclassification that would include an addition to the Intensive Use Area from the Vanderwhacker Mountain Wild Forest and an addition to the Siamese Ponds Wilderness Area from the Intensive Use Area (see UMP section IV.8).

7. Any request for classification of a new acquisition or reclassification of existing lands from another land use category to an Intensive Use Area will be accompanied by a draft unit management plan for the proposed Intensive Use Area that will demonstrate how the applicable guidelines will be respected.

These same ten Intensive Use Area guidelines from the SLMP will be examined for the lands requested for reclassification (see UMP section IV.8).

8. No new structures or improvements at any Intensive Use Area will be constructed except in conformity with a final adopted unit management plan for such area. This guideline

will not prevent the ordinary maintenance, rehabilitation or minor relocation of conforming structures or improvements.

None of the new management actions contained in this UMP amendment will be constructed unless and until they are included in the final UMP amendment adopted by NYSDEC.

9. Since the concentrations of visitors at certain intensive use facilities often pose a threat of water pollution, the state should set an example for the private sector by installing modern sewage treatment systems with the objective of maintaining high water quality. Standards for the state should in no case be less than those for the private sector and in all cases any pit privy, leach field or seepage pit will be at least 150 feet from the mean high water mark of any lake, pond, river or stream.

No in-ground wastewater treatment is proposed.

10. Any new, reconstructed or relocated buildings or structures located on shorelines of lakes, ponds, rivers or major streams, other than docks, primitive tent sites not a part of a campground (which will be governed by the general guidelines for such sites set forth elsewhere in this master plan) boat launching sites, fishing and waterway access sites, boathouses, and similar water related facilities, will be set back a minimum of 150 feet from the mean high water mark and will be located so as to be reasonably screened from the water body to avoid intruding on the natural character of the shoreline and the public enjoyment and use thereof.

No new buildings or structures are proposed anywhere near any shorelines.

V. <u>IMPACT ANALYSIS</u>

A. Geology

Bedrock is at or near the ground surface in many locations in the Gore Mountain Intensive Use Area.

Bedrock may be encountered when constructing a portion of the dedicated shuttle lane. There is an area of Lyman-Rock Outcrop soils between parking lot E and the base lodge. It may be necessary to blast some bedrock to create the shuttle lane through this area. It is also possible that blasting may be necessary as part of some of the trail creation or trail widening management actions. Bedrock may also be encountered when enlarging the snowmaking reservoir which could also necessitate blasting. Hermon-Lyman-Rock Outcrop soils are mapped on the north and south sides of the reservoir.

As described in UMP Section II.A.1.a, the landform that is Gore Mountain, including the Barton garnet mine that is located on the north side of the mountain, is considered a unique geologic

feature because of the nearby garnet deposits (http://www.dec.ny.gov/permits/53858.html). These deposits will not be affected by the construction activities associated with the shuttle lane or the snowmaking reservoir which are both located at low elevations on the mountain.

ORDA will employ the services of a professional, licensed and insured blasting company to perform any needed blasting. Blasters in New York State are required to possess a valid NY State Department of Labor issued Explosive License and Blaster Certificate of Competence. The Explosives License permits the licensee to purchase, own, possess or transport explosives. The Blaster Certificate of Competence permits the use of explosives.

If it is determined that blasting will be required, a written blasting plan will be developed and approved prior to the commencement of blasting. In general, the blast plan will contain information about the blasting methods to be employed, measures to be taken to protect the safety of the public, and how the applicable rules and regulations will be complied with. If during the evolution of the project there are significant changes in the blast design a new blast plan will be required. A test shot will be required for the first shot after the approval of each blast plan.

See Section V.A.1 for a full description of all of the measures ORDA will implement to mitigate potential impacts from any blasting that may be required.

B. Soils

Soil Erodibility (K) Factors are discussed in Section 2.A.1.b of the UMP. "K" is one factor used to calculate potential soil loss using the Revised Universal Soil Loss Equation (RUSLE). Other factors in RUSLE include slope length (L) and slope steepness (S).

Construction of most new Management Actions is proposed on soils with an "E" slope category. E soils are described as steep. Some new management actions are proposed on soils with a "C" slope category. C soils are described as sloping.

Disturbance of areas of steep slopes during construction can lead to an increased vulnerability of the soils to erosion. Suitable measures must be implemented to first prevent soil erosion and then second to make sure that any soils that are eroded are contained and prevented for causing sedimentation in receiving waters.

ORDA will implement proper erosion and sediment control practices when undertaking construction practices at their venues that oftentimes involve construction on steep slopes. These proper practices are set forth in the New York State Standards and Specifications for Erosion and Sediment Control (last updated November 2016). These standards and specifications will be used to develop Stormwater Pollution Prevention Plans (SWPPPs) for construction activities in accordance with NYSDEC's SPDES General Permit for Stormwater Discharge from Construction Activity, GP-0-15-002.

SWPPPS will detail those measures that will be implemented during construction to mitigate potential soil erosion and surface water sedimentation. SWPPP content will include such things as construction sequencing and phasing, temporary and permanent stabilization, structural erosion control practices and vegetative control practices. SWPPPs will include provisions for monitoring, inspections, data collection, and compliance documentation.

Section V.A.2 provides a lengthy and detailed description of mitigation measures that ORDA commonly and successfully employs during ski area construction activities that will be incorporated into pre-construction SWPPP plans and specifications, and installed, monitored and maintained during construction until soils become stabilized.

C. Topography and Slope

Very limited grading is required for new ski trails, trail widening or ski lifts. Trails are laid out to follow natural fall lines. Lift grading is limited to the upper and lower terminals and at the lift tower foundations.

Grading will be required to create the building pad for the groomer garage as well as for sections of the shuttle lane. Significant grading (excavation) is proposed for the enlargement of the snowmaking reservoir.

Impacts associated with grading involve erosion and sediment control (see the previous section) and protection of water resources (see the following section).

D. Water Resources

Identified impacts to surface water are (1) sedimentation of eroded soils, (2) increased stormwater runoff with accompanying loadings (nutrients, dissolved solids, etc.), and (3) exposure of disturbed soils in the snowmaking reservoir expansion area along with separating clean inflow waters from the active construction areas during reservoir excavation.

Those measures that will be implemented to prevent erosion and subsequent sedimentation were described previously in the Soils section.

The new management actions include only two actions that will introduce significant amounts of new impervious surfaces that will increase stormwater runoff. These are the new groomer garage and those portions of the shuttle lane that will be outside of existing parking areas and drives. A Stormwater Management Report has been prepared for these two actions. See UMP Appendix 7.

The Project has been designed in accordance with Chapter 4 of the NYSDEC Stormwater Management Design Manual (SWMDM), and NYSDEC's General Permit GP-0-15-002 for construction activities. Stormwater calculations were performed utilizing widely accepted

engineering methodologies, including TR-55, and the stormwater modeling computer program HydroCAD (version 10.00) produced by HydroCAD Software Solutions, LLC.

Under the watershed's proposed condition, all stormwater from the Project will continue to discharge to the same point as in the existing condition (Analysis Points 1 & 2). The total watershed has generally remained unchanged, as is shown on the drawing "W-2 Proposed Conditions Watershed Map" contained in Appendix 7. To meet NYSDEC requirements (see Section 5.0, NYSDEC Design Criteria in Appendix 7) a bioretention basin and wet swale have been incorporated into the stormwater management design to mitigate the quality and quantity of stormwater runoff discharged from the Project Site.

For the snowmaking reservoir expansion, first the reservoir will be fully drained through its drain valve. Once the reservoir is drained a haul road stabilized outlet will be created in the southeast corner of the reservoir where the remnant of a haul road currently exists. Next, a rip rap stream channel will be constructed to convey water from the main reservoir inlet to the outlet structure. The intent is to isolate and pass through reservoir inflow from the inlet while the reservoir is being excavated. Two 24 foot wide haul roads would then be constructed in order to remove excavated materials from the north and south ends of the reservoir. Excavation work will proceed from west to east. Once excavation is complete, the outlet valve will be closed and the reservoir will be allowed to gradually fill. This gradual filling should allow for the settling of solids that become suspended during pond refilling. Exposed soils will be mostly fine sands that will tend not to stay in suspension as compared to silts or clays.

E. Wetlands

None of the new management actions proposed in the UMP Amendment will impact wetlands. Avoidance of wetland impacts in the areas of the groomer garage, the shuttle lane and the snowmaking reservoir was accomplished by field evaluation for the presence of wetlands and then designing these components to avoid wetlands. Periphery wetlands at the snowmaking reservoir will experience temporary hydrological alteration when the reservoir is emptied. This will not significantly impact wetlands since the effects will be temporary and since these wetlands have persisted when the reservoir has regularly been emptied in the past for inspection and maintenance purposes. Additional information regarding wetland avoidance can be found in UMP Section 6, Alternatives.

F. Climate and Air Quality

No new permanent sources of air emissions are proposed as part of this UMP.

Gore Mountain Ski Center has a current NYSDEC Air Quality Permit for which they are compliant.

Construction activities may result in localized increases in dust levels. However, areas of proposed construction that can take place after this UMP Amendment is adopted are located within the interior of the Intensive Use Areas, so no offsite areas will be affected.

Many ORDA venues exist within the boundaries of State protected lands and the impact of climate change on our environment is recognized. ORDA will be a leader in environmental stewardship with consistent commitment to sustainability, responsible development practices, and continuous communication with DEC, APA, and other regulatory agencies to ensure we are taking the appropriate measures.

G. Vegetation

Tree clearing associated with the new management actions includes 18.1 acres for downhill ski trails (9.4 on the current Intensive Use Area lands and 8.7 acres in the lands that could be added from the VMWF reclassification), 9.2 acres for trail widening, 3.1 acres for ski lifts, 0.8 acres for the groomer garage, and 6.5 acres for the shuttle lane. An area around maintenance and Lifts 9A and 9B previously approved in 1995 is no longer proposed. The 7.3 acres of clearing in this area is no longer proposed.

The numbers of trees proposed to be cut are summarized in the Table below.

Tree Cutting by Location and Community Type

Location	Community	Action(s)	Acreage	Total Trees
Gore Mtn IUA	B (mixed hardwood)	Burnt Ridge Trail	4.2	1,565
		(partial)		
Gore Mtn IUA	E (mixed hardwood)	Burnt Ridge Trail	6.9	4,447
		(partial) + Trails 11A,		
		1N-P		
Gore Mtn IUA	Q (pioneer hardwood)	Twister Widening	1.1	415
Gore Mtn IUA	P (northern hardwood)	Various	15.4	3315
			SUBTOTAL	9,742
Land Reclassif.	E (mixed hardwood)	Lift 12 and Trails 12	10.2	6,574
			TOTAL	16,316

A total of 9,742 trees are proposed to be cut on lands that are currently classified as Intensive Use Area. Approximately 25% of these will be 3-4"dbh and the remainder will be >4" dbh.

The area of Gore Mountain tree cutting is less than 1% of the size of the Intensive Use Area which fits within the capacity of the natural resources to absorb the impact.

There is no tree cutting proposed above 2,800 feet in elevation.

All tree cutting will be done in compliance with the DEC tree cutting policy LF-91-2.

No rare, threatened or endangered plant species will be impacted.

Only areas absolutely necessary for construction of ski trails, ski lifts, and other proposed improvements will be cleared of vegetation. All other areas will be maintained in a natural state.

Erosion control measures will be used on cleared areas with disturbed soils to avoid affecting adjacent vegetation by erosion or siltation. Erosion-control devices to be used will include filter fabric fences and staked straw bale filters.

Upon the completion of clearing of new ski trails and ski lift corridors, they will be seeded with grass mixtures to promote rapid revegetation. Areas disturbed for any other improvements will also be landscaped and revegetated as soon as practicable.

H. Wildlife

The actions proposed in this UMP are expected to have minimal impacts on wildlife. Proposed management actions are spread over the landscape of the existing developed ski trails and lifts. New management actions are proposed at low elevations on the mountain.

Trail widening projects, including the green trails, involve existing trails. This will result in the loss of some currently treed areas along the edge of existing ski trails and move most of the forest edge slightly outward.

Replacing and relocation the Sunway Lift will occur in the immediate vicinity of the existing lift.

The new lift 9B will parallel the existing Lower Sunway trail and much of it will occur in an already cleared area.

Enlarging the snowmaking reservoir will entail converting 1.6 acres of shoreline wooded areas to open water.

The new groomer garage will require some tree removal in an area that has existing work roads on two sides and an existing ski trail on a third side.

The NYSEF building expansion will occur in a grassy area immediately adjacent to the existing building.

The improvements associated with the dedicated shuttle lane take place in and around existing parking areas and the existing access road and will have minimal wildlife habitat impact.

Fisheries

The only proposed management action that involves aquatic resources is the expansion of the snowmaking reservoir. Significant adverse impacts to fisheries resources are not expected to occur as a result of reservoir drawdown for construction of the expansion. There may be some temporary short-term impacts to the fisheries resource within the reservoir proper, but these resources have developed and persisted while the reservoir is regularly drained for inspection and maintenance activities.

See the earlier section entitled Water Resources for a description of how the flow of clean inflow through the reservoir and downstream in Roaring Brook will be maintained in the snowmaking reservoir during the expansion process. The same section describes how the reservoir will be allowed to fill gradually after expansion is complete in order to allow for settling out of suspended solids within the reservoir before the reservoir begins to flow over the spillway.

J. Unique Areas

There are no unique biological areas present.

K. Critical Habitat

No new management actions are proposed to occur above 2,800 feet in elevation. There will no impact to the Adirondack Sub Alpine Forest Bird Conservation Area. Any carryover actions from previous UMPs that require construction activities above 2,800 feet in elevation will not commence prior to August 1 of any year.

L. Visual Resources

The actions proposed in this UMP are expected to have minimal visual impacts. The existing ski area is already visible from some area roadways. Proposed actions are spread across the landscape of the existing developed ski trails and lifts. New management actions are proposed at low elevations on the mountain.

Trail widening projects involve existing trails. For any trails that are currently visible from off site, the visual effect of minor widenings will be essentially imperceptible.

Replacing and relocating the Sunway Lift will occur in the immediate vicinity of the existing lift.

The new lift 9B will be low on the mountain and will parallel the existing Lower Sunway trail. The widening of the green trails will occur at low elevations not visible from off site.

The snowmaking reservoir is not visible from outside the Intensive Use Area.

The new groomer garage will be located in a low elevation wooded area. Although it will be visible on-site, it will not be visible from off site

The NYSEF building is not visible from off site.

The improvements associated with the dedicated shuttle lane take place in and around existing parking areas and the existing access road that are not visible from off site.

The suggested land reclassification itself would not result in any changes to the site.

M. Transportation

The proposed management actions do not include any significant expansion of mountain facilities, such as the addition of a new pod of ski trails, that would result in significant increases in peak hour traffic generation.

N. Community Services

The project primarily involves improvements to existing facilities designed to retain the existing skier base and increase the future number of skiers, hikers and bikers at Gore Mountain. It is anticipated that there will be a minor incremental increase in demand for community services such as fire, police, rescue, solid waste and health care due to the gradual increase in the number of visitors to the mountain. Many of the improvements are designed to build visitation during the off-seasons of spring, summer and fall thereby distributing the potential impacts over a 12 month period. The Ski Center presently makes very little demand on most services and the increase in such demand is anticipated to be small and can be accommodated by the service providers.

The North Creek Health Center was developed and the Warrensburg Health Center was recently expanded to respond to the growing need for services in local communities and businesses in the region. The potential long-term and incremental increase in visitors may increase the demand for medical care slightly and these facilities are capable of meeting any increased demand. The Glens Falls Hospital is also prepared to handle a minor increase in patients to the emergency room.

The extra revenue derived from EMS calls from skiers, hikers and mountain bikers helps offsets the year-round costs and therefore has a positive impact on the people who live and pay taxes in Johnsburg.

O. Local Land Use Plans

The actions in the UMP Amendment are consistent with local planning documents including the 2005 Johnsburg Comprehensive Plan and the 2007 Town of Johnsburg Zoning Law/LLUP that serve to guide community planning. Both documents seek to forge stronger links between the

Gore Mountain Ski Resort, the North Creek Ski Bowl, and the hamlet of North Creek, all of which are goals of Gore Mountain, ORDA and this UMP Amendment.

The UMP Amendment contains specific actions designed to encourage skiers to use both ski areas thereby increasing the overall number of skiers at both Gore Mountain and the Ski Bowl. ORDA has cooperated with North Creek in developing hiking, cross-country ski and mountain bike trails with the goal of connecting Ski Bowl Park and Gore Mountain lands.

The actions on State lands authorized by the UMP Amendment will not have any effects on adjoining or nearby private lands inconsistent with local land use controls such as the Johnsburg Zoning Law and the North Creek Action Plan that serve to guide community planning.

P. Historical and Archaeological Resources

Appendix 3 of the UMP Amendment contains a November 9, 2017 letter from NYS Office of Parks Recreation and Historic Preservation stating that there will be no impacts to archeological or historic resources.

VI. ALTERNATIVES ANALYSIS

Section 6 of the UMP contains an analysis of alternatives to the proposed management actions. Alternatives were examined for trail improvements, lift configurations, parking and circulation improvements, appurtenances (including the snowmaking reservoir) and the no-action alternative. Information is provided as to why the proposed management actions are the preferred alternatives from a ski area operations standpoint, while at the same the proposed actions have avoided significant adverse environmental impacts as compared to other alternatives considered.

Gore Mountain

Proposed Final 2018 Amendment to the 2002 Unit Management Plan and Final Generic Environmental Impact Statement

Executive Summary

Table of Contents

List of Figures List of Tables List of Appendices List of Abbreviations

SECTION I INTRODUCTIO

Α.	Proje	ct Purpose	I-1
B.	Brief	Overview	I-2
C.	Gene	ral Facility Description	I-3
	1.	Location Description	I-3
	2.	Property Description	I-4
D.	Histo	ry of the Ski Area	I-4
E.	Descr	iption of UMP/GEIS Process	I-5
F.	Statu	s of Previous UMP Updates and Amendments	I-7
SECTIO	II NC	INVENTORY OF EXISTING RESOURCES, FACILITIES, SYSTEMS AND	USE
A.	Inven	tory of Natural Resources	II-1
	1.	Physical Resources	II-1
		a. Geology	II-1
		b. Soils	II-1
		c. Topography and Slope	II-3
		d. Water Resources	II-3
		e. Wetlands	II-4
		f. Climate and Air Quality	II-5
	2.	Biological Resources	II-9
		a. Vegetation	II-9
		b. Wildlife	II-9
		c. Fisheries	II-11
		d. Unique Areas	II-11
		e. Critical Habitat	II-11
	3.	Visual Resources	II-12
B.	Huma	an Resources	II-12
	1.	Transportation	II-12
	2.	Community Services	II-13
	3.	Local Land Use Plans	II-14
	4.	Historical and Archaeological Resources	II-16

	1.	Inventory of Constructed Facilities	. II-16
		a. Downhill Ski Slopes	. II-16
		b. Backcountry, Hiking and Mountain Bike Trails	. II-18
		c. Lifts	. II-18
		d. Parking	. II-19
		e. Access Roads	. II-20
		f. Buildings	. II-20
		g. Maintenance Roads	. II-21
		h. Potable Water	. II-21
		i. Snowmaking	. II-21
		j. Grooming Equipment	. II-22
		k. Water Supply for Snowmaking	
		I. Sanitary Wastewater	
		m. Drainage	. II-23
		n. Electrical Distribution	. II-23
		o. Solid Waste Management	. II-23
		p. Equipment Inventory	
	2.	Inventory of Systems	
		a. Management	
		b. Organization	
		c. Operations	
		d. Contractual Arrangements	
D.	Public	Use of the Ski Center	
	1.	Ski Season Use	
	2.	Non-Ski Season Use	. II-28
SECTIO	N III	MANAGEMENT AND POLICY	
A.	Orient	ation and Evolution of Management Philosophy	III-1
B.	Regula	tory Issues	III-2
	1.	New York State Constitution Article 14	III-2
	2.	Adirondack State Land Master Plan	III-5
	3.	2005 Unit Management Plan Amendment	III- 7
	4.	Environmental Conservation Law	III- 7
	5.	Olympic Regional Development Authority Act	III- 7
	6.	DEC - ORDA Memorandum of Understanding and	
		Consolidation Agreement	III-8
C.	Manag	gement Goals and Objectives	III-8
SECTIO		PROPOSED MANAGEMENT ACTIONS AND PROJECTED USE	
A.		sed Management Actions to be Undertaken after Acceptance and	
	Adopti	ion of this UMP	
	1.	General	
	2.	New Downhill Trails and Lifts	IV-1
		a. Non-Beginner Trail Widening	IV-1
		b. Add new triple or quad chair (Lift 9B), from Northwoods Lodge	
		217 da new cripie of quad endir (2111 32), from from the criticolar	

Man-Made Facilities.....II-16

C.

		up Lower Sunway to just past the bend in Lower Sunway	
		c. Widen Sunway and other green trails served by Lift 3	
	3.	Enlarge snowmaking reservoir	IV-2
	4.	Buildings	IV-3
		a. Expand NYSEF building	IV-3
		b. Reconfigure 1995 UMP-approved maintenance area to locate	
		groomer garage and fueling adjacent to existing ski trail	IV-4
	5.	Bike Trail - Single track bike loop for Town trail at top of Little Go	e IV-4
	6.	Vehicle Access-modify 1995 UMP-approved shuttle lane separate	d from
		and independent of main traffic circulation route and parking	IV-5
	7.	Land reclassification involving Gore Mountain Intensive Use Area	,
		Vanderwhacker Mountain Wild Forest and Siamese Ponds Wilder	ness Area
		which could allow the historic Rabbit Pond trail to be reclaimed a	nd used winter
		and summer	IV-5
	8.	Rabbit Pond Trail Activities	IV-10
В.	Proje	cted Use	IV-10
C.	Actio	ns Approved in Previous UMP/EIS which are Part of the	
	Fore	going 5-year Plan	IV-10
D.	Prior	itization of Management Actions	IV-11
SECT	ION V	POTENTIAL IMPACTS AND MITIGATION MEASURES	
A.	Physi	cal Resources	V-1
	1.	Geology	V-1
	2.	Soils	V-3
	3.	Topography and Slope	V-9
	4.	Water Resources	V-10
	5.	Wetlands	\/ ₋ 12
	6.	Wettanus	V-12
В.	٥.	Climate and Air Quality	
			V-12
		Climate and Air Quality	V-12 V-13
	Biolo	Climate and Air Qualitygical Resources	V-12 V-13 V-13
	Biolo 1.	Climate and Air Qualitygical Resources Vegetation	V-12 V-13 V-13 V-15
	Biolo 1. 2.	Climate and Air Qualitygical ResourcesVegetationWildlife	V-12 V-13 V-13 V-15
	Biolo 1. 2. 3.	Climate and Air Quality	V-12 V-13 V-13 V-15 V-15
C.	Biolo 1. 2. 3. 4. 5.	Climate and Air Quality	V-12 V-13 V-15 V-15 V-16
C.	Biolo 1. 2. 3. 4. 5.	Climate and Air Quality gical Resources Vegetation. Wildlife Fisheries Unique Areas Critical Habitat	V-12 V-13 V-15 V-15 V-16 V-16
C.	Biolo 1. 2. 3. 4. 5.	Climate and Air Quality	V-12 V-13 V-15 V-15 V-16 V-16 V-16
C.	Biolo 1. 2. 3. 4. 5. Human	Climate and Air Quality	V-12V-13V-15V-15V-16V-16V-16V-16
C.	Biolo 1. 2. 3. 4. 5. Hum: 1. 2.	Climate and Air Quality gical Resources Vegetation Wildlife Fisheries Unique Areas Critical Habitat an Resources Visual Resources Transportation	V-12V-13V-15V-16V-16V-16V-16V-17

SECTION VI	ALTERNATIVES
A. Altern	ative Trail ImprovementsVI-1
B. Altern	ative Lift ConfigurationsVI-1
C. Altern	ative Parking/Circulation ImprovementsVI-2
D. Altern	ative AppurtenancesVI-2
E. The No	o-Action AlternativeVI-3
SECTION VII	SUMMARY OF UNAVOIDABLE ADVERSE ENVIRONMENTAL IMPACTS
SECTION VIII	IRREVERSIBLE AND IRRETRIEVABLE COMMITMENTS OF RESOURCES
SECTION IX	GROWTH INDUCING, SECONDARY AND CUMULATIVE IMPACTS
SECTION X	EFFECTS ON THE USE AND CONSERVATION OF ENERGY
List of Figures	
Figure ES-1	2018 Master Plan – Approved and Proposed Actions (South)
Figure ES-2	2018 Master Plan – Approved and Proposed Actions (North)
Figure 1	2018 New Management Actions (South)
Figure 2	2018 New Management Actions (North)
Figure 3	Regional Location Map
Figure 4	Site Location Map
Figure 5	Intensive Use Area Boundary
Figure 6	Surrounding Land Use Classification
Figure 7	Existing Conditions (South)
Figure 8	Existing Conditions (North)
Figure 9	Existing and Approved Hiking and Biking Trails (South)
Figure 10	Existing and Approved Hiking and Biking Trails (North)
Figure 11	Previously Approved Actions, Not Yet Constructed (South)
Figure 12	Previously Approved Actions, Not Yet Constructed (North)
Figure 13	2018 Master Plan – Approved and Proposed Actions (South)
Figure 14	2018 Master Plan – Approved and Proposed Actions (Base Area)
Figure 15	2018 Master Plan – Approved and Proposed Actions (North)
Figure 16	Soils Map
Figure 17	Topography
Figure 18	Slope Map
Figure 19	Surface Water and Wetland Resources
Figure 20	Vegetation Map
Figure 21	Potential Bicknell's Thrush Habitat
Figure 22	Gore Mountain Ski Trail Inventory
Figure 23	Organizational Structure Gore Mountain Ski Area
Figure 24	Snowmaking Reservoir Existing Conditions
Figure 25	Proposed Snowmaking Reservoir Expansion
Figure 26	Shuttle Lane Plan
Figure 27	Land Reclassification Map
Figure 27A	North Creek Ski Map 1940's

Figure 27B	1958 USGS Map Gore Mountain Area
Figure 27C	Ski Bowl Trail Network
Figure 27D	Rabbit Pond Trail Relocation Area
Figure 28	Soils Map and Management Actions
Figure 29	Topography and Management Actions
Figure 30	Surface Water, Wetland Resources, and Proposed Actions
Figure 31	Snowmaking Reservoir Construction Sequencing
Figure 32	Vegetation and Management Actions
Figure 33	Potential Bicknell's Thrush Habitat and Management Actions
Figure 34	Snowmaking Reservoir Expansion Alternative 1
Figure 35	Snowmaking Reservoir Expansion Alternative 2
Figure 36	Snowmaking Reservoir Expansion Alternative 3
Figure 37	Snowmaking Reservoir Expansion Alternative 4
Figure 38	Snowmaking Reservoir Expansion Alternative 5
Figure 39	Snowmaking Reservoir Expansion Alternative 6
List of Tables	
Table 1	2018 UMP Amendment and Status of 2005 UMP Actions
Table 1A	Ski Trails at Gore Mountain
Table 2	Town of Johnsburg Land Classification
Table 3	Gore Mountain Lifts
Table 4	Snowmaking Utilization
Table 5	Winter Public Use of Gore Mountain Ski Area
Table 6	Non-winter Public Use of Gore Mountain Ski Area
Table 7	Tree Cutting by Location and Community Type
List of Append	dices
Appendix 1	SEQRA Full Environmental Assessment Form Parts 1, 2 and 3
Appendix 2	ORDA/NYSDEC Consolidation Agreement
Appendix 3	Correspondence
Appendix 4	Adirondack Sub-alpine Forest Bird Conservation Area Description
Appendix 5	Trail Inventory and Analysis
Appendix 6	Vanderwhacker Mountain Wild Forest 2005 UMP Excerpts
Appendix 7	Stormwater Management Report
Appendix 8	Tree Counts
Appendix 9	Gore Mountain Sustainability Analysis
Appendix 10	DGEIS Public Hearing Transcript
Appendix 11	DGEIS Written Public Comments
Appendix 12	DGEIS Comments and Responses to Comments
Appendix 13	Errata – Narrative Summary of Changes Made to the DGEIS in the FGEIS
List of Abbrev	riations
APA – Adirono	dack Park Agency

APSLMP – Adirondack Park State Land Master Plan

DGEIS – Draft Generic Environmental Impact Statement

FEAF – Full Environmental Assessment Form

FGEIS – Final Generic Environmental Impact Statement

LLUP – Locally Approved Land Use Program
Mgal – million gallons
NYSDEC – NYS Department of Environmental Conservation
ORDA _ NYS Olympic Regional Development Authority
SEQRA – (NY) State Environmental Quality Review Act
UMP – Unit Management Plan
VMWF – Vanderwhacker Mountain Wild Forest

A. Project Purpose

The Olympic Regional Development Authority (ORDA), in conjunction with the New York State Department of Environmental Conservation (NYSDEC), is amending the 2002 Unit Management Plan (UMP) and Generic Environmental Impact Statement (GEIS) for Gore Mountain Ski Center in North Creek, Town of Johnsburg, Warren County, New York. This document serves as an amendment to that 2002 UMP. As an amendment to the 2002 UMP, this document will discuss changes to actions which have been previously approved, will include any new information relating to changes such that it satisfies State Environmental Quality Review Act (SEQRA) requirements, and will refer to the previously accepted and approved EIS for sections which have not changed as a result of this UMP Amendment. The document is organized so that it follows the sequence of the 2002 UMP.

ORDA's goals for Gore Mountain will be advanced through the actions contained in this UMP Amendment. Included in these goals are the following:

- modernize facilities in order to enhance the guest experience, improve skier safety, and increase local and regional economic benefits, while maintaining environmental quality,
- develop new summer and fall uses of the Ski Center to provide greater year-round use
 of the facility by the public, consistent with Article 14 and the APSLMP,
- work closely with the North Creek community and Town of Johnsburg to provide
 information to visitors about the area and to cooperate in the establishment of a shuttle
 link between the Ski Center and North Creek and a physical ski link to Ski Bowl Park in
 order that public use may better help promote the economy of the area,
- improve environmental performance in all aspects of its operations and managing the area to allow for continued enjoyment by future generations,
- seek to increase the capacity of the ski area in concert with other modernization objectives in order to provide a higher quality skiing experience,
- improve infrastructure reliability in order to reduce the high frequency of breakdown, excessive staffing requirements and consequent financial drain,
- seek to reduce its operations and maintenance costs by replacing outdated and aged equipment,

- improve skier safety and enjoyment by widening certain trails and improving certain trail intersections, and
- improve trail selection and create a better balance among trails in order to appeal to a greater cross-section of the skiing market by increasing the number of trails for the beginning and advanced skier.

B. Brief Overview

The following lists the New Management Actions that are the subject of this UMP Amendment and that can be undertaken after the UMP Amendment is adopted. **Figures** 1 and 2, 2018 UMP New Management Actions (North and South), show the locations of the actions.

Trail Construction and Trail Widening

- Construct a new trail at Burnt Ridge (11-0) that connects to the Base Lodge via the lower portion of Echo
- Construct a new trail adjacent to the Ski Bowl to replace the existing Half 'N Half glade.
- Widen the bottom of Echo as it turns toward the base area
- Widen some sections of Twister
- Widen Sunway and other green trails served by Lift 3
- Reestablish alpine skiing on a portion of Rabbit Pond Trail (can only occur after land reclassification takes place)

Lifts

 Add a new triple or quad chair (Lift 9B) from Northwoods Lodge up Lower Sunway to just past the bend in Lower Sunway

Vehicular Access and Parking


 Modify the 1995-approved shuttle lane separated from and independent of main traffic route and circulation route and parking

Buildings

- Expand the NYSEF building
- Reconfigure the 1995-approved maintenance complex to locate a groomer garage and fueling station adjacent to Sunway trail

Snowmaking

- Enlarge the snowmaking reservoir
- Install new 24 inch gravity water line from the snowmaking reservoir to the pump house








Olympic Regional **Development Authority** 2634 Main Street Lake Placid, New York 12946



Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement







Figure 1



Gore Mountain: 2018 Unit Management Plan Amendment &

Final Generic Environmental Impact Statement

Olympic Regional

2634 Main Street Lake Placid, New York 12946

Development Authority

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law.

© the LA Group 2017

Figure 2

Mountain Biking

Construct a single track bike trail loop for the Town trail at the top of Little Gore

Hiking

Develop a hiking center at the Northwoods Lodge

Land Reclassification (Requires Separate APA Approval)


 Request land reclassification from Wild Forest to Intensive Use and From Intensive Use to Wilderness which could allow the historic Rabbit Pond Trail to be reclaimed and used winter and summer if authorized in a subsequent UMP.


(Note: The Adirondack Park Agency cannot find that a UMP Amendment proposing management actions on lands to be reclassified conforms to the APSLMP before the land is reclassified. First, the Agency must receive a request to reclassify, accompanied by a UMP for the proposed Intensive Use lands. The Agency must follow SEQRA regulations regarding public notice and comment and must hold hearings inside and outside the Adirondack Park on the request to reclassify, pursuant to the APSLMP. After notice, comment and hearings, the reclassification proposals would be presented to the Agency for a recommendation to the Governor for approval of the classification. The process culminates in the Governor's action on that recommendation. This UMP Amendment does not assume that a reclassification request will be approved and does not authorize any actions on lands to be reclassified, based on a proposed future classification. The actual request for reclassification and a UMP Amendment for those actions on the lands proposed for reclassification would be presented separately from this UMP Amendment. Discussion of actions on those lands in this UMP is conceptual only, and those actions cannot be authorized by this UMP Amendment.)


C. General Facility Description

1. Location Description

Gore Mountain Ski Center is located off NY Route 28, approximately two miles south of the Hamlet of North Creek, and 15 miles northwest of Warrensburg, in the Town of Johnsburg, Warren County, New York. A paved access road approximately one and one-half miles in length leads from County Route 29, Peaceful Valley Road, to the base lodge and parking areas. See Figure 3, "Regional Location Map," and Figure 4, "Site Location Map," for site location and regional travel routes. Gore Mountain Ski Center is State Land classified as "Intensive Use" under the APSLMP. The APSLMP identifies the specific boundaries of the ski center. The ski area's holdings encompass slopes of two mountains, Gore Mountain and Pete Gay Mountain, with approximately 3,755 acres of land. See Figure 5, "Intensive Use Area Boundary," for the delineation of the area boundaries.







Adjoining lands are a mix of State lands and private lands. Gore Mountain Ski Center is bordered to the north by a portion of the Vanderwhacker Mountain Wild Forest. The Siamese Ponds Wilderness Area adjoins the Ski Center to the west.

Private land borders the ski area lands to the north, south, east and west. According to the Adirondack Park Land Use and Development Plan Map, lands to the north and west are classified as "Resource Management" and "Industrial," to the east as "Low Intensity Use," "Hamlet," and "Moderate Intensity Use," and to the south as "Moderate Intensity Use" and "Rural Use," as shown on **Figure** 6, "Surrounding Land Use Classification."

The industrial use lands are under the ownership of the Barton Mines Corporation. The corporation has been in operation, mining garnet for use as coated abrasives, since 1878. Operations by Barton Mines at Gore Mountain were ceased in the late 1970's, and the corporation is now actively mining at Ruby Mountain.


2. Property Description


The facility is classified as an "Intensive Use Area" under the Adirondack Park State Land Master Plan. Gore Mountain targets winter sports enthusiasts for downhill and cross-country skiing. It includes 27.4 miles of constructed alpine ski trails, 14.6 miles of Nordic ski trails, 11 ski lifts, a ski school program, a ski racing program, three lodges, a nursery program and a cocktail lounge/restaurant. There are eight parking lots for cars and buses. See **Figures** 7 and 8, Existing Conditions (South and North), and **Figures** 9 and 10, Existing and Approved Hiking and Biking Trails (South and North)

The summer and fall season program centers around hiking, mountain biking (including mountain bike racing), educational interpretive opportunities and nature-oriented activities. Gore Mountain hosts an annual fall festival. The gondola is operated as a tourist attraction year-round. Hunting, trapping and fishing are prohibited at the Gore Mountain Ski Center. Only non-consumptive use of wildlife resources is permitted on Ski Center lands. Current annual non-winter usage was approximately 8,500 people in 2016-2017 and has been as high as almost 13,000 people within the last 5 years.

D. History of the Ski Area

Gore Mountain Ski Center was built in the early 1960's and was first opened to the public in 1964. Early management was under the direction of the Bureau of Winter Recreation, Conservation Department (now known as the Department of Environmental Conservation). On April 1, 1984, management was delegated to the Olympic Regional Development Authority (ORDA) through an agreement with DEC, authorized by Chapter 99 of the Laws of 1984 (Article 8, Title 28, Section 2614, Public Authorities Law).










Olympic Regional **Development Authority** 2634 Main Street Lake Placid, New York 12946




Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement



Scale:	1"=1000
Design:	MJT
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037

Figure 7







Olympic Regional **Development Authority** 2634 Main Street Lake Placid, New York 12946





Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

(North)



Date:	Nov. 6, 201
Scale:	1"=1000
Design:	MJT
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037










Olympic Regional **Development Authority**

2634 Main Street Lake Placid, New York 12946



Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

Existing and Approved, Hiking and Biking Trails (North)



Design:	MJT
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037

This agreement transferred to ORDA the use, operation, maintenance and management of the ski area. DEC remains the statutory custodian of the state-owned ski area. Under the agreement, ORDA is to maintain the facility subject to DEC inspections; make capital improvements with DEC'S prior written approval; establish a sinking fund for capital improvements; continue the level of prior public recreation; comply with specified prior agreements; and cooperate with DEC in completion of a Unit Management Plan for the ski area.

In 1991 DEC and ORDA entered into a Memorandum of Understanding superseding a 1984 memorandum between the parties, establishing methods and procedures by which managerial requirements contained in the underlying DEC/ORDA management agreements are to be complied with, and setting forth requirements for the operation of ORDA facilities and detailing procedures on how Unit Management Plans for each of the ORDA facilities are to be implemented. In 2013 ORDA and DEC executed a Consolidation Agreement that incorporated the 1991 MOU. A copy of the Consolidation Agreement is in **Appendix** 2.

E. Description of UMP/GEIS Process

Section 816 of the Adirondack Park Agency Act directs the DEC to develop, in consultation with the Adirondack Park Agency (APA), Unit Management Plans (UMPs) for each unit of land under its jurisdiction classified in the SLMP. Pursuant to its enabling law and agreement with the DEC for the management of Gore Mountain, ORDA works with the DEC, in the consultation of the APA, to update and amend the Gore Mountain UMP. The original UMP for Gore Mountain was prepared in 1987. UMP Amendments for Gore Mountain were prepared 1995, 2002, and 2005.

Specific requirements pertaining to the development of UMPs for ORDA venues was specified in the March 9, 1991 DEC/ORDA MOU and were then expounded upon in the November 2013 DEC/ORDA Consolidation Agreement. Section 2 of the Consolidation Agreement (copy in **Appendix** 2) provides specifics regarding the preparation of UMPs for ORDA venues, including the following topics:

- UMP Content,
- SLMP Compliance,
- Consultation with NYSDEC Prior to and During UMP Preparation,
- Procedural Steps for preparation of Preliminary Draft UMPs, Public Review Draft UMPs, and Final UMP's,
- Consultation with APA,
- APA SLMP Consistency Review,
- APA Resolution on APSLMP Conformance, and
- Commissioner Approval of UMPs

The Generic Environmental Impact Statement (GEIS) included in this document in prepared in accordance with the New York State Environmental Quality Review Act (SEQRA, 6 NYCRR Part 617 and Implementing Regulations). The March 9, 1991 DEC/ORDA MOU, which is now incorporated as part of the November 2013 DEC/ORDA Consolidation Agreement states, "ORDA will normally serve as lead agency for State Environmental Quality Review (SEQR) and the Department and the Agency will participate in the SEQRA process as involved agencies."

ORDA, as lead agency, completed a SEQRA Full Environmental Assessment Form (FEAF) Parts 1, 2, and 3 (See **Appendix** 1). Based on the analysis in Part 3 of the FEAF, ORDA determined that the Project may result in one or more significant adverse impacts on the environment and that an Environmental Impact Statement (EIS) must be prepared to further assess the impacts and possible mitigation and to explore alternatives to avoid or reduce these impacts.

The SEQRA aspects of this document are presented as a Generic Environmental Impact Statement (GEIS). A Generic EIS may be used to assess the environmental effects of a sequence of actions contemplated by a single agency or an entire program or plan having wide application (6NYCRR 617.10(a)(2) and (4)). They differ from a site specific EIS in that it applies to a group of common and related activities which have similar or related impacts. It is the intent of this GEIS to provide sufficient, site-specific information for all aspects of the UMP. In conformance with SEQRA, these related actions are being considered in this FGEIS. No additional SEQRA analyses are anticipated to be required for any new management action in this UMP, provided that such actions are carried out in accordance with the recommendations of this document. Any conceptual actions will require additional review under SEQRA should they be pursued in the future.

A preliminary version of the UMP Draft Amendment/DGEIS was provided to NYSDEC and to the APA for their review on December 8, 2017. Comments from these agencies were received by ORDA, and ORDA revised the preliminary document accordingly. ORDA then declared the Public Review UMP Draft Amendment/DGEIS to be complete for public review on January 3, 2018. Notice of ORDA's acceptance of the EIS, establishment of the public comment period with a public hearing, and directions for accessing this document was published in the January 10, 2018 issue of the Environmental Notice Bulletin. The Public Draft of this document was presented to the NYS APA at their January 11, 2018 Agency meeting.

The 2018 UMP Draft Amendment/DGEIS was open for public comment until February 9, 2018 including a SEQRA public hearing that was held at 7:00 PM on January 24, 2018 at the Gore Mountain Base Lodge. Following the completion of the public comment period, ORDA, in consultation with NYSDEC and in cooperation with the APA, prepared this FGEIS in accordance with the requirements of SEQRA. Responses were prepared to comments received at the public hearing and to written comments submitted during the public comment period. A

transcript of the public hearing, copies of written comments and responses to comments are included in this FGEIS. Also included in this FGEIS is an errata section that summarizes the changes that were made to the DGEIS when preparing this FGEIS.

This proposed final UMP Amendment/FGEIS is available online at http://www.dec.ny.gov/lands/41866.html. Hard copies of the document are available at ORDA offices in Lake Placid at and Johnsburg Town Hall. CD copies are available upon request.

This proposed final UMP Amendment/FGEIS will be presented to the APA at their March 8, 2018 meeting for a first reading.

F. Status of Previous UMP Updates and Amendments


See **Figure** 7, Existing Conditions (South) and **Figure** 8, Existing Conditions (North). These are the facilities that currently exist on the Gore Mountain Intensive Use Area.


There are a number of management actions that were approved for Gore Mountain in earlier UMPs that have yet to be constructed. These actions remain in effect as approved and continue to be proposed. See **Figure 11**, Previously Approved Actions, Not Yet Constructed (South) and **Figure 12**, Previously Approved Actions, Not Yet Constructed (North).

Figures 1 and 2 referenced previously show the new management actions that are proposed in this 2018 UMP Amendment.

Together, the previously approved, but not yet constructed actions, combined with the 2018 new management actions, constitute the proposed Master Plan for Gore Mountain. Master Plans for the southern part of the Intensive Use Area, the base area, and the northern part of the Intensive Use Area are shown on **Figures** 13, 14 and 15 respectively.

Table 1 below indicates which management actions approved in previous UMPs are completed, partially completed, pending construction, modified in this 2018 UMP Amendment, or are abandoned altogether.







© the LA Group 2017



Olympic Regional **Development Authority**


2634 Main Street Lake Placid, New York 12946





Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement



Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037







Final Generic Environmental Impact Statement

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law.

© the LA Group 2017

Development Authority

2634 Main Street Lake Placid, New York 12946

Table 1 2018 UMP Amendment and Status of 2005 UMP Actions (with carry over 1987, 1995, and 2002) Actions

			1					
Item#	Facility		Management Action / Improvements	Current Stat	us			
1	Ski Trails							
	Trail # (By Pod)	Trail Name						
			Build on previously approved widening efforts and widen portions less than 120' wide to 120' width to					
	1F	Twister	achieve consistent width along entire trail.	New Manageme	ent Action, 201	8 UMP amendm	ent	
			Widen bottom to 120' to accommodate new trail					
-	11A, 1N-P	Echo	connection and existing ski racing on Echo Widen and re-grade bottom portion to 120' width	New Managem	ent Action, 201	8 UMP amendm	ent	
			for use as primary beginner trail accessed by new Lift	:				
	1C (1C-1A), 3A	Sunway	9В	New Manageme	ent Action, 201	8 UMP amendm	ent	
			Widen to 120' width and grade for increased ski					
	3B	Ward Hill	ability / safety for beginner-intermediate skier	New Manageme	ent Action, 201	8 UMP amendm	ent	
	3C-UP	Cutoff	Widen to avg. 100' width and grade for increased ski ability / safety for beginner-intermediate skier	New Managem	ant Action 201	8 UMP amendm	ent	
	5C 0F	Cuton	Sales of Service Seguiner-Intermediate Skiel	ivew ividilagelli	ACOUI, 201	o olvir amenum	CIIC	
			Widen to avg. 100' width and grade for increased					
	3C-LOW	Little Dipper	ski ability / safety for beginner-intermediate skier Widen to 120' width to alleviate congestion at	New Manageme	ent Action, 201	8 UMP amendm	ent	
			intersection at Sunway and accommodate new Lift 3					
	31	Otter Slide	terminal location.	New Manageme	ent Action, 201	8 UMP amendm	ent	
	9A		Abandon clearing proposed in 1995 but never undertaken	New Managem	ant Action 201	8 UMP amendm	ent	
	3A		New downhill trail 11-0 on Burnt Ridge, as additiona		ent Action, 201	o Olvir amenum	ent	
			intermediate trail connection from Burnt Ridge to					
	11-0	New Trail	Base Area	New Manageme	ent Action, 201	8 UMP amendm	ent	
			New Downhill Trail from the intersection of Peaceful Valley and The Oak Ridge Trail connecting to					
	120	New Trail	Moxham, replacing the Half 'N Half Glade.	New Manageme	ent Action, 201	8 UMP amendm	ent	
			N D 11117 115 1 5 1 115 12					
	12L	New Trail	New Downhill Trail from top of New Lift 12, connecting to Ski Bowl Trails and Burnt Ridge	Ski Bowl				
			New Downhill Trail from top of New Lift 12,					
	12M	New Trail	connecting to Ski Bowl Trails	Ski Bowl				
			New Downhill Trail from top of New Lift 12,					
	12I-A	New Trail	providing access to Rabbit Pond area, Ski Bowl Trails	Ski Bowl				
				Action	Action	Partially	Annuariad Nat	Action
	Previously Approved Act	tion - Ski Trail Construction		Action Approved In	Action Completed	Completed (% complete)	Approved, Not Yet Started	Action Abandoned
	1N-O			1995	·	, , ,	Х	
-	1N-P	Echo (Lower)		1995	Х		v	
-	2N-L 6N-O			1995 1995			X	
	7N-P			1995			Х	
-	9A Upper			1995			X	
	9B 10B-UPPER			1995 1995			Х	X (05)
	10D			1995				X (05)
	10F			1995			Х	V (05)
-	10G Lower 10H	+		1995 1995			Х	X (05)
	11A	Echo (Upper)		2002	Х			
	11B-UPPER	Hedges		2002	Х			
-	11B Lower 11C	+		2002 2002			Х	X (05)
	11D			2002				X (05)
	11E			2002				X (05)
-	11F 11G			2002 2002			Х	X (05)
	11M			2002			X	
	11L			2005			Х	
-	11I 11J	+		2005 2005			X	
	11K	Sagamore		2005	Х		^	
		•	•					

				1				
tem#	Facility		Management Action / Improvements	Current Stat	us			
	11N	Eagle's Nest Crossover		2005	Х			
	12A	Peaceful Valley (Lower)		2005	X			
	12B	The Oak Ridge Trail		2002	X			
	12C 12D	Peaceful Valley (Upper) Moxham		2005 2002	X			
	12E	IVIOXITATII		2002	^		Х	
	12F	46ER		2005	Х		^	
	12G Upper	IOEN		2005	,		х	
	12G Lower	Hudson		2005	х			
	12H			2005			Х	
	121			2005			Х	
	12J			2005			Х	
	12K			2002				X (05)
	12L			2002				X (05)
	12M			2002				X (05)
	15A			2002				X (05)
	C5			1995	.,			X (05)
	C7	Ruby Run		2005	Х			
	 			1		Partially	1	-
				Action	Action	Completed	Approved, Not	Action
	Previously Approved A	ction - Ski Trail Widening		Approved In	Completed	(% complete)	Yet Started	Abandon
	1H	1A		1995	- Jonephotou	(/o co.iipicte)	X	
	1E	2B		2002		1	X	
	3F, 3H	3B		1995,2002		1	X	
	9A Lower	Bear Cub Run		1995		Х		X(2018)
	7A	Chatiemac		1987		5		· · · · · · ·
	6B-UP, 2K	Cloud		1987,1995		50		
	7B	Hawkeye		1987,2002			Х	
	7F	Headwaters		1987,2002			Х	
	3G	Jamboree		2002			X	
	3C-LOW	Little Dipper		1995,2002			Х	
	6G	Lower Darby		1995			Х	
	6F	Lower Steilhang		1995			Х	
	3A	Lower Sunway		87,95,02			X	
	2D	North Star		1995			X	
	6E, 7N-O	Open Pit		2002		-	Х	
	2E UP, LOW 2C	Pete Gay Powder Pass		1995,2002 1995		5	Х	
	1B	Quicksilver		1995			X	
	1C (1A-1D), 1D	Showcase		1987,2002		5	^	
	1K	Showoff		1995		3	х	
	2B, 2I	Sleeping Bear		1987			X	
	1C (1C-1A), 1A	Sunway		87,95,02		15		
	2A	Tahawus		1995		-	Х	
	C1	Tannery		1995	Х			
	1C (FROM 1NR)	The Arena		2002			Х	
	7H	The Glen		1987			Х	
	2F (2J-2E)	The Loop		2002			Х	
	3E	Twin Fawns		2002			Х	
	1F	Twister		1995	Х			
	10C-UP	Uncas		2002			X	
	6D	Upper Darby		1995		-	X	ļ
	1G	Upper Sleighride		1995		-	X	
	6C	Upper Steilhang		1987			X	
	2F (TO 2J) 1N-Q-1NR, 1N-R	Upper Wood In Wildair		2002 2002		-	X	
	6J	Wood Lot North		1995			X X	
	6B-LOW(FROM 6K)	Wood Lot North		1995			X	
	CO LOVY (I NOIVI ON)	.vood Lot Joutil		1307			^	1
				1				
2	Ski Lifts							
			Add new triple or quad chair (Lift 9B) from					
			Northwoods Lodge up Lower Sunway to just past the					
	Lift 9b	New Lift	bend in Lower Sunway.	New Manageme	ent Action 201	8 UMP amendm	ent	
						. J unichalli		
			Replace, re-align and extend Lift 12 to location north of existing top terminal, to enhance access to Rabbit	Ski Boud				
	Lift 12	Hudson Chair	Pond area for both Winter and Summer recreation	SKI BUWI				
			rond area for both whiter and Summer recreation					
					1	T	1	
	1	l		-		B	 	-
								1
				A a4! a	A salie	Partially	Annrauad M.	A1-
	Previously Approved A	ction - Lift Installation		Action Approved In	Action Completed	Completed (% complete)	Approved, Not Yet Started	Action Abandon

4	F 1114		Name and Astion / Income and					
Item#	Facility		Management Action / Improvements	Current Stat	us			
	Lift 3 (Re-Locate)	Sunway Chair		2002			X	
	Lift 4 (Relocate)	J-Bar		2002			X	
	Lift 6 (Extend)	High Peaks Chair		2002			X	
	Lift 9b	Beginner Triple		2002			X	
	Lift 9c	Surface-Magic Carpet		2002	Х			
	Lift 9d	Surface-Magic Carpet		2002	Х			
	Lift 11	Burnt Ridge Quad		2005	X			
	Lift 12	Hudson Chair	Ski Bowl	2002	Х			
	Lift 13	Village Chair	Ski Bowl	2002	Х			
	Lift 14	Base to Base Gondola	IUA and Ski Bowl	2005			Х	
						l		
3	Buildings							
	NYSEF Building		Expand NYSEF building	New Manageme	ent Action, 201	8 UMP amendm	ent	
	Base Lodge		Incorporate Hiking center into Main Lodge			8 UMP amendm		
			,		,			
						Partially		
				Action	Action	Completed	Approved, Not	Action
	Previously Approved Acti	ons		Approved In	Completed	(% complete)	Yet Started	Abandoned
	Freviously Approved Activ	ons		Approved iii	Completed	(% complete)	recotanteu	Abandoneu
	D	-1-d/5	Demonstration (Supersiste	4005		F50/		
		s Lodge (Former Gondola Building)		1995		55%		
	Saddle Lodge	ļ	Renovation/Expansion/Ski Patrol	1995	Х			
	Bear Mtn. Lodge	1	Build Lodge	1995		ļ	Х	
			Wastewater Line to Saddle Lodge	1995			X	
	NYSEF Building		Addition/Expansion	2005	Х			
	Summit Lodge		Build Summit Lodge	1987		Х		
	Sand Shed		Build Sand Shed in existing parking lot	2002				X (2005)
4	Snowmaking							
			Increase reservoir capacity to improve snowmaking					
	North Creek Snowmaking Re	eservoir	efficiency and operational flexibility.	New Manageme	ent Action 201	8 UMP amendm	ent	
	North Creek Showmaking N	eservon	enciency and operational nexibility.	ivew ividilageiiie	ent Action, 201	o Olvir amenum	ent	
				Previously Appr	oved Action. 4	,400 GPM		
	Overall Snowmaking Capaci	ty	Permit withdrawal Capacity	completed, 6,800 GPM Approved				
	Distribution Lines		Install Distribution Lines on New Trails	Previously Appr	oved Action, o	ngoing		
	Diesel Air Compressors		Create area for Diesel Air compressors with Fuel	Previously Appr	oved Action, pa	artially complete	ed.	
_								
5	Maintenance Facility							
			Re-Configure approved maintenance complex to					
			locate new groomer garage and fueling station					
			adjacent to existing ski trail, to improve efficiency					
	Groomer Garage		and functionality of operations	New Manageme	ant Action 201	RIIND		
	Groomer Garage		and functionality of operations	Approved in 199				
	Conoral Buildings		Delegate Buildings, renovate and garages					
	General Buildings		Relocate Buildings, renovate, add garages			gement Action)		
	Fuel		Install additional fuel storage	Approved in 199	55, partially col	mpietea		
6	Parking / Circulation							
	0,			1				
			Update 1995-approved shuttle lane to conform to					
			current conditions, and provide service separated					
	Shuttle Lane		from and independent of primary traffic circulation				ent	
	General Parking		Construct New Lots	Action approved	d in 1995, 50%	completed		
	Drop Off Area		Reconfigure entry lane and drop off area	Action approved				
					_			_
	Shuttle Lane		Build independent Shuttle Lane	Action approve	d in 1905 not	et constructed (Reconfiguration	is 2018 Action
	Bus Parking Lot	1	Built new Bus Lot	Conceptual Acti		et constructed (necomiguration	3 2010 ACTION)
	Dus Faiking LUL	+	Duilt HEW DUS LUL	Conceptual ACTI	011 111 2003	1		
	Pookoo:		<u> </u>	1				
7	Backcountry Trail							
	Network		I=	Τ.				1
	Hiking and X/C Ski Trails	1	Trail Construction	Approved in 199	5, partially cor	mpleted.		
		<u> </u>				<u> </u>		
8	Miscellaneous							
•	Wildcellalleous							
			Suggested land reclassification involving Gore					
			Mountain IUA, Vanderwhacker Mtn. WF and					
			Siamese Ponds Wilderness Area which could allow					
	Land Use Reclassification		the historic Rabbit Pond trail to be reclaimed and					
			used winter and summer	New Manageme	ent Action. 201	8 UMP amendm	ent	
	Interpretive Systems		Interpretive Systems installed	Approved, 25%			-	
	Sand Pit Reclamation		Re-claim sand pit area	Approved, parti		İ		
		<u> </u>	· · · · · · · · · · · · · · · · ·	FF. C. Ca, parti	,pieceu	 		
		ı		<u> </u>	L	L		l

Table 1A that follows is derived from Table 1 above, and provides the amounts of ski trails at Gore Mountain that (1) currently exist, (2) were previously approved but have not yet been constructed, and (3) are proposed in this UMP Amendment. Locations of trails are shown on **Figures** 13 and 15. Detailed information on the inventory of Gore Mountain ski trails in contained in Appendix 5.

Table 1A Ski Trails at Gore Mountain

Trail Length Data			
Trail Pod #	Trail Name	Trail Length on Intensive Use Area Lands	Trail Length on Town Lands
Existing Trails			
1H	1A	825	0
1E	2B	357	0
3F	3B	1952	0
12F	46ER	0	3260
9A Lower	Bear Cub Run	608	0
WORKRD	Cedar's Traverse	3514	0
7A	Chatiemac	3119	0
6B-UP, 2K	Cloud	3486	0
N/A	Crystal	157	0
3C-UP	Cutoff	922	0
7E	Dell	344	0
7N-Q(b)	Double Barrel (Looker's Right)	780	0
11N	Eagle's Nest Crossover	4082	0
11A, 1N-P	Echo	5735	0
C4	Farview	965	0
10G-Upper, C6	Foxlair	1870	0
7B	Hawkeye	1939	0
7F	Headwaters	2740	0
11B-UP, M8	Hedges	1489	0
12G Lower	Hudson	0	2403
6H	Hullabloo	1173	0
3G	Jamboree	1619	0
N/A	Jibland	318	0
N/A	Jug Handle	434	0
7N-M	Lies	1109	0

Trail Pod #	Trail Name	Trail Length on	Trail
		Intensive Use Area Lands	Length on Town Lands
6K	Little Cloud	364	0
3C-LOW	Little Dipper	993	0
N/A	Little Gore Crossover	0	770
2K	Lower Cloud Traverse	655	0
6G	Lower Darby	1019	0
1C (1D-1NR)	Lower Sleighride	1817	0
6F	Lower Steilhang	1246	0
3A	Lower Sunway	3769	0
10C-LOW	Lower Uncus	794	0
2J-UP	Lower Wood In Traverse	1115	0
M2	Mica	444	0
12D	Moxham	368	2509
2D	North Star	1803	0
6E, 7N-O	Open Pit	972	0
31	Otter Slide	407	0
12C, 12A	Peaceful Valley	3173	2837
2E UP, LOW	Pete Gay	3976	0
10A, 10B LOW	Pine Knot	2455	0
N/A	Pipeline Traverse	5419	0
1C (1NR-3F)	Pot Luck	723	0
2C	Powder Pass	3580	0
1B	Quicksilver	2036	0
C7	Ruby Run	2563	0
11K	Sagamore	6037	0
6B-LOW (2K- 6K)	Santanoni	133	47
1C (1A-1D), 1D	Showcase	5928	22
1K	Showoff	188	0
2B, 2I	Sleeping Bear	2796	0
N/A	Starting Gate	359	0
1C (1C-1A), 1A	Sunway	5047	0
2A	Tahawus	4184	0
C1	Tannery	2768	0
1C (FROM 1NR)	The Arena	991	0
7H	The Glen	433	0

	Trail Pod #	Trail Name	Trail Length on Intensive Use Area Lands	Trail Length on Town Lands
	N/A	The Gully	730	0
	2F (2J-2E)	The Loop	850	0
	12B	The Oak Ridge Trail	1984	0
	N/A	The Peace Pipe	918	0
	7N-L	The Rumor	1260	0
	10E	Topridge	3900	0
	1K	Tower 6	118	0
	3E	Twin Fawns	1094	0
	1F	Twister	6603	0
	N/A	Twister's Little Sister	121	0
	10C-UP	Uncas	1833	0
	12c	Eagles Nest Bridge	620	0
	6D	Upper Darby	808	0
	1G	Upper Sleighride	1727	0
	6C	Upper Steilhang	1739	0
	2F (TO 2J)	Upper Wood In	973	0
	13A	Village Slopes	0	1260
	3B	Ward Hill	874	0
	1N-Q-1NR, 1N- R	Wildair	4980	0
	6J	Wood Lot North	924	0
	6B-LOW(FROM 6K)	Wood Lot South	1163	0
	2J (FROM 6B)	Wood Out	2340	0
	M1	Woodchuck	1163	0
		Totals (LF)	144,814	13,108
		Totals (MILAGE)	27.43	2.48
o:le	Annuariad Nat Vat	Constructed		1
alis	Approved, Not Yet	Approved, not yet constructed	2,850	0
	2N-L	Approved, not yet constructed Approved, not yet constructed	600	0
	6N-O	Approved, not yet constructed Approved, not yet constructed	362	0
	7N-P	Approved, not yet constructed Approved, not yet constructed	630	0
	/ IN I	Approved, not yet constructed	330	1

Trail Pod #	Trail Name	Trail Length on Intensive Use Area Lands	Trail Length or Town Lands
9B	Approved, not yet constructed	1,250	0
10F	Approved, not yet constructed	2,345	0
10H	Approved, not yet constructed	3,848	0
11B Lower	Approved, not yet constructed	1,480	0
11G	Approved, not yet constructed	1,720	0
11M	Approved, not yet constructed	1,925	0
11L	Approved, not yet constructed	4,095	0
111	Approved, not yet constructed	2,495	0
11J	Approved, not yet constructed	4,085	0
12E	Approved, not yet constructed	0	1,605
12G Upper	Approved, not yet constructed	0	1,580
12H	Approved, not yet constructed	0	3,067
121	Approved, not yet constructed	0	6,410
12J	Approved, not yet constructed	0	2,140
	Totals (LF)	29,150	14,802
	Totals (MILAGE)	5.42	2.80
_	•		
Proposed in 201			
110	Proposed	3,415	0
12L	Proposed	1,210	0
12M	Proposed	340	1,035
12I-A	Proposed	1,520	1,223
12J-A	Proposed	100	1,235
12N	Proposed	0	600
120	Proposed	305	280
	Totals (LF)	6,890	4,373
	100000 (21)		<u> </u>

Summary of Totals	(In Miles)
Total Existing Trails on Intensive Use Lands	27.43
Total Approved/Not Constructed Trails on Intensive Use Lands	5.42
Total Existing and Approved Trails on Intensive Use (IU) Lands	32.85
Total Proposed Trails on Intensive Use Lands	1.30
Total Existing/Approved and Proposed Trails on IU Lands	34.15
Constitutional Trail Mileage Limit	40.00
Total Allowable Trail Mileage Remaining	5.85
Total Existing/Approved and Proposed Trails on IU Lands	34.15
Total Existing Glades on IU Lands	4.60
Total Existing/Approved and Proposed Trails and Glades	<i>38.75</i>

SECTION II INVENTORY OF EXISTING RESOURCES, FACILITIES, SYSTEMS AND USE

A. Inventory of Natural Resources

1. Physical Resources

a. Geology

Gore Mountain Ski Center is within the Adirondack Upland physiographic province which consists of an ancient domed Pre-Cambrian erosion surface, with erosional remnants forming the higher, more rugged features such as The High Peaks. Ancient crystalline metamorphic rocks similar to those of the Canadian Shield in Canada prevail. Specifically, the bedrock at the Ski Center is composed of granitic and quartz syenitic gneiss which contains varying amounts of such minerals as hornblende, pyroxene, garnet and micas. Intense glacial scour has removed most of the glacial soil and, in general, smoothed the land surface.

The landform that is Gore Mountain, including the former Barton garnet mine that is located on the north side of the mountain, is considered a unique geologic feature because of the nearby garnet deposits (http://www.dec.ny.gov/permits/53858.html).

b. Soils

Soils on the site are shown on **Figure** 16, "Soils Map". Soils mapping was obtained from the US National Resources Conservation Service's Soil Survey Geographical Data Base (SSURGO).


The following soils are present within the Intensive Use Area.

Bice very bouldery fine sandy loam – these are deep, well drained soils on hillsides, hill crests and narrow valley sides.

Hermon very bouldery fine sandy loam – these are very deep, well drained and somewhat excessively drained soils on hilltops, hill sides, ridges and mountainsides.

Hermon-Lyman Rock outcrop complex – this complex is a mix of the previously described Hermon soils with the shallow and somewhat excessively drained Lyman soils. This complex is found on mountain sides and hilltops where the landscape is influenced by underlying bedrock. Bedrock outcrops typically make up 15%. This series is the most prevalent soil type in the Intensive Use Area.

Hinckley cobbly sandy loam – these a gently sloping to sloping, deep, excessively drained soils on terraces and benches in valleys.



Hinckley-Plainfield complex – the Plainfield series is in complex with the Hinckley series described above, and consist of deep, excessively drained sandy and gravelly soils. This complex occurs along the Gore Mountain access road from Peaceful Valley Road.

Lyman – Rock outcrop complex – these are shallow and somewhat excessively drained Lyman soils with 30 percent rock outcrop. These soils occur on mountain tops in the Intensive Use Area.

Marlow very bouldery fine sandy loam – these are deep well drained soils on hillsides, crests of hills and mountainsides. A large portion of the lower elevations of the Intensive Use Area contain Marlow soils.

Plainfield loamy sand – see the description of the Hinckley-Plainfield complex above for a description of the Plainfield soils.

Wareham loamy sand – two very small areas of this series are located in the southwest corner of the Intensive Use Area. These are nearly level, deep, and somewhat poorly drained soils.

Two of the important soil characteristics that need to be given consideration are the susceptibility of soils to erosion and the depth to bedrock in the soils.

Soil erodibility is a function of soil detachment potential and the amount of runoff generated from a soil. Clays tend to have low detachment potentials and coarse sands tend to have low runoff potential. Both of these soil types with have a low erodibility which is expressed numerically as soil K factors. Generally speaking, low erosion potential soils have K values that range from 0.05 to 0.2. Soils with moderate erosion potential generally have K factors that range from 0.25 to 0.4, while high erosion potential soils have K factor values higher than 0.4. The following provides the list of soils in the Intensive Use Areas and their K values.

Soil Series	Erosion Factor (K)
Bice	0.20-0.24
Hermon	0.10
Hinckley	0.17
Lyman	0.20-0.32
Marlow	0.20-0.32
Plainfield	0.15-0.17
Wareham	0.10-0.17

Soils in the Intensive Use Area generally have low erosion potentials with the Lyman and Marlow series being in the low-moderate range of erodibility.

Construction activities that require excavation in areas of soils with shallow depth to bedrock can require blasting. Generally speaking, the soils at lower elevation in the Intensive Use Area

have deeper bedrock. The following are the depths at which bedrock is typically present in the soils at Gore Mountain.

Soil Series	Depth to Bedrock (inches)
Bice very bouldery fine sandy loam	>72
Hermon very bouldery fine sandy loam	>60
Hermon-Lyman-Rock outcrop complex	0 - >60
Hinckley cobbly sandy loam	>65
Hinckley-Plainfield complex	>60
Lyman-Rock outcrop complex	0 - 17
Marlow very bouldery fine sandy loam	>65
Plainfield loamy sand	>60
Wareham loamy sand	>60

c. Topography and Slope

As shown on **Figure** 17, "Topography," topography on the site ranges from approximately 1100 to 3500 feet above mean sea level (MSL).


The peak of Gore Mountain is situated at an elevation of 3583 feet MSL, Bear Mountain is at 3218 feet MSL and Pete Gay Mountain is at 3130 feet MSL. The base lodge is located at 1500 feet MSL. The Slope Map, **Figure** 18, was developed from site topography and slope classes by percentage are provided below:


Slope Class	% of Site
0- 10%	5.4
10-15%	11.9
15-25%	33.7
25-30%	16.5
30-35%	10.4
35-40%	7.1
40-45%	4.9
45-60%	6.7
60-85%	2.7
>85%	0.4


d. Water Resources

See Figure 19, Surface Water and Wetland Resources.

There are three streams on the site which flow to the east and are tributaries to North Creek. Straight Brook (941-1257) drains the southwest part of the Intensive Use Area. Roaring Brook







(943-1253 and 1254) drains the northern part of the Intensive Use Area. The North Creek Reservoir, now the snowmaking reservoir for Gore Mountain, was formed by damming Roaring Brook. The unnamed brook which is crossed by the ski center entry road is tributary 2 of North Creek and drains the central portion of the Intensive Use Area.

Rabbit Pond (H-P527b) is currently located on the part of the Vanderwhacker Mountain Wild Forest (VMWF) to the north of the Intensive Use Area. A land reclassification that would add the portion of the VMWF containing Rabbit Pond to the Intensive Use Area is suggested in this UMP/GEIS. According to the 2005 UMP for the VMWF, Rabbit Pond is 0.4 acre in size.

A water quality monitoring summary was prepared on behalf of ORDA in March 2007, evaluating data collected during the period 1995 – 2006. The data were collected with the intent of assessing changes in water quality "as it relates to construction activities and changes in vegetation cover types following construction". The conclusions of that report are restated in pertinent part below:

- Based on the analysis of storm-event conductivity data from the two streams, construction activities at Gore Mountain for the period analyzed do not appear to be affecting local surface water quality.
- The location of construction activities and their proximity to surface water resources does not appear to be a factor affecting water quality in the streams that drain Gore Mountain.
- Consideration should be given to increasing the number of baseline samples that
 are taken and analyzed for conductivity and phosphorus levels. This would provide
 a more robust data set which may be helpful in elucidating any trends in water
 quality.

e. Wetlands

The official New York State wetland map for this area and aerial photographs were used to locate potential wetlands on the ski center property. These areas were then visited in the field and their approximate boundaries were drawn on aerial photographs. The boundaries were then transferred to a topographic map of the site to develop **Figure** 19, "Surface Water and Wetland Resources," which shows the locations of wetlands, ponds, streams, and the main drainage courses on the ski area property. A map of the wetland locations at a scale of 1 inch = 400 feet is incorporated by reference and is available from the Lead Agency. There are several scattered, small boggy wetlands on Gore Mountain that range in size from less than an acre to approximately 5 acres. These are found in flat pocket areas that hold water flowing from steep slopes above. Water is at or near the surface in these areas during most of the year. Predominant vegetation consists of sedges, peat moss, alders, red maple, or cedar.

The large wetland just above the snowmaking reservoir had previous beaver activity. The earlier flooding and standing water in the wetland is no longer present since the abandoned


beaver dam has naturally breached over time. The two wetlands on the upper mountain are intermittent drainageways that are shrub swamps typical of hillside drainages. Alders, balsam fir and viburnums are predominant. In terms of the functions and benefits that they provide, wetlands on the mountain serve to retain and slow down runoff flowing from higher elevations. They also may serve as habitats for certain species of wildlife, particularly some species of amphibians and reptiles, which may not be able to use the surrounding upland habitats for their breeding or foraging activities. The wetlands on the ski center were field checked by APA personnel during the preparation of the 1995 UMP.

f. Climate and Air Quality


Climate-Snowfall

For the past five November to March ski seasons Gore Mountain received an average of 128.4 inches of snowfall. Each of the last five seasons is presented below. (Source: https://www.onthesnow.com/new-york/gore-mountain/historical-snowfall.html?&y=2009)


Gore Mountain received 122 inches of snowfall in the 2016-2017 ski season. Snowfall amounts were spread fairly evenly from December to March. The first snowfall of the season was 2 inches that fell on November 24.




The 2015 to 2016 ski season in the northeast was characterized by many as "the winter that wasn't". Gore Mountain received a total of 39 inches all ski season. The first snowfall of the season, 7 inches, did not fall until December 19. Attendance was down that ski season by 30% compare to the average of the other 4 of the last 5 seasons.




The 2014-2015 ski season had a total of 134 inches of snowfall with the first snowfall occurring on November 23.




The 2013-2014 ski season saw a total of 158 inches of natural snowfall at Gore Mountain with the first snowfall occurring on November 23.



The highest ski season snowfall for the past 5 seasons occurred in 2012-2013 when Gore Mountain received 189 inches of total snowfall.



Just looking at the last 5 ski seasons leading up to last year it would appear that there is a downward trend in the amount of ski season snowfall (198, 158, 134, 39 and 122 inches). However, if the period examined is extended back another 3 seasons, this trend does not continue. It turns out that 2012-2013 and 2013-14 had higher than normal amounts and that 2016-2017 was consistent with 2009-2010 and 2010-2011.



Climate- Temperature

For the months of November through March average monthly temperatures in the region (in degrees Fahrenheit) are 20 degrees in December, 14.9 for January, 16.4 for February, and 26.6 degrees in March. No temperature data specific to North Creek were available from the National Climatic Data Center, so these regional average monthly temperatures may vary somewhat from North Creek due to local climatic influences. The presence and configuration of the Adirondack Mountains contribute to the variability of the climate within the region including an increase in cloudiness and precipitation during the winter months.

Both natural snow cover and winter temperatures influence the duration of the ski season. Although natural snow cover generally exists between December and May, the ski season generally runs from November through April if conditions suitable to snow making exist early in the season. Snowmaking generally requires that the mean temperature drops to 32 degrees Fahrenheit. As long as the night temperatures are sufficiently cold an accumulation of manmade snow is possible even if daytime temperatures rise slightly above the freezing point.

The frost-free growing season generally extends from the first week in May to the first week in October and average monthly temperatures in this interval range from a low of 45.3 degrees Fahrenheit in October to a high of 65.1 degrees in June.

Air Quality

NYSDEC's New York State Ambient Air Quality Report for 2016 reports that levels of sulfur dioxide and inhalable particulates (PM2.5) in Region 5 were well within acceptable air quality standards.

2. Biological Resources

a. Vegetation

Figure 20, "Vegetation," illustrates the plant communities existing on Gore Mountain Ski Center mapped as part of the 1995 UMP. Tree composition data from NYSDEC timber cruises were provided in Appendix 2 of the 1995 UMP, "NYSDEC Tree Cruise Data For Gore Mountain," were used to determine which of the ecological communities defined by the New York Natural Heritage Program (NHP) of NYSDEC (Reschke, 1990) were present on the project site. The timber inventory data and corresponding maps were then used in combination with 1983 aerial photographs to produce a map illustrating the approximate extent of the plant communities. This map shows only the broad-scale forest patterns and does not include such fine detail as the vegetation types within small areas such as clearings for ski trails and powerlines.

Following are brief descriptions of each of the major plant communities:

Beech-Maple Mesic Forest. This is the community that occupies the largest area on the site, especially the areas below about 2400 feet MSL elevation in the eastern and northern parts of the site. Sugar maple and beech are dominant, along with variable quantities of paper birch, red maple, yellow birch, and red oak.

Hemlock-Northern Hardwood Forest. In this community, hemlock is codominant with deciduous trees such as sugar maple, beech, red maple, and yellow birch. A small area that is potentially of this forest type was identified in the southeastern part of the site. Other, smaller areas may be located through ground-level vegetation surveys.


Spruce-Northern Hardwood Forest. At its upper elevation, beech-maple forest grades into this forest type, which extends up to about 3200 feet MSL. Its composition includes red spruce, sugar maple, beech, yellow birch, white birch, red maple and balsam fir. Striped maple is a common understory tree.

Mountain Spruce-Fir Forest. The tops of the highest mountains, above 3100 feet MSL, are dominated by red spruce and balsam fir, along with some paper birch and mountain ash.

Successional Northern Hardwoods. A few small areas in the easternmost part of the Intensive Use Area, plus areas on neighboring lands, were logged in the recent past and have undergone succession to a young woodland. Trees in these, areas may include red maple, aspens, balsam poplar, paper birch, white pine, green ash, and American elm.

b. Wildlife

In addition to the five forest habitat types on the project site described above, other community types occur on the site in lesser amounts including Mowed Roadside/Pathway (ski trails) and Reservoir/Artificial Impoundment (North Creek Reservoir).




The on-site vegetation communities support a variety of wildlife species known to utilize these habitat types within the Central Adirondack Ecozone. A number of species which have been documented to historically occur in the Upper Hudson River Basin (Hudson River Fish and Wildlife Report, Hudson River Level B Study, prepared by New York State Department of Environmental Conservation and United States Fish and Wildlife Service, April 1978) in general, and of these a number are likely to commonly occur on the site based upon their habitat preferences. Mammalian species likely to be common on the site include deer mouse, white-footed mouse, pine vole, woodland jumping mouse, short-tailed shrew, eastern chipmunk, porcupine, coyote, red squirrel, northern flying squirrel, pine marten, snowshoe hare, red fox, black bear, and whitetail deer.

A number of avian species are also likely to occur commonly on the site, some throughout the year and some as migrants. Based upon the NYSDEC/USFWS study and the habitat types found on the site, the avian species most likely to commonly occur on the site at any one time include ruffed grouse, broad-winged hawk, yellowbellied sapsucker, American robin, red-eyed vireo, brown-headed cowbird, rosebreasted grossbeak, purple finch, dark-eyed junco, white-throated sparrow, blue jay, American crow, black-capped chickadee, and brown creeper. Previous reports have stated that bald eagles and golden eagles have been observed in flight around the ski center lands, but these reports also state that no nesting sites are known to occur on the site or its immediate surroundings. A check with the Endangered Species Unit of NYSDEC confirmed that occurrences in the Gore Mountain area are instances of migrating individuals and not resident individuals of these two species.

Common amphibian and reptilian species known to occur in the upper Hudson River Basin and likely to occur on the site include spotted salamander, red-spotted newt, northern dusky salamander, red-backed salamander, spring salamander, northern twolined salamander, American toad, spring peeper, bullfrog, northern leopard frog, pickerel frog, snapping turtle, wood turtle, Eastern painted turtle, northern water snake, eastern garter snake and eastern milk snake. Of these species, the wood turtle is listed as a Special Concern species by the Natural Heritage Program of NYSDEC. As a special concern species, the wood turtle is not recognized as endangered or threatened, but documented concern exists for its continued welfare in New York.

Portions of the Gore Mountain Intensive Use Area at elevations above 2,800 feet are potential Bicknell's thrush habitat. See **Figure** 21, "Potential Bicknell's Thrush Habitat." Field studies were undertaken by the Wildlife Conservation Society (Saranac Lake) in 2004 and 2005 to determine if ski trail construction on Bear Mountain could potentially impact Bicknell's thrush. "Surveys involving playbacks conducted in 2004 and 2005 did not detect presence of Bicknell's thrush at Gore Mountain." See subsection "e" below regarding the Adirondack Sub-Alpine Forest Bird Conservation Area.

An inquiry to NY Natural Heritage Program resulted in a response that identified only Bicknell's thrush as being present at Gore Mountain IUA. No rare, threatened or endangered plant or



animal species, or unique plant communities or habitats were identified by the Natural Heritage Program. See the letter in **Appendix** 3. Also see section "e. Critical Habitat" below.

c. Fisheries

The ski area property contains the headwaters of three tributaries of North Creek and a portion of North Creek which is tributary to the Hudson River. Straight Brook, Roaring Brook and an unnamed tributary all begin on the ski area property, and on the Gore lands Roaring Brook has been dammed to form the North Creek Reservoir. The North Creek Reservoir once provided water to the Village of North Creek but is now used by Gore Mountain Ski Center for snowmaking. North Creek and its tributaries which are on the site are designated as trout waters by the NYSDEC. This indicates that these waters, at least historically, supported native trout populations. Confirmation of the presence of native trout populations was not made as part of the study. However, it is known that North Creek receives annual stocking of trout (brown, brook, and rainbow) by both NYSDEC and Warren County.

While the goal of this stocking program is to perpetuate the put and take fishery in North Creek, carry-over between years has likely resulted in the establishment of a population of the stocked strain(s). Prior investigations have theorized that the on-site tributaries to North Creek support native brook trout populations. Other species likely to be found in the coldwater communities of North Creek and its tributaries include various cyprinids (i.e. blacknose dace, cutlips minnows), sculpins, and white suckers.

The impounded North Creek Reservoir could conceivably support a community dominated by coolwater species such as yellow perch, chain pickerel, and brown bullhead.

According to the 2005 VMWF UMP, there have been no biological surveys of Rabbit Pond. "However, based on its small size, 0.4 acres, Rabbit Pond probably supports minimal to no fish life."

d. Unique Areas

No unique biological areas are known to occur on the ski center property or adjacent lands.

e. Critical Habitat

Adirondack Mountain summits above 2,800 feet in Clinton Essex, Franklin, Hamilton and Warren counties comprise the Adirondack Sub-alpine Forest Bird Conservation Area (BCA). More specifically, those summits above 2,800 feet with dense subalpine coniferous forests favored by Bicknell's thrush and other neotropical bird species. **Appendix** 4 contains NYSDEC's full description of this BCA.

Visual Resources

Visual inventories and visual impact assessments were performed as part of the 1995 UMP and for the 2002 UMP. Views into the ski area of Gore Mountain are primarily limited to its south and east exposures. The views of the ski area from the north are blocked to a large degree by South and Pete Gay Mountains.

The views of Gore Mountain from the south are limited to primarily to NY Route 28 at a few locations between Wevertown and the hill leading down to Peaceful Valley Road. Some other locations from where the ski area is visible are Durkin Road and County Route 29 near Oven Mountain Road. The ski area is visible from the section of NY Route 28N heading south from Olmstedville towards North Creek. Views from these locations are oftentimes screened by intervening vegetation.

B. Human Resources

1. Transportation

The local roadway network which provides access to the ski center includes NY Route 28, County Route 29 (Peaceful Valley Road), and County Route 73 (Gore Mountain Road). **Figures** 3 and 4 show the ski area in relation to these highways.

NY Route 28 is an east-west highway which is classified as a minor arterial. In the vicinity of Peaceful Valley Road, NY Route 28 is a two-lane facility providing 11 foot travel lanes and shoulders of four to six feet in width. The speed limit is posted at 55 MPH for travel in both directions.

Peaceful Valley Road is a two lane collector facility that intersects NY Route 28 from the south forming a T-intersection. Gore Mountain Road intersects Peaceful Valley Road from the west at nearly 90 degrees. Gore Mountain Road provides a circuitous alignment and is on a steady westbound upgrade approaching the ski area.

The NY Route 28/Peaceful Valley Road intersection provides an exclusive westbound left turn lane on NY Route 28 to turn onto Peaceful Valley Road. The approach to NY Route 28 on Peaceful Valley Road has right turn and left turn lanes with the right turn lane facilitating traffic flow back towards Warrensburg.

Saturday is consistently the busiest day of the week. There is a distinct morning arrival peak that occurs between 8:00 and 10:00 and a distinct afternoon departure peak between 3:00 and 5:00.

2. Community Services

Police Protection

The Warren County Sheriff's Office and the New York State Police provide police protection in the Town of Johnsburg.

Fire and Rescue Services

The Town of Johnsburg has multiple volunteer fire departments. The North Creek Fire House, located on Main Street, covers the Gore Mountain area.

The Johnsburg Volunteer Emergency Squad is located on Peaceful Valley Road and serves the Gore Mountain Area. In most instances the Gore Ski Patrol and first aid staff have patients stabilized for transport when the Emergency Squad arrives. A large number of Ski Patrol people and first aid staff are members of the Johnsburg or Minerva emergency squads.

Solid Waste Disposal

A private hauler takes refuse and recyclables from Gore Mountain to the Town of Johnsburg Recycling Center Transfer Station in North Creek where it is compacted and then disposed of through Warren county contracts with the incinerator in Hudson Falls.

Hospital and Physician Services

Most medical emergencies are transported to Glens Falls Hospital which is a travel time of approximately 45 minutes.

North Creek Health Center on Ski Bowl Road does provide emergency medical services but they are only open certain hours of the day and are closed on Sunday.

The Warrensburg Health Center provided urgent care 7 days a week but only for certain hours of the day.

Schools

The Johnsburg Central School District incorporates most of the Town of Johnsburg and portions of the Towns of Chestertown and Thurman. The K-12 school is located in North Creek and graduated 14 students in 2016.

Water Supplies

The North Creek area is within the North Creek Water District which serves 355 structures or between 900 and 950 individuals. The water source is drilled wells. Those living outside the District rely on individual wells. Gore Mountain has its own water supply and distribution system and does not rely on the North Creek Water District (see section II.C.1.h, Potable Water).

Sewage

There is no public sewage treatment facility in Johnsburg. See section II.C1.I, Sanitary Wastewater.

Electric and Telecommunications

Niagara Mohawk Power Corporation provides electric services to the Johnsburg area.

A number of "household" phone services are available in the Johnsburg area.

Cellphone service on the mountain and along NY Route 28 in the vicinity of the mountain is variable depending on the cell phone provider.

3. Local Land Use Plans

The Town of Johnsburg has a total land area of 204.6 square miles, representing 23.5 percent of all of Warren County lands, making it the largest township in the county. The town is entirely located in the Adirondack Park with approximately two-thirds of the land area designated as wilderness, wild forest or other public lands. As reported by the Adirondack Park Agency in June 2017, approximately 40% of lands in the Town of Johnsburg are privately owned and the other 60% is owned by the State of New York. These lands are distributed under the private and state land classification in the Table below.

Table 2
Town of Johnsburg Land Classifications

Land Use Classification	Acres	Percentage
PRIVATE LANDS		
Hamlet	1,911	3.6%
Resource Management	5,376	10%
Moderate Intensity	648	1.2%
Industrial Use	939	1.8%
Low Intensity	8,634	16.1%
Rural Use	36,111	67.4%
TOTAL	53,619	100%
STATE LANDS		
Wilderness	51,900	65.4%
Wild Forest	21,517	27.1%
Primitive	4	<1%
Intensive Use	3,844 (Gore Mt. Ski Resort)	4.8%
Pending State	173	<1%
Water	2,023	2.6%
TOTAL	79,288	100%

Source: Adirondack Park Agency

The Adirondack Park Agency regulates land uses within the boundaries of each of the above land classifications. In addition, the Town of Johnsburg regulates land use through its approved Local Land Use Program (LLUP) completed in 2007, which also serves as the Town of Johnsburg Zoning Law. The Johnsburg Zoning Law designates residential, business and mixed-use districts within the hamlet of North Creek. The remainder of land is classified as rural mixed use generally following the APA Land Use Classification boundaries and density requirements. The Zoning Law regulates land uses and area requirements and includes Commercial-Industrial Floating Zone, sign regulations, and special use and site plan review provisions.

The Town's LLUP received strong support from the 2005 Johnsburg Comprehensive Plan which is intended to serve as a guide for future growth, development, and preservation in the Town of Johnsburg. This plan was also intended to serve as the basis for requests for any requests to amend the Adirondack Park Land Use and Development Plan Map pursuant to Section 805, part 2, c, (3) of the Adirondack Park Agency (APA) Act. Specifically, it is meant to serve as the "comprehensive inventory and analysis of the natural resource, public, economic and other land use factors as may reflect the relative development amenability and limitations of the lands within the entire jurisdiction," as well as the formally adopted comprehensive master plan cited in the aforementioned section and part of the APA Act.

A goal of the plan is to promote tourism and recreation for all seasons in order to provide local employment opportunities. Specific policies supported in the LLUP are as follows:

- Support the Gore Mountain Unit Management Plan that proposes to link the Gore Mountain Ski Resort with the hamlet of North Creek.
- Pursue other enhancements for the North Creek hamlet area and Ski-Bowl Park as may be part of on-going implementation of the various plans prepared in the past.
- Continue to work with the Gore Mountain Region Chamber of Commerce, ORDA, and other interested groups to identify infrastructure improvements likely to be attractive to tourists.
- Identify appropriate locations for tourist and recreation businesses, and revise local zoning accordingly.

Other planning initiatives that support Gore Mountain improvements include:

- North Creek Action Plan (1993) dealt with economic development, hamlet revitalization, increasing tourism potential, and Main Street revitalization.
- Ski Bowl Park Enhancement Plan (1997) that provided details and cost estimates for needed facilities at the town owned and operated Ski Bowl Park.
- First Wilderness Heritage Corridor Plan (2001) for the rail corridor between Saratoga and North Creek was prepared. This plan established North Creek, Riparius, and The Glen as stops along the tourist railroad that began operation in 1999. Facilities constructed at each stop include parking, interpretative signs and small parks.
 - 4. Historical and Archaeological Resources

There are no known historical or archeological resources present in the area proposed for the improvements.

C. Man-Made Facilities


- Inventory of Constructed Facilities
- a. Downhill Ski Slopes

A comprehensive inventory of existing downhill ski trails at Gore Mountain was undertaken for this 2018 UMP Amendment. See **Appendix** 5.

Figure 22, "Gore Mountain, Ski Trail Inventory," illustrates the existing ski trails at Gore Mountain for the Winter 2016/2017 ski season.

Final trail length measurements were made electronically using AutoCAD Civil 3D-2014 and GIS software. **Table 1** in Appendix 5, "Gore Mountain Trail Inventory," presents the results of the inventory and mileage measurement for each trail. The Table lists each trail by name, indicates if a ski lift and/or snowmaking exists on a trail, and presents lengths of each trail by width (less

Gore Mountain Section II - 16



p: 518/587-8100 f: 518/587-0180

© the LA group 2017

Olympic Regional Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law. **Development Authority** 2634 Main Street Lake Placid, New York 12946



Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

1 inch = 1,500 feet |750

Feet

Drawing No: 22 than 30 feet wide, 30 feet to 120 feet wide and 120 feet to 200 feet wide. Key totals are summarized below:

1. Total constructed trail length 0-200 feet wide at Gore Mountain, including Ski Bowl Trails 29.9 miles. A breakdown by trail difficulty is as follows:

a)	Easier	5.1 mi	17% of total
b)	More Difficult	17.3 mi	58% of total
c)	Most Difficult	6.5 mi	22% of total
d)	Experts Only	1.0 mi	3% of total

- 2. Net constructed trail length for trails 0-200 feet wide on "Intensive Use" lands (excluding trails on Town Park lands in the North Creek Ski Bowl) is 27.43 miles.
- 3. Total trail length by width on "Intensive Use" lands is as follows:

a) Under 30 feet wide (on trail map and named)	1.31 miles
b) 30 feet to 120 feet wide	25.69 miles
c) 120 feet to 200 feet wide	0.42 miles

As stated above, the total constructed trail length 0-200 feet wide on Intensive Use lands is 27.43 miles. Based on updated calculations using the rules and methodology presented in Sections 2 and 3 in Appendix 5, 32.85 miles are approved to be constructed. This is less than the 35.4 miles noted as approved in the 2005 UMP amendment. Gore Mountain is authorized to operate up to 40 miles of ski trails, and therefore has 7.15 miles of trails available for future planning and approval.

It is important to clarify that the <u>areas</u> on the mountain approved for trail construction in the 2005 UMP have not changed. The calculation methodology, applied rules and criteria and high resolution aerial imagery used in the inventory in Appendix 5 are more detailed than those applied previously, and therefore have resulted in a different total mileage. The 2005 UMP only provides a 'grand total' mileage calculation, and does not document the mileage individually for each trail. The last time a detailed mileage calculation was performed on a 'trail- by- trail' basis was over 20 years ago in the 1995 UMP. Since that time, portions of some trails have been renamed, previously proposed trails have been abandoned and additional mountain areas have been approved and developed. As a result, a tabulation of mileage calculated for each trail in the 1995 UMP, along with each trail described in the current Trail Inventory in Appendix 5, would not provide comparable data.

According to Article 14, ski trails include areas 30-200 feet wide. At Gore Mountain, 1.31 miles of trails are less than 30 feet wide. Should trails less than 30 feet wide be excluded from the total length of constructed trail calculation (27.43 miles), then Gore would have 26.12 miles of constructed trails out of the 32.9 miles of approved trails and the 40 mile maximum.

Gore Mountain Section II - 17

b. Backcountry, Hiking and Mountain Bike Trails

Gore Mountain has approximately 14.6 miles of groomed cross country ski trails, with terrain ranging from "easiest" to "most difficult." The trails form several loops located on the lower part of Gore Mountain, as illustrated on **Figure 7**, Existing Conditions (South).

The trails average 12 feet in width. All trails are accessible from the base lodge and are routinely patrolled by professional ski patrol members. Trails are open from early December to late March as weather permits. Lessons, rentals and repair service are available from the base lodge, as well as access to other amenities and services.

The existing hiking trails at Gore Mountain, allowed by an amendment to the 1995 UMP, are located as shown on **Figures** 9 and 10, Existing and Proposed Hiking and Biking Trails (South and North) There are approximately 10 miles of such trails, generally consisting of a 5.5 mile trail to the top of Gore Mountain, known as the Schaeffer Trail, a 3 mile loop referred to as the Rabbit Pond and Oak Ridge Trails (about half of this trail is on ski center lands), and the Roaring Brook Trail which is about 1.5 miles long.

Existing trails for mountain biking are located as shown on **Figures** 9 and 10, Existing and Approved Hiking and Biking Trails (South and North). There are 22 such trails, which are accessed from the base or via the Northwoods Gondola to the summit of Bear Mountain. The gondola runs for the mountain biking season from June 30th to September 3rd on Friday, Saturday and Sunday, and from September 9th to October 9, from 10:30 AM through 5:30 PM. Helmets are required. Gore Mountain has mountain bike staff which patrols the trails during operation.

c. Lifts

There are 13 existing ski lifts at Gore Mountain. Lift locations are illustrated on **Figures** 7 and 8, Existing Conditions (South and North) Lift types and lift ages are listed below in Table 3, "Gore Mountain Lifts."

Table 3
Gore Mountain Lifts

1	2014 Poma	Quad	Adirondack Express II
2	1997 CTEC	Quad	North Quad
3	1986 Riblet	Double	Sunway Chair
4	1963 Hall	JBar	J-Bar
9d	2001 Sun Kid	Conveyor	Snow train
6	1967 Riblet	Double	Parts from 1987 Riblet & 1996 CTEC High Peaks Chair
7	1995 CTEC	Quad	Straightbrook Quad
8	1999 Poma	Gondola	Northwoods Gondola
9a	1997 Poma	Platter	Old lift modernized & installed by Gore Bear Cub Lift
9c	2013 Sun Kid	Conveyor	Greenway Conveyor
10	2002 CTEC	Triple	Topridge Triple
11	2008 Poma	Detachable	Burnt Ridge Quad
12	Poma	Triple	Hudson Chair (top only in IUA, rest in Ski Bowl)

The Adirondack Express II, Lift #1, runs from the base to an intermediate point on the mountain referred to as the Saddle. The North Quad, Lift #2, services the north side of the mountain and discharges passengers just above the Saddle area. Two lifts run from an intermediate point to the summit (High Peaks Chair - Lift #6 and the Straight Brook Quad - Lift #7). Only the Northwoods Gondola, Lift #8, runs directly from the base to the summit of Bear Mountain. The Sunway Chair, Lift #3, runs from the base to approximately the midpoint of the Sunway trail. The Bear Cub Poma, Lift #9 A, is a beginner facility located southwest of the base lodge. The J-Bar, Lift #4, is another beginner facility located to the east of the base lodge.

d. Parking

Skier and visitor parking are currently provided in five lots located adjacent to the base lodge and gondola area. Four of these lots are dedicated to cars and one to buses. There is also a 6th satellite parking lot located on the lower portion of the access roadway which is limited to employee parking and some overflow bus parking on busy days.

Using an industry standard range of 140 to 180 cars per acre of parking, Gore Mountain's parking facilities can handle between 1,736 and 2,232 cars. During a typical ski weekend, the resort also accommodates between 20 and 25 buses. At the present time, the current available parking area is adequate to handle the parking demand, except during periods of peak demand when parking overflows onto the access road. Such overflows occur 3-5 times per year.

e. Access Roads

No revision to this section is necessary, except to note that the access road now terminates in the redesigned entry, circulation and ski center arrival/drop-off area approved in the 1995 UMP. The entry road will become a one way circular roadway with 3 lanes available in the passenger vehicle drop-off area, and 2 lanes available in the drop off area for buses. The improved circulation and drop-off area will be a significant asset by improving the efficiency and safety of the ski center.

f. Buildings

The ski area has four lodges available for use by skiers and visitors. The main lodge and Northwoods lodge are located at the base of the mountain and the Saddle Lodge is located mid-way up the mountain. The warming hut located at the Straight Brook area has been supplemented with a new Straight Brook lodge in the old summit gondola building.

The main lodge has a total area of approximately 45,000 square feet and consists of two stories. Facilities in the main lodge include food and beverage services, restrooms, ski school, retail sales, ski rental, public lockers, ticket office, bar/lounge, and nursery.

A recent addition to the Northwoods Lodge offers extra space to the rental and repair shop, expansion to the space allotted to the children's Mountain Adventure programs and food service for the Snow Sports School, and improved arrival and registration process. Larger restrooms on the lower level include a "family restroom" to accommodate parents with young children.

There is a new mid-mountain experience at the Saddle Lodge. The size of the space has more than doubled to 7,125 square feet, and occupancy has increased from 100 people to 238. Services now include a full-service or food court style meal with dining in front of a spectacular showcase of the Adirondack High Peaks. Updates to the Saddle Lodge also include an attractively styled vernacular, an expanded and updated kitchen to serve a larger, more creative menu, new bathrooms, and an approachable façade and lobby area upon entry. The fully renovated Saddle Lodge offers guests an appealing lunch alternative to the Base Lodge Food Court and Tannery Pub & Restaurant.

Gore Mountain's guests also have a new summit place to warm up at the Straight Brook Lodge. A complete renovation of the original 1967 gondola unloading station has kept the

original structure and most of the lift machinery intact while facilitating the basics of shelter, restrooms, and a place for socializing and camaraderie between skiers. Inside there is a warming room with tables and benches, vending machines, and eco-friendly composting toilets.

g. Maintenance Roads

Approximately 9 miles of maintenance roads traverse the ski area. These roads are used to accomplish summer maintenance of slopes and lifts and to access particular areas such as the saddle, the summit, pumphouse, reservoir, etc.

h. Potable Water

Potable water for the base area is provided by a drilled well located approximately 75 feet from the J-Bar lift. The well is 280 feet deep and has a capacity of 60 gpm at a depth of 46 to 48 feet. All water mains and hydrants are 6-inch cast iron. On demand, water is fed to a 100,000 gallon holding tank located at the top of the J-Bar hill. From there, the system is gravity fed and metered as it enters the lodge. During periods of high water demand in the lodge, when the well pump is running, water is routed directly into the lodge's distribution system.

Water supply for the Saddle Lodge located at mid-mountain is now supplied by a new 6 inch diameter drilled well. It is located in the vicinity of the Saddle Lodge. The well is 180 feet deep and yields 6+ gpm. The water is transmitted via a new main to the existing 5000 gallon static storage tank and then pumped to an existing 600 gallon pressure tank.

i. Snowmaking

Snowmaking is provided on almost 100% of Gore Mountain's trail terrain which covers approximately 334 acres. Sixty-five all-new high-efficiency ground guns and another new tower gun were added to the mountain in 2016. A fresh fleet of high-efficiency towers was installed in 2015, primarily along Showcase and Wild Air, allowing existing guns to be utilized in other areas. Twenty-two new permanent, high-efficiency tower guns were added the Topridge trail in 2014. These guns require significantly less air than the more traditional ground guns, offsetting energy use. New snowmaking was also placed around the Pipeline Bridge to further improve the interconnect with the Historic North Creek Ski Bowl.

The total snowmaking system combines both air and airless snowmaking technology. The Ski Center has increased its water use from the snowmaking reservoir from 223 million gallons in 2009-2010, to 305 million gallons during the 2013-2014 season. Hours of snowmaking operation averaged approximately 1,450 over the past 5 seasons.

Gore Mountain Section II - 21

j. Grooming Equipment

Grooming of alpine and nordic trails is accomplished with a fleet of seven grooming machines. It is anticipated that as terrain is developed as a result of the New Actions, that a total of two new grooming machines will be purchased.

k. Water Supply for Snowmaking

Snowmaking water is stored and drawn from the former North Creek Reservoir located northwest of the base area. The reservoir has a storage capacity of approximately 20 million gallons of water and is capable of recharging itself approximately four times per ski season. The Hudson River intake and pipeline was constructed, as proposed in the 1995 UMP, and water is now pumped from the river to the reservoir, and distributed on the mountain. Refer to Table 4, "Snowmaking Utilization" for additional detail.

Table 4 Snowmaking Utilization

		System					
	Trails	Capabilities	Operations	Water Use	Water Use	Average	
	(Acres)	(gpm)	(hours)	(gal)	(ac-ft.)	gpm	Utilization
Long term							
GOAL	334	4800	1250	290,000,000	1,450	3,866.67	80.56%
2015/2016	334	4800	1384	276,000,000	1,380	3,323.70	69.24%
2014/2015	334	4800	1370	290,000,000	1,450	3,527.98	73.50%
2013/2014	334	4800	1520	305,000,000	1,525	3,344.30	69.67%
2012/2013	332	4800	1677	276,816,000	1,384	2,751.10	57.31%
2011/2012	331.12	4800	1307	208,835,252	1,044	2,663.04	55.48%
2010/2011	331.12	4800	1544	228,528,000	1,143	2,466.84	51.39%
2009/2010	323	4800	1544	222,960,000	1,115	2,406.74	50.14%

I. Sanitary Wastewater

Gore Mountain's base area wastewater treatment plant underwent a major upgrade in 1991-1992. During the winter season (peak use period), wastewater is treated by a microbiologically

activated sludge process consisting of equalization/pre-treatment, oxidation ditch and a tertiary microscreen and post-aeration. The plant capacity is 65,000 gallons per day (gpd) and can accommodate all of the proposed improvements to the ski center which are included in this UMP (including the on-mountain lodges). During the off-season, the oxidation ditch is taken off-line and wastewater is treated in a sequencing batch reactor in an extended aeration mode using the activated sludge process. Effluent polishing in the tertiary stage is accomplished by microscreen. The upper limit capacity is 20,000 gpd.

m. Drainage

Gore Mountain's existing stormwater drainage at the base of the mountain (lodge and parking lots) consists of pocket ponds, porous gravel lots and vegetated swales. Erosion and sediment control on the mountain is provided by water bars discharging to wooded areas that prevent water from reaching erosive velocities as runoff travels down the mountain.

n. Flectrical Distribution

Power is supplied by the Niagara Mohawk Power Corporation to the site and is distributed throughout the ski area via 34,500 volt and 4,800 volt aerial power lines. The Gore Mountain power station is set for a 34,500 volt power supply at a maximum demand load of 7.5 megavolt amperes (MVA). The current peak demand is approximately 7 MVA. Of the total MVA currently used during peak operational periods, 3 MVA operates the air compressors. Niagara Mohawk Power Corporation has allocated a peak load power demand of 7.5 MVA to Gore Mountain. All primary lines originate at a substation where 34,500 incoming volts are distributed. Distribution is then accomplished via 34,500 volt aerial lines to some parts of the mountain, and by 4,800 volt aerial lines to other parts of the mountain.

o. Solid Waste Management

Solid waste from the ski center is hauled by ski center employees to the transfer station in North Creek. The town then transports refuse to the Adirondack Resource Recovery Facility in Hudson Falls. Approximately 448 cubic yards of compacted waste per year is generated by the ski center.

p. Equipment Inventory

The ski area owns and maintains equipment ranging from office and computer equipment to furniture, carpentry equipment, trail grooming equipment, vehicles and snowmaking equipment. A complete listing of "Inventory Equipment" is available for review at ORDA headquarters in Lake Placid, New York.

2. Inventory of Systems

a. Management

Gore Mountain Ski Center was built in the early 1960's and was first opened to the public in 1964. Early management was under the direction of the Bureau of Winter Recreation, Conservation Department (now known as the Department of Environmental Conservation). On April 1, 1984, management was delegated to the Olympic Regional Development Authority (ORDA) through an agreement with DEC, authorized by Chapter 99 of the Laws of 1984 (Article 8, Title 28, Section 2614, Public Authorities Law).

This agreement transferred to ORDA the use, operation, maintenance and management of the ski area. DEC remains the statutory custodian of the state-owned ski area. Under the agreement, ORDA is to maintain the facility subject to DEC inspections; make capital improvements with DEC'S prior written approval; establish a sinking fund for capital improvements; continue the level of prior public recreation; comply with specified prior agreements; and cooperate with DEC in completion of a Unit Management Plan for the ski area. In 1991 DEC and ORDA entered into a Memorandum of Understanding superseding a 1984 memorandum between the parties, establishing methods and procedures by which managerial requirements contained in the underlying DEC/ORDA management agreements are to be complied with, and setting forth requirements for the operation of ORDA facilities and detailing procedures on how Unit Management Plans for each of the ORDA facilities are to be implemented. The MOU, in particular, relates to requirements for notices of management actions described in Unit Management Plans; the need to adhere to the DEC tree cutting policy; and identifies those activities that need to be undertaken which are not described in Unit Management Plans. This 1991 MOU was incorporated into the current (2013) DEC/ORDA Consolidation Agreement that covers Whiteface, Gore, the Memorial Highway and Mount Van Hoevenberg. A copy of the 2013 Consolidation Agreement is in Appendix 2 of this UMP. The 2013 Consolidation Agreement reestablishes the procedures for preparation of UMP's including such things as UMP content, UMP conformance with the SLMP, and the roles of ORDA, DEC and the APA in preparation, review and approval of UMPs.

b. Organization


The New York State Olympic Regional Development Authority (ORDA) was created in 1981 by the State Legislature as a public authority to oversee and manage the Olympic facilities in an effort to insure continued use and enjoyment of the facilities by the public. ORDA is composed of twelve members, three of these the Commissioners of the NYS Department of Environmental Conservation, Economic Development, and Parks & Recreation Departments, and the remaining seven appointed by the Governor of the State of New York. One of the appointed members, since the management of Gore Mountain was transferred to ORDA, must be a resident of Warren County. ORDA manages and operates the Gore Mountain Ski Center under its agreement with the Department of Environmental Conservation. The staff is led by the

Authority's President and Chief Executive Officer.

c. Operations

Personnel employed at Gore Mountain Ski Center vary with the season. During the winter season there are approximately 47 permanent and 453 seasonal staff. The ski school employs approximate one year-round, 4 full-time seasonal and 189 part-time personnel. The ski patrol operates with 45 staff and approximately 90 volunteers. During the summer months, there are approximately 37 fulltime staff and a maintenance crew which totals approximately 70 personnel.

Figure 23
Organizational Structure
Gore Mountain Ski Area



d. Contractual Arrangements

On July 16, 2011, the Authority entered into a 10 year agreement with Centerplate whereby the Authority granted Centerplate a license to have exclusive rights to furnish and install certain equipment and improvements and to manage and operate the food, beverage, catering and merchandise services, equipment rental/ski touring concessions including liquor/sales, food,

and retail services at all ORDA Olympic facilities on a year-round basis. Per the Agreement, the license is valid until July 15, 2021 with an option to renew for another 10 years upon the mutual written consent of both parties.

Under the terms of the Agreement, Centerplate's exclusive rights are subject to certain other contracts existing with the Authority, including: for Whiteface: the summer mountain bike rental concession agreement with High Peaks Cyclery of Lake Placid, New York.

Part and parcel to the Agreement is Centerplate's obligation to comply with all present and future federal and state laws, codes and regulations applicable to the conduct of the activities authorized, including all other applicable governmental regulations affecting the ORDA and the Olympic facilities in regard to the sale, use and storage of materials. Centerplate is also responsible for procuring, at its own expense, all permits, licenses or other approvals necessary for the performance of its duties under the terms of the License.

Snowmaking Water Supply - In accordance with the management agreement with DEC, ORDA continues to abide by the license granted by the Town of Johnsburg for the use of water in the North Creek Reservoir in connection with snowmaking operations at Gore Mountain Ski Center.

D. Public Use of the Ski Center

Ski Season Use

In **Table** 5, Winter Public Use of Gore Mountain Ski Center, it can be seen that there was no clear trend in the number of ticketed visits between 2005/2006 and this past winter (2016-2017). Average annual ticketed visits to the Ski Center during this time period was 137,090.

Similarly, there was no clear trend over time for the number of annual season pass holder visits. Average annual passholder visits for the period was 78,174.

The peak ticketed days of attendance used to always be within the February Presidents' Week. Since the last UMP Amendment, this has changed. President's Week continues to be the time of highest attendance with 8 of the 12 years reported below occurring during this February holiday. For two of the years below, the peak attendance day occurred in January during the Martin Luther King holiday weekend period. In one year (2012-2013) peak attendance occurred during the week of Christmas on December 28th. Last season's peak day attendance of 7,225 was the highest for the 2005-2017period.

Table 5
Winter Public Use of Gore Mountain Ski Center
from 2005-2006 until 2016-2017 (includes passholders)

Snow Season	Ticketed Visits	Passholder Visits	Total Visits
05-06	164,363	69,930	234,293
06-07	127,277	74,820	202,097
07-08	147,960	82,275	230,235
08-09	141,134	82,488	223,622
09-10	133,772	84,000	217,772
10-11	131,824	80,463	212,287
11-12	119,288	74,115	193,403
12-13	148,264	70,740	219,004
13-14	161,757	79,695	241,452
14-15	154,217	82,815	237,032
15-16	78,314	82,170	160,484
16-17	136,907	74,580	211,487

Snow Season	Peak Day	Ticketed Visits
05-06	2/18/2006	4,417
06-07	2/14/2007	5,989
07-08	2/16/2008	6,002
08-09	2/14/2009	5,414
09-10	2/13/2010	6,520
10-11	1/15/2011	5,476
11-12	2/18/2012	5,405
12-13	12/28/2012	5,763
13-14	2/16/2014	5,919
14-15	1/18/2015	5,428
15-16	1/17/2016	4,753
16-17	2/19/2017	7,225

	President's Holiday Week
Snow Season	(Ticketed Visits)
05-06	31,662
06-07	35,537
07-08	31,390
08-09	31,955
09-10	33,446
10-11	31,134

11-12	29,358
12-13	28,302
13-14	32,636
14-15	25,450
15-16	20,004
16-17	32,748

2. Non-Ski Season Use

The summer and fall season program centers around hiking, mountain biking (including mountain bike racing), educational interpretive opportunities and nature-oriented activities. Gore Mountain hosts an annual fall festival. The gondola is operated as a tourist attraction year-round. Hunting, trapping and fishing are prohibited at the Gore Mountain Ski Center. Only non-consumptive use of wildlife resources is permitted on Ski Center lands.

Use data for mountain biking, scenic rides, hiking, and base area activities have all been collected since the 2012-2013 season and those data are presented in the table below. During this period there has been a decline in mountain biking by almost 2/3. There was no real trend over the years for the number of gondola riders/hikers with the average for the 5-year period being 9,565. There is a decreasing trend in the number of base area activities participants, but not a consistent trend through the 5 year period.

Table 6 Non-winter Public Use of Gore Mountain Ski Center (2012-2013 to 2016-2017)

	2016-17	2015-16	2014-15	2013-14	2012-13
Summer / Fall Visits	Visits	Visits	Visits	Visits	Visits
Mountain Biking	134	212	248	257	391
Scenic Rides/Hiking	7780	10,088	8,442	11,615	9,899
Other (disc golf, bungee, etc.)	614	869	843	1,037	936
	8,528	11,169	9,533	12,909	11,226

SECTION III MANAGEMENT AND POLICY

A. Orientation and Evolution of Management Philosophy

ORDA's central management goal and management philosophy as stated in the 1987 UMP:

"The Olympic Regional Development Authority will continue to provide a safe, quality, recreational experience to the public and promote both local and regional economic benefits through its responsibility to manage and operate the Gore Mountain Ski Center to the highest standard."

ORDA's goals and management philosophy have evolved since its inception following the 1980 Olympic Games. Originally created as a management organization with a priority of providing a safe, quality, recreational experience, ORDA has expanded its operational philosophy to encompass business strategies that are similar to leaders in the ski resort and sports industry. It is recognized that ORDA's unique portfolio of assets have an ability to positively impact the economies in which it operates. In addition, ORDA's sporting events, attractions, and training facilities enhance people's lives.

Today, ORDA continues to build on the foundation of its mission and is deploying a philosophy that will allow the organization to be sustainable long into the future. This will be accomplished through strategic planning and open communication both internally and externally with all constituents. The business priorities are organized into three categories:

- 1.) Revenue Growth and Opportunities
- 2.) Capital Projects and Development
- 3.) Organizational Excellence

Within each of these categories, ORDA's centralized team works with management teams to develop strategic business plans for each venue that are in line with ORDA's goals and objectives. Short descriptions of these priorities are as follows:

Revenue Growth and Opportunities

Each year, management teams evaluate short term and long term concepts to increase revenue. Additionally, they explore opportunities in hosting major events, creating new partnerships that amplify ORDA's offerings, and overall, provide guests with the best experience. ORDA measures success through end of the year evaluations in specific revenue segments, visitation numbers, event profit and loss statements, and NPS (Net Promoter Score). (NPS is system utilized by leading resort operators in the industry and has been directly correlated with the ability to increase visitation and revenue.)

Capital Projects and Environment

Capital projects will be initiated through management and in line with ORDA's strategic plans. General priorities include refurbishment of outdated structures for safety, development or improvement of attractions or infrastructure that enhance the guest experience or allows ORDA to increase visitation and revenue.

Many ORDA venues exist within the boundaries of State protected lands and the impact of climate change on our environment is recognized. ORDA will be a leader in environmental stewardship with consistent commitment to sustainability, responsible development practices, and continuous communication with DEC, APA, and other regulatory agencies to ensure we are taking the appropriate measures.

Organizational Excellence

ORDA will strive for organizational excellence in every facet of its operation. From financial management, team building, communication, education, strategic planning, to overall safety, organizational excellence is a vision where every employee focuses on ways to improve or positively influence our operations.

B. Regulatory Issues

1. New York State Constitution Article 14

Article 14 of the State Constitution defines the intended "Forever Wild" character of Forest Preserve lands and establishes authorized uses and exceptions. Significant issues with respect to Gore Mountain are as follows:

a. Ski Trails

Article 14 establishes allowable limits for timber cutting to construct ski slopes on Forest Preserve lands at certain specified lengths and widths. As originally promulgated, Article 14 allowed up to thirty (30) miles of ski-trails from thirty (30) to eighty (80) feet in width on the slopes of Gore and Pete Gay Mountains in the Gore Mountain Intensive Use Area. In 1987, Article 14 was amended to allow up to forty (40) miles of trails and to increase the maximum allowable width of ski trails on the slopes of Gore and Pete Gay Mountains from 80 feet to 200 feet, provided that no more than eight miles of such trails are in excess of 120 feet wide. Based on Attorney General and NYSDEC legal reviews, the cross country trails are not considered a part of the 40 mile limit. The 1987 Constitutional Amendment removed South Mountain from the Gore Mountain Ski Center.

The construction of cross country ski trails was authorized by an Attorney General's Opinion dated January 18, 1934. These trails are allowed on Forest Preserve land when the cutting of

trees "to any material degree" will not be necessary, and the character of the preserve is not impaired.

The Constitution, while it establishes a limit for the width of ski trails, infers that these trails will be separated by buffer strips. There are no specific guidelines for widths of buffer zones that separate ski trails from other trails, lifts, access roadways, snowmaking facilities and buildings.

Buffer zone widths are influenced by variations in topography, drainage patterns, rock outcrops, soil stabilization concerns, safety considerations, machinery requirements and visual aesthetics.

b. Vegetative Cutting

Article 14 states that Forest Preserve land, as currently fixed by law, either presently owned or acquired in the future by the State, will be kept forever as wild forest lands. As such, Forest Preserve lands cannot be leased, sold, or exchanged, or be taken by any public or private corporation. Timber on Forest Preserve land cannot be removed, sold or destroyed. In the interest of public safety and in consideration of the development of protective and recreational facilities, it has been necessary for the Department of Environmental Conservation, as the managing authority for Forest Preserve lands, to periodically ascertain the limitations of legislative intent from the State Attorney General pertaining to the cutting, removal and destruction of trees.

In instances where cutting has not been sanctioned by constitutional amendment, the opinion and interpretation of the State's Attorney General has been sought on allowable cutting activities. One such opinion, dated January 18, 1934, pertaining to ski trail construction stated; "ski-trails (cross-country) may be constructed by the Conservation Department in the Forest Preserve when cutting trees to any material degree, will not be necessary and the wild forest character of the Preserve will not be impaired."

In addition, trees may be removed for several other purposes. An Attorney General's opinion dated February 5, 1935 authorizes the removal of trees in the Forest Preserve that endanger public safety. An Attorney General's opinion dated September 20, 1934 allows the use or removal of vegetation for surveying triangulation stations, where these stations serve as an aid to the conservation work of the State, and where the number of small trees used or removed for the work appear immaterial.

The cutting of trees to establish scenic vistas is addressed in an Attorney General's opinion of January 17, 1935. In this opinion, vistas may be established as long as the work is "carried on with care in order that the tree removal may not be sufficient to pass the point of immateriality."

Gore Mountain Section III - 3

Before the creation of a vista, alternate locations in the area and alternate methods of achieving the view must be considered. For example, a more sparsely wooded site might be found, or an observation platform erected.

The salvage of windfall timber is authorized when it is determined that it represents a fire hazard in an opinion dated July 26, 1945. Salvaged timber cannot be sold or given away to anyone who may sell it, but it can be used for any project under Department of Environmental Conservation jurisdiction.

A June 24, 1986 Attorney General Opinion (No. 86-F3) addresses the issue of whether the DEC may cut live-standing trees for use in the maintenance of existing trails in the forest preserve. The opinion concludes that: "The carefully planned and supervised selective cutting in the forest preserve of only those few scattered trees necessary for the maintenance of popular and steep trails to lessen soil compaction, erosion and the destruction of vegetation may be conducted consistent with the 'forever wild' provisions of the State Constitution, as long as it does not occur to any material degree." The Gore Mountain Unit Management Plan and supporting GEIS provides the necessary framework and procedures to ensure compliance with this standard.

Adherence to the DEC Commissioner's Tree Cutting Policy (Organization and Delegation Memorandum 84-06) is mandated in the 1991 DEC/ORDA Memorandum of Understanding for the implementation of Unit Management Plans. The Memorandum of Understanding requires approval of the DEC Director of the Division of Lands and Forest for the cutting of any vegetation at the State Facilities under ORDA's control. The request for approval to cut trees for the purposes of new construction, expansion or modification of projects must be submitted in writing and include specifically required detailed information. Furthermore, the DEC policy and procedures were amended in 1986 to include the requirement for adequate notice in the Environmental Notice Bulletin to the public as to the number of trees proposed to be cut and the size of the land involved on specific projects.

These requirements combine to assure that the test for "carefully planned and supervised selective cutting" will be met. In addition to authorizing tree cutting for ski trails, Article 14 permits cutting for appurtenances associated with the trails. ORDA, as did the previous DEC management, considers appurtenances to the ski trails to be those improvements and structures necessary to operate a modem, state-of-the-art ski center for safe, enjoyable skiing. Generally, these include such facilities as ski lifts, lodges, service roadways, parking lots, utility and water lines and other buildings and improvements needed for the operation and management of the ski center. Appurtenances are constructed on a case-by-case basis based upon criteria of effective use, safe engineering design and minimum disturbance to vegetation and other natural features. They are performed in accordance with this UMP and the 2013 DEC/ORDA Consolidation Agreement, as well as in accordance with the guidelines and criteria expressed in the Adirondack Park State Land Master Plan.

DEC'S established policy regarding cutting, removal and destruction of trees and other vegetation on all forest preserve lands is found in the Policies and Procedures of the Commissioner of Environmental Conservation (Organization and Delegation Memorandum #84-06 as amended). This policy recognizes the tree cutting sanctioned through constitutional amendment (e.g. ski trails) and by the Attorney General's Opinions above. Adherence to the commissioner's tree cutting policy is mandated in the DEC/ORDA Memorandum of Understanding of 1991 that is part of the 2013 DEC/ORDA Consolidation Agreement. All vegetation cutting at the Gore Mountain Ski Center must be in accordance with this policy.

The removal of cut trees may be done in any manner consistent with the guidelines of the SLMP, the UMP and Article 8 of the ECL.

c. Non-Alienation

Article 14 of the State Constitution provides that Forest Preserve Lands "...shall not be leased, sold or exchanged to any corporation public or private".

In the case of Slutsky vs. Cuomo et.al., the DEC management agreement with ORDA was challenged as violative of the non-alienation of State Forest Preserve land provisions in Article 14. The Appellate Division, Third Department, affirmed a lower court decision and upheld the constitutionality of this statutorily mandated agreement. On June 10, 1986, the Court of Appeals dismissed the Appellants appeal on the ground that no substantial constitutional ground was involved in the matter.

2. Adirondack Park State Land Master Plan

The APSLMP classifies State Lands in the Forest Preserve according to their character and capacity to withstand use and sets forth general guidelines and criteria for the management and use of state lands. The APSLMP classifies the Gore Mountain Ski Center as an Intensive Use Area. Intensive Use Areas are defined as follows:

"An Intensive Use Area is an area where the state provides facilities for intensive forms of outdoor recreation by the public. Two types of Intensive Use Areas are defined by this plan: campground and day use areas."

"These areas provide overnight accommodations or day use facilities for a significant number of visitors to the Park and often function as a base for use of wild forest, wilderness, primitive and canoe areas."

Guidelines for management and use which apply to Intensive Use Areas, including Gore Mountain, include:

 "The primary management guideline for Intensive Use Areas will be to provide the public opportunities for family group camping, developed swimming and boating, downhill skiing, cross country skiing under competitive or developed conditions on improved cross country ski trails, visitor information and similar outdoor recreational pursuits in a setting and on a scale that are in harmony with the relatively wild and undeveloped character of the Adirondack Park.

- "All intensive use facilities should be located, designed and managed so as to blend with the Adirondack environment and to have the minimum adverse impact possible on surrounding state lands and nearby private holdings. They will not be situated where they will aggravate problems on lands already subject to or threatened by overuse, such as the eastern portion of the High Peaks Wilderness, the Pharaoh Lake Wilderness or the St. Regis Canoe Area or where they will have a negative impact on competing private facilities. Such facilities will be adjacent to or serviceable from existing public road systems or water bodies open to motorboat use within the Park."
- "Construction and development activities in Intensive Use Areas will:
 - avoid material alteration of wetlands;
 - minimize extensive topographic alterations;
 - limit vegetative clearing; and,
 - preserve the scenic, natural and open space resources of the Intensive Use Area."
- "Priority should be given to the rehabilitation and modernization of existing Intensive Use
 Areas and the complete development of partially developed existing Intensive Use Areas
 before the construction of new facilities is considered."
- "No new structures or improvements at any Intensive Use Area will be constructed except in conformity with a final adopted unit management plan for such area. This guideline will not prevent the ordinary maintenance rehabilitation or minor relocation of conforming structures or improvements."
- "Since the concentrations of visitors at certain intensive use facilities often pose a threat of water pollution, the state should set an example for the private sector by installing modern sewage treatment systems with the objective of maintaining high water quality. Standards for the state should in no case be less than those for the private sector and in all cases any pit privy, leach field or seepage pit will be at least 150 feet from the mean high water mark of any lake, pond, river or stream."

There is one management guideline specific to Gore Mountain in the SLMP:

"Existing downhill ski centers at Gore and Whiteface should be modernized to the extent physical and biological resources allow. Cross country skiing on improved cross country ski trails may be developed at these downhill ski centers."

The APSLMP provides that Unit Management Plans be developed by the DEC in consultation with the APA for management of state lands. Such management plans shall conform to the

Gore Mountain Section III - 6

general guidelines and criteria set forth in the APSLMP. UMPs are also to be amended from time to time. The responsibility for preparation of the Gore Mountain UMP has been delegated to ORDA, as discussed below.

3. 2005 Unit Management Plan Amendment

The following is a summary of the current status of management action that have changed since the 2005 UMP Amendment. The status of all actions is included in **Table** 1 in Section 1 of this UMP/GEIS.

New Trails and Crossovers

- 12-A Pipeline Access to Gore Base is now 30% complete
- 12-B Oak Ridge access to Pipeline Trail is now 50% complete

Existing Trail Widening

- 1-F Upper Twister 80% is now complete
- 1-F Lower Twister 80% is now complete

Lifts – Lift #1 has been constructed

Lodges and Buildings

- Entry Drive/Drop off/Parking Renovation is now 50% complete
- Learning Center is completed

Trail Markers and Interpretive Systems – Interpretive Systems are now 25% complete

Parking Lots – New Passenger Car Lots are now 50% complete.

4. Environmental Conservation Law

Section 9-09031 of the Environmental Conservation Law places the "care, custody and control" of the Gore Mountain Ski Center with the Department of Environmental Conservation.

5. Olympic Regional Development Authority Act

The Olympic Regional Development Act (Article 8, Title 28, NYS Public Authorities Law) establishes the Olympic Regional Development Authority (ORDA) and sets forth its responsibilities, functions and duties. The management of the Gore Mountain Ski Center was transferred to ORDA pursuant to Chapter 99 of the Laws of 1984. This authority was implemented by an agreement between the DEC and ORDA on April 1, 1984.

Gore Mountain Section III - 7

6. DEC - ORDA Memorandum of Understanding and Consolidation Agreement

The DEC and ORDA implement their mutual responsibilities for management of Gore through a Memorandum of Understanding (MOU) dated March 8, 1991. The MOU sets forth mutually agreeable methods and procedures by which managerial requirements are implemented. The MOU also establishes the means by which the existing UMP is implemented. Such means generally involve notification, inspection and review of actions to ensure compliance with the UMP and applicable regulations.

In 2013 DEC and ORDA entered into a Consolidation Agreement that, in part, incorporates the 1991 MOU. A copy of this Agreement Consolidating the Management Agreements for the Gore Mountain Ski Center, the Whiteface Mountain Ski Center and Memorial Highway, and the Mount Van Hoevenberg Recreation Area is in Appendix 2. The 2013 Consolidation Agreement reestablishes the procedures for preparation of UMP's including such things as UMP content, UMP conformance with the SLMP, and the roles of ORDA, DEC and the APA in preparation, review and approval of UMPs.

C. Management Goals and Objectives

Gore Management has established goals and objectives in line with ORDA's key priorities:

- 1.) Revenue Growth and Opportunities
- 2.) Capital Projects and Environment
- 3.) Organizational Excellence

Revenue Growth and Opportunities

- a. Gore Mountain will seek to modernize facilities at Gore in order to enhance the guest experience, improve skier safety, and increase local and regional economic benefits, while maintaining environmental quality.
- b. Gore Mountain will seek to develop new summer and fall usage of the Ski Center to provide greater year-round use of the facility by the public, consistent with Article 14 and the SLMP.
- c. Gore Mountain will work closely with the North Creek community and Town of Johnsburg to provide information to visitors about the area and to cooperate in the establishment of a shuttle link between the Ski Center and North Creek and a physical ski link to Ski Bowl Park in order that public use may better help promote the economy of the area.

Capital Projects and Environment

- a. Gore Mountain Ski Center is a participator in Sustainable Slopes, which is the environmental charter for ski areas compiled by the National Ski Areas Association. Ski areas provide a quality outdoor recreation experience in a manner that complements the natural and aesthetic qualities that draws skiers to the mountains. Gore Mountain Ski Center is committed to improving environmental performance in all aspects of its operations and managing the area to allow for continued enjoyment by future generations.
- b. Gore Mountain will seek to increase the capacity of the ski area in concert with other modernization objectives in order to provide a higher quality skiing experience.
- c. Gore Mountain will implement a capital improvements program to achieve the above objectives. Specific elements are discussed in Section IV below.

Organizational Excellence

- a. Gore Mountain management will seek to establish annual budgets and schedules in support of the proposed capital improvements plan and other management objectives.
- b. Gore Mountain will seek to improve infrastructure reliability in order to reduce the high frequency of breakdown, excessive staffing requirements and consequent financial drain.
- c. Gore Mountain will seek to reduce its operations and maintenance costs by replacing outdated and aged equipment.
- d. Gore Mountain will seek to improve its economic return by making the mountain more attractive to skiers, and thus increasing ticket sales.
- e. Gore Mountain will seek to improve skier safety and enjoyment by widening certain trails and improving certain trail intersections.
- f. Gore Mountain will seek to improve trail selection and create a better balance among trails in order to appeal to a greater cross-section of the skiing market by increasing the number of trails for the beginning and advanced skier.
- g. Gore Mountain will continue to develop informational and interpretive graphics and displays which will educate the ski center's users to the historical, cultural and environmental conditions in the North Creek area as well as the Adirondack Park in general.

Gore Mountain Section III - 9

SECTION IV PROPOSED MANAGEMENT ACTIONS AND PROJECTED USE

A. Proposed Management Actions to be Undertaken after Acceptance and Adoption of this UMP

General

ORDA proposes to undertake a number of management actions to further its goals for the future of Gore Mountain. Those goals include the following.

- Make Gore Mountain more desirable for recreational guests, athlete training and hosting premier events.
- Modernize aging facilities and infrastructure
- Continue energy efficiency improvements
- Improve operational efficiency
- Increase competitiveness in the marketplace
- Explore potential for, and increase development of year-round and summer attractions
- Improve quality and diversity of recreational facilities
- Attract more visitors, including the younger generation/next generation

2. New Downhill Trails and Lifts

a. Widen Non-Beginner Trails

Trail Widening is proposed for Twister and for Echo.

The plan for Twister is to build upon previously approved widening efforts and widen portions less than 120 feet wide to 120 feet to achieve consistent width along the entire trail.

The bottom of the Echo trail it is proposed be widened to 120 feet to accommodate the new trail connection from Burnt Ridge and to better accommodate existing ski racing on Echo.

b. Add new triple or quad chair (Lift 9B), from Northwoods Lodge up Lower Sunway to just past the bend in Lower Sunway

Sunway/Lower Sunway is the longest beginner ski trail on Gore Mountain. The trail extends from its top near the Saddle Lodge down to the Northwoods Lodge. While the trail as a whole is rated as a beginner/easiest trail, different sections of the trail have different levels of difficulty.

Beginning skiers will typically progress from starting with the surface lifts on Bear Cub Run and the J-bar lift at Starting Gate to riding the existing Sunway Chair. This progression of terrain difficulty is sometimes too challenging for the beginning skier.

By adding this additional lift that puts beginning skiers lower on Lower Sunway where terrain is less challenging, there can be a more gradual progression of terrain difficulty for beginning skiers.

c. Widen Sunway and other green trails served by Lift 3

Figure 1, 2018 New Management Actions (South), shows the areas of trail widening.

- Sunway above and below the relocated Sunway lift
- Otter Slide
- 3B
- Cutoff
- Ward Hill
- Lower Sunway
- Little Dipper
- Jamboree

Trail widening in these areas will lessen congestion and provide for more enjoyable and safer skiing conditions on this beginner and intermediate terrain.

3. Snowmaking - Enlarge snowmaking reservoir

During periods of optimal snowmaking weather, the capacity of the existing snowmaking reservoir can limit the ski trail snowmaking capability on Gore Mountain.


The primary snowmaking water source for Gore Mountain is its intake on the Hudson River near the North Creek train station. Gore Mountain is permitted to withdraw 4,800 gallons per minute at its Hudson River intake (2014 NYSDEC Water Withdrawal Permit). Water that is withdrawn from the Hudson River is pumped up to the existing snowmaking reservoir near the Pipeline Traverse.

There is a snowmaking pumphouse located adjacent to the reservoir that pumps water from the reservoir up to the mountain snowmaking system. Pumping capacity at the pumphouse is permitted for 6,800 gpm (2005 UMP).

Thus, the withdrawal capacity from the reservoir can exceed the supply capacity from the Hudson River by 2,000 gpm. This 2,000 gpm can be considered as a "supply deficit."

The snowmaking reservoir has a surface area of +/- 5.2 acres and a storage capacity of +/- 19,000,000 gallons (19 Mgal). See **Figure** 24, Existing Snowmaking Reservoir.

Gore Mountain Section IV - 2








Olympic Regional **Development Authority** 2634 Main Street Lake Placid, New York 12946



Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

Snowmaking Reservoir Existing Conditions



Scale:	1"=60"
Design:	MJT
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037

24

With a supply deficit of 2,000 gpm, the reservoir can be emptied in times of peak snowmaking in approximately 6 ½ days of continuous peak withdrawal snowmaking.

Providing more storage volume would extend the time period when Gore Mountain can make snow during optimal snowmaking conditions.

Various options were examined for expanding the storage capacity of the snowmaking reservoir.

Option 1 involves excavating out portions of the reservoir within its existing footprint. By creating 3:1 sideslopes around the perimeter of the reservoir down to the depth of the reservoir intake, the volume of the reservoir could be increased from 19 Mgal to 23.5 Mgal (+4.5 Mgal).

Other options involve expanding the footprint of the existing reservoir.

Examination of these options included delineation of wetlands. The SLMP Guidelines for Management and Use of Intensive Use Areas include avoidance of material alteration of wetlands from construction and development activities. Identified wetlands included a complex located on the west end along the main reservoir inlet and a coniferous wetland located on a topographic bench between the Pipeline Traverse and the south shore of the reservoir.

Figure 25, Snowmaking Reservoir Expansion, illustrates an option for expanding the reservoir that avoids material alteration of wetlands. Under this option the reservoir snowmaking water supply storage capacity increases from 19 Mgal to 30.1 Mgal. This additional 11.1 Mgal would provide for an additional 92 continuous hours of peak snowmaking water supply from the reservoir.

4. Buildings


a. Expand NYSEF building

Two additions will be built on the NYSEF building. See **Figure** 14, 2018 Master Plan – Approved and Proposed Actions (Base Area).

The first will be a 2,350 square feet (25 x 47) addition. This may be one story or it may be two stories.

The second addition will be 775 square feet (31 x 25) and will be one story.

These additions will house administrative space, expanded and improved restrooms, expanded







Olympic Regional **Development Authority** 2634 Main Street Lake Placid, New York 12946



Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

Proposed Snowmaking Reservoir Expansion



Date:	November 6, 2017
Scale:	1"=60"
Design:	MJT
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037

ski tuning area, an event registration room, ski and equipment storage, and meeting space.

b. Reconfigure 1995 UMP-approved maintenance area to locate groomer garage and fueling adjacent to existing ski trail

Figure 14, 2018 Master Plan – Approved and Proposed Action (Base Area), illustrates the location of the garage where Gore Mountain groomers are stored and maintained as well as the location of the fuel pumps used to fuel the groomers.

These locations do not have direct access to and from ski trails and present operational issues when grooming takes place. Groomers are forced to travel over areas without snow cover to get in and out of the garage and to get fuel. This results in damage to groomer tracks and cleats that must be repaired and groomers being out of service during repairs. In addition, groomers currently track dirt/mud onto the ski trails after they refuel and go back onto the mountain.

Figure 14, 2018 Master Plan – Approved and Proposed Action (Base Area), illustrates the location of a new groomer garage building located in a currently wooded area adjacent to the Sunway trail. There are existing work roads on the east and south sides of the proposed new garage.

The 75 feet by 120 feet garage building will be able to house 9 groomers. There will be garage doors on the north and south ends of the building. Attached to the garage would be a 20 feet by 40 feet area for office/shop uses.

Groomers would come off a lower section of the new lift 9B and onto the upper section of the existing work road. Snowmaking will be added to the section of the work road leading up to the garage. A new fuel tank will be located adjacent to the snow covered work road. Groomers would then proceed up to the garage building. When exiting the building and going onmountain, groomers would take the other existing work road, which will have snowmaking, onto the Sunway Trail.

5. Bike Trail - Single track bike loop for Town trail at top of Little Gore

See **Figure** 10, Existing and Proposed Hiking and Mountain Bike Trails (North). Currently there is a mountain bike trail located on Ski Bowl property that switches back between the Oak Ridge and Moxham trails. The trail currently extends just a short distance onto the Intensive Use Area where it ends where it meets the Schaeffer hiking trail. It is proposed that a single track trail be provided from where the trail currently ends to the top of Lift 12 (the 46er lift). As shown on **Figure** 10, the trail would generally follow the route of the Oak Ridge Trail, switching back a number of times including some crossings of the Oak Ridge Trail as well as the upper part of the Moxham Trail.

6. Vehicle Access-modify 1995 UMP-approved shuttle lane separated from and independent of main traffic circulation route and parking

Figure 32 of the 1995 UMP included a plan for a shuttle path that started at the lower parking lots, ran to the west of the entry road and parking, and had a circular drop-off at the Northwoods Lodge.


The 1995 plan has been modified and is shown on **Figure** 26, Shuttle Lane Plan. A two way shuttle lane, separate from general traffic would begin along the section of the access road that is widened and allows for parallel parking along the access road. The shuttle lane would then loop through Lot G, cross the access road, parallel the east side of the road, pass through Lot E, and then continue past Lot D and Lot A to a drop-off and turnaround at the Main Base Lodge. This modified shuttle plan also includes optional loops into Lot B and into Lot F for less busy days when the shuttle does not need to return to the starting point as quickly.


Designated pick up/drop off points will be established along the separated shuttle lane in order increase shuttle efficiency. Shuttle stop locations will be clearly identified through simple signage. Related amenities such as ski racks and/or shelters may be installed at shuttle stop locations. Shuttle stops may be equipped with call buttons linked to the shuttle vehicles to alert shuttle drivers to waiting skiers.

7. Land reclassification involving Gore Mountain Intensive Use Area,
Vanderwhacker Mountain Wild Forest and Siamese Ponds Wilderness Area
which could allow the historic Rabbit Pond trail to be reclaimed and used winter
and summer

See **Figure** 27, Land Reclassification Map. This UMP Amendment proposes that 33 acres in the Gore Mountain Intensive Use Area becomes part of the abutting Siamese Pond Wilderness Area. In addition, 159 acres of Vanderwhacker Mountain Wild Forest would be added to the Gore Mountain Intensive Use Area. This land reclassification would require an APA process separate from this UMP.

The Adirondack Park Agency cannot find that a UMP Amendment proposing management actions on lands to be reclassified conforms to the APSLMP before the land is reclassified. First, the Agency must receive a request to reclassify, accompanied by a UMP for the proposed Intensive Use lands. The Agency must follow SEQRA regulations regarding public notice and comment and must hold hearings inside and outside the Adirondack Park on the request to reclassify, pursuant to the APSLMP. After notice, comment and hearings, the reclassification proposals would be presented to the Agency for a recommendation to the Governor for approval of the classification. The process culminates in the Governor's action on that





recommendation. This UMP Amendment does not assume that a reclassification request will be approved and does not authorize any actions on lands to be reclassified, based on a proposed future classification. The actual request for reclassification and a UMP Amendment for those actions on the lands proposed for reclassification would be presented separately from this UMP Amendment. Discussion of actions on those lands in this is conceptual only, and those actions cannot be authorized by this UMP Amendment.

Intensive Use Area to Wilderness Area

The lands on the top of Gore Mountain that would go into the Siamese Ponds Wilderness are at elevations 2,785 to 3,585 feet and are predominantly mountain spruce-fir forest with some beech-maple mesic forest at the lower elevations. This area is part of the Adirondack Sub Alpine Forest Bird Conservation Area and the dense subalpine coniferous forest is favored by Bicknell's thrush and other neotropical bird species.

Wild Forest to Intensive Use Area

There are trails in the vicinity of Rabbit Pond (Roaring Brook, Rabbit and Oak Ridge trails) that were presumably built in connection with ski use of Little Gore, perhaps as early as the 1920's (Vanderwhacker Mountain Wild Forest (VMWF) UMP, 2005). In the middle of the twentieth century, a network of ski trails was operated on and around Gore Mountain and Peter Gay Mountain on state and private land. Some of these trails on private land were eventually closed, and other became part of Little Gore (also known as North Creek Ski Bowl) (Ibid.). A Management Action proposed in the 2005 VMWF UMP involved the construction of the Raymond Brook nordic ski trail that would connect a new trailhead off of NY Route 28 with trails in the Siamese Pond Wilderness Area. See **Appendix** 6 for text and map excerpts from the 2005 VMWF UMP. This trail has been constructed.

This UMP management action also included: "If an agreement can be reached with the neighboring private owner(s), a short trail will connect from Forest Preserve to existing ski trails on Little Gore (see map). The Town of Johnsburg has indicated that they have arranged for permission to cut and mark ski/hiking trails from the North Creek Ski Bowl across this private land to the state boundary." This connection (Ski Bowl Connection) has also been constructed.

ORDA has been long time proponent of making a strong connection between the IUA and North Creek. ORDA's dedication to strengthening this connection is evidenced by past and present UMP Management Actions to link Gore Mountain, the Ski Bowl and North Creek.

See **Figure** 2, 2018 New Management Actions (North), Adding the area around Rabbit Pond into the Gore Mountain Intensive Use Area would provide the opportunity for ORDA to construct a ski lift from the base of the Ski Bowl to a point high enough on Little Gore that would allow

skiers to ski to the west to the Rabbit Pond Trail, ski on a section of the Rabbit Pond Trail and then tie into trails that return to the base of the Ski Bowl. This ski connection would make use of currently approved, but not yet constructed ski trails on Town of Johnsburg lands. The connection would also require some new sections of trail on private lands that would need to get subdivided out of the private lands and transferring these lands to the Town of Johnsburg. A similar transfer of lands to the Town would be required for the upper portion of the lift that is located on currently private lands. See **Figure** 2. The owner of these private lands has indicated to ORDA their willingness to convey these lands to the Town.

APSLMP Intensive Use Area Guidelines

The following 10 numbered items and the language that follows them demonstrate how the suggested reclassification of existing lands from Wild Forest to Intensive Use Area comply with the 10 applicable Intensive Use Area guidelines in the APSLMP.

1. The primary management guideline for Intensive Use Areas will be to provide the public opportunities for family group camping, developed swimming and boating, downhill skiing, cross country skiing under competitive or developed conditions on improved cross country ski trails, visitor information and similar outdoor recreational pursuits in a setting and on a scale that are in harmony with the relatively wild and undeveloped character of the Adirondack Park.

The proposed reclassification will provide public opportunities for downhill skiing, cross country skiing under competitive or developed conditions on improved cross country skill trails in a setting and on a scale that are harmony with the relatively wild and undeveloped character of the Adirondack Park.

The involved lands are currently on outer edge of the VMWF in close proximity to the hamlet of North Creek. The involved lands have contained ski trails dating back to the 1940s and possibly as far back as the 1920's. The involved lands are bounded on three sides by ski area development from the Gore Mountain Ski Area and the Town of Johnsburg Ski Bowl Park.

The possible activities involve installing a chairlift that would roughly parallel an existing Ski Bowl Chair lift and terminate at its top, just inside of the new Intensive Use Area lands. Potential ski trails in the additional Intensive Use Area would extend to from the upper lift terminal to a portion of the historic Rabbit Pond Trail. The remaining western portion of the Rabbit Pond trail in the Intensive Use Area would be actively maintained for cross country skiing and hiking.

2. All intensive use facilities should be located, designed and managed so as to blend with the Adirondack environment and to have the minimum adverse impact possible on surrounding state lands and nearby private holdings. They will not be situated where they will aggravate problems on lands already subject to or threatened by overuse, such as the eastern portion of the High Peaks Wilderness, the Pharaoh Lake Wilderness or the St. Regis Canoe Area or where they will have a negative impact on competing private facilities. Such facilities will be adjacent to or serviceable from existing public road systems or water bodies open to motorboat use within the Park.

The reclassification would result in an addition to an existing Intensive Use Area that is compatible with the character of the Adirondack environment and surrounding land uses. The suggested reclassification is not in the vicinity of areas of potential overuse, including the aforementioned units.

- 3. Construction and development activities in Intensive Use Areas will:
 - minimize extensive topographic alterations;
 - limit vegetative clearing; and,
 - preserve the scenic, natural and open space resources of the Intensive Use Area.

Minimal topographic alteration would be required to construct the upper lift terminal and possibly a lift tower or two below the upper terminal. Limited alpine trail construction would follow existing fall lines and would require minimal topographic alteration.

Vegetative clearing would be limited to only that needed to construct the lift and limited alpine trails. The cross country ski/hiking trail would just require brushing and blowdown removal from the historic Rabbit Pond trail.

Only the very eastern edge of the Intensive Use Area lands would experience any disturbance.

4. Day use areas will not provide for overnight camping or other overnight accommodations for the public.

No overnight accommodations, including camping would occur.

Final Generic Environmental Impact Statement

5. Priority should be given to the rehabilitation and modernization of existing Intensive Use Areas and the complete development of partially developed existing Intensive Use Areas before the construction of new facilities is considered.

The action would involve the slight expansion of an existing Intensive Use Area into an area that has historically been used for skiing. The action promotes the ongoing goal of providing for a better connection between the Intensive Use Area and North Creek.

6. Additions to the intensive use category should come either from new acquisitions or from the reclassification of appropriate wild forest areas, and only in exceptional circumstances from wilderness, primitive or canoe areas.

The suggested addition would come from the reclassification of a small outlying area of the VMWF.

7. Any request for classification of a new acquisition or reclassification of existing lands from another land use category to an Intensive Use Area will be accompanied by a draft unit management plan for the proposed Intensive Use Area that will demonstrate how the applicable guidelines will be respected.

The 10 applicable guidelines are being evaluated in this 2018 UMP Amendment for the Gore Mountain Intensive Use Area.

8. No new structures or improvements at any Intensive Use Area will be constructed except in conformity with a final adopted unit management plan for such area. This guideline will not prevent the ordinary maintenance, rehabilitation or minor relocation of conforming structures or improvements.

The only structures being contemplated in this UMP Amendment are the upper lift terminal and possibly a lift tower or two below the terminal. Likewise, the only other improvements being considered are some limited amounts of alpine ski trail to connect with previously approved ski trails at the North Creek Ski Bowl.

9. Since the concentrations of visitors at certain intensive use facilities often pose a threat of water pollution, the state should set an example for the private sector by installing modern sewage treatment systems with the objective of maintaining high water quality. Standards for the state should in no case be less than those for the private sector and in all cases any pit privy, leach field or seepage pit will be at least 150 feet from the mean high water mark of any lake, pond, river or stream.

No sewage treatment systems would be proposed.

10. Any new, reconstructed or relocated buildings or structures located on shorelines of lakes, ponds, rivers or major streams, other than docks, primitive tent sites not a part of a campground (which will be governed by the general guidelines for such sites set forth elsewhere in this master plan) boat launching sites, fishing and waterway access sites, boathouses, and similar water related facilities, will be set back a minimum of 150 feet from the mean high water mark and will be located so as to be reasonably screened from the water body to avoid intruding on the natural character of the shoreline and the public enjoyment and use thereof.

The only involved shoreline is that of Rabbit Pond. The nearest structure would be the upper lift terminal located over 1,000 feet from the shoreline of Rabbit Pond.

8. Rabbit Pond Trail Activities

As shown on **Figure** 2, 2018 New Management Actions (North), a new ski trail is proposed along +/- 600 feet of the existing Rabbit Pond Trail.


The Rabbit Pond Trail was among the early ski trails created in the North Creek/North River area in the 1930's and 1940's. A circa 1940's map entitled "Precise Ski Data of North Creek, N.Y., A Stone's Throw from Train to Tow" (see Figure 27A) shows the intermediate Rabbit Pond Trail located at the "Village Slopes". The trail and Rabbit Pond itself also appear on the 1958 USGS map of the area shown on Figure 27B.

Figure 27C shows the current mapping of the Rabbit Pond Trail, the 1958 USGS mapping of the Rabbit Pond Trail and the UMP-proposed ski trail. Mapping of the current Rabbit Pond Trail on Figure 27C was produced from GPS data collected by Wilderness Property Management Inc. (Steve Ovitt) and mapped by Warren County GIS Department (Ski Bowl Park 2017 Smart Growth Grant Long Trail to Little Gore Summit). Approximately 600 feet of the existing Rabbit Pond Trail would be within or very near the proposed ski trail.

Figure 27D shows how this section of the existing Rabbit Pond Trail could be easily relocated slightly to the north and away from the proposed ski trail where it would pass over terrain similar to what is currently crossed. Figure 27D shows the area within which the trail could be relocated. ORDA will work with NYSDEC, Steve Ovitt and members of the local hiking and backcountry skiing community to select the best Rabbit Pond Trail location within this area, including a location that provides adequate setbacks from the proposed ski trail.

Creation of the alpine trail and relocation of the section of Rabbit Pond Trail are not anticipated to cause any significant adverse impacts to the ecology of Rabbit Pond. Water quality within the pond will not be impacted. Data in previous UMP's have demonstrated that creation of ski trails in previously wooded areas do not impact nutrient and solids levels in nearby receiving waters. Data in previous UMP's have also demonstrated that snowmaking within a drainage basin does not significantly alter rates of stormwater runoff. The pond itself will not be physically affected. The mapping in Figure 4 shows that both the ski trail and the hiking trail will be no closer to the pond than what currently exists.

From the overall perspective of the attractiveness of the area's backcountry character and the benefits that are derived therefrom, ORDA believes that the relocation of +/- 600 feet of one trail within a network that consists of miles of interconnected trails will not cause a significant impact. ORDA believes that the proposed conceptual action will not cause significant economic





p: 518/587-8100 f: 518/587-0180

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law. © the LA group 2017



Olympic Regional **Development Authority**

2634 Main Street Lake Placid, New York 12946




Gore Mountain: 2017 Unit Management Plan Draft Amendment & Draft Generic Environmental Impact Statement

201537.01

Figure:

27A





40 Long Alley Saratoga Springs NY 12866 p: 518/587-8100 f: 518/587-0180

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law. 2634 Main Street Lake Placid, New York 12946 © the LA group 2017



Olympic Regional **Development Authority**




Gore Mountain: 2017 Unit Management Plan Draft Amendment & Draft Generic Environmental Impact Statement

Drawing Title

1958 USGS Map Gore Mountain Area 02/16/2018 201537.01

Figure:

27B








Olympic Regional **Development Authority** 2634 Main Street Lake Placid, New York 12946

Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement





Figure 27c



or experiential issues.

B. Projected Use

As per attendance figures previously provided in Section 2, ticketed and passholder ski visits are expected to fluctuate around the 215,200 per year average.

Peak day attendance is expected to range from 5,000 to 6,000 ski visits with peak day attendance over 7,000 being possible. President's Day weekend is expected to be the most likely time of peak day attendance.

Off-season visits for things such as mountain biking, gondola rides, hiking etc. are expected to average 11,000 per year.

C. Actions Approved in Previous UMP/EIS which are Part of the Foregoing 5-year Plan

Table 1 in Section 1 previously presented an accounting of management actions from previous UMP/EIS documents. Included in this accounting were categories for previously approved management actions that are partially completed and management actions that were approved and for which construction is pending.

These categories include the following which will continue to be part of the foregoing 5-year plan.

- Continued trail development
- Ongoing trail widening
- Lift improvements
- Lodge improvements and expansion
- Parking development
- Snowmaking modernization/improvements
- Continued infrastructure and energy efficiency improvements
- Continue to develop/improve compatible recreation amenities and public access
- Continue to develop/improve strong connections between Gore, the Ski Bowl and North Creek

D. Prioritization of Management Actions

The following is a listing of new management actions by priority.

Top Priority

Replace and relocate Sunway Lift

- Add new lift from Northwoods Lodge to Lower Sunway
- Widen Sunway and other green trails served by these lifts
- Snowmaking enlarge snowmaking reservoir
- Dedicated shuttle circulation

Moderate Priority

• Reconfigure groomer garage and fueling

Lower Priority

- Expand NYSEF building
- Single track bike loop on Little Gore

SECTION V POTENTIAL IMPACTS AND MITIGATION MEASURES

A. Physical Resources

Geology

Bedrock is at or near the ground surface in many locations in the Gore Mountain Intensive Use

Bedrock may be encountered when constructing a portion of the dedicated shuttle lane. There is an area of Lyman-Rock Outcrop soils between parking lot E and the base lodge. It may be necessary to blast some bedrock to create the shuttle lane through this area. It is also possible that blasting may be necessary as part of some of the trail creation or trail widening management actions. Bedrock may also be encountered when enlarging the snowmaking reservoir which could also necessitate blasting. Hermon-Lyman-Rock Outcrop soils are mapped on the north and south sides of the reservoir.

As described previously in Section 2, the landform that is Gore Mountain, including the Barton garnet mine that is located on the north side of the mountain, is considered a unique geologic feature (http://www.dec.ny.gov/permits/53858.html). These deposits will not be affected by the construction activities associated with the shuttle lane or the snowmaking reservoir which are both located at low elevations on the mountain.

Mitigation Measures

ORDA will employ the services of a professional, licensed and insured blasting company to perform any needed blasting. Blasters in New York State are required to possess a valid NY State Department of Labor issued Explosive License and Blaster Certificate of Competence. The Explosives License permits the licensee to purchase, own, possess or transport explosives. The Blaster Certificate of Competence permits the use of explosives.

If it is determined that blasting will be required, a written blasting plan will be developed and approved prior to the commencement of blasting. In general, the blast plan will contain information about the blasting methods to be employed, measures to be taken to protect the safety of the public, and how the applicable rules and regulations will be complied with. If, during the evolution of the project, there are significant changes in the blast design a new blast plan will be required. A test shot will be required for the first shot after the approval of each blast plan.

While each blast plan is tailored to meet the specific needs of a particular project, they all contain certain elements. Typically the general information provided will include: the blasting contractor; the project blaster; locations of blasting; the duration of blasting operations;

locations of offsite receptors; location of any nearby utilities; the drill hole pattern; the explosives and detonation systems to be employed; the proposed loading of the holes; the maximum weight of explosives to be detonated in any delay period; measures to be taken to minimize the offsite impacts of blasting; traffic control and warning signs; the sequence and type of blasting warning signals; location of seismographs to monitor blast induced vibrations; what, if any local permits are required; will pre-blast surveys be performed, and if so where; and other information as necessary.

In addition, prior to the commencement of blasting, a pre-blast meeting will be held with the blaster, project manager, and other interested parties.

A record of each blast should be made by the blaster, and a copy provided to and retained by the project, which contains at a minimum the following information:

- Name of the operator and/or contractor conducting the blast.
- The location, date and time of the blast.
- Name, signature and identification number of the blaster (certificate of competency number, as issued by the Department of Labor).
- Type of material to be blasted.
- Diagram of shot including number of holes, depth of holes, diameter of holes, burden, spacing, and face orientation.
- Location and distance of nearest non-company owned structure.
- A record of the shot including amount of subdrilling, decking, stemming height and type, quantity and type of explosive, quantity and type of detonator, weather conditions (including wind speed and direction), type of initiation system and all delay periods progressively, in milliseconds. A drill log reviewed and signed by the licensed blaster and company supervisor including date, time, location, shot number, number of holes, hole depth, average face height, burden, spacing, diameter and any potential problem areas such as seams, cracks, voids and water.

The following techniques and control measures will be considered in blast design to reduce ground vibration:

- Adjusting the blast hole pattern
- Reducing the pounds of explosive per delay:
 - o use of smaller diameter blast holes
 - o reduce bench height
 - use of decking
- Avoiding overly confined charges (e.g. excessive burden).
- Avoiding excessive subdrilling.

- Strict control over spacing and orientation of blast holes.
- Borehole deviation monitoring.
- If possible, designing the blast sequence to direct vibration away from structures of concern.

A properly designed blast will give lower vibrations per pound of explosive. Close to the blast, the ground vibration character is affected by factors of blast design and rock geometry, particularly charge weight per delay, delay interval, and to some extent direction of initiation, burden, and spacing.

Additionally, to reduce the public's concern regarding ground vibrations:

- Blasts will be scheduled for the same time of day whenever possible.
- Blasts will be scheduled for periods of high local activity.
- Blasts will not be scheduled for quiet periods.
- Neighbors will be notified of the blast schedule in advance.

2. Soils

Potential Impacts

Soil Erodability (K) Factors were discussed previously in Section2.A.1.b. "K" is one factor used to calculate potential soil loss using the Revised Universal Soil Loss Equation (RUSLE). Other factors in RUSLE include slope length (L) and slope steepness (S).


See **Figure** 28, Soils Map and Management Actions.

Construction of most new Management Actions is proposed on soils with an "E" slope category. E soils are described as steep. Some new management actions are proposed on soils with a "C" slope category. C soils are described as sloping (Soils Survey of Warren County, 1989)

Disturbance of areas of steep slopes during construction can lead to an increased vulnerability of the soils to erosion. Suitable measures must be implemented to first prevent soil erosion and then second to make sure that any soils that are eroded are contained and prevented from causing sedimentation in receiving waters.

ORDA will implement proper erosion and sediment control practices when undertaking construction practices at their venues that oftentimes involve construction on steep slopes. These proper practices are set forth in the *New York State Standards and Specifications for Erosion and Sediment Control* (last updated November 2016). These standards and specifications will be used to develop Stormwater Pollution Prevention Plans (SWPPPs) for construction activities in accordance with NYSDEC's *SPDES General Permit for Stormwater Discharge from Construction Activity, GP-0-15-002.*

SWPPPS will detail those measures that will be implemented during construction to mitigate



potential soil erosion and surface water sedimentation. SWPPP content will include such things as construction sequencing and phasing, temporary and permanent stabilization, structural erosion control practices and vegetative control practices. SWPPPs will include provisions for monitoring, inspections, data collection, and compliance documentation.

Mitigation measures that ORDA commonly and successfully employs during ski area construction activities include the following that will be incorporated into pre-construction SWPPP plans and specifications.

Mitigation Measures

Construction Road Stabilization – site access will be achieved using existing work roads, ski trails, driveways and parking areas. At this time, no new disturbance is anticipated for site access, material storage areas or other construction uses.

Concrete Washout – Concrete truck washouts will be provided in existing parking areas located in proximity to the Base Area.

Protecting Vegetation to Remain – clearing limits will be marked with flagging tape, paint or other suitable means prior to the felling of trees for lift line and ski trail construction. ORDA is particularly sensitive to adhering to clearing limits on the Forest Preserve lands on which they operate their venues.

Runoff Control

 Water Bars – Water bars shall be installed during construction of the ski slopes and lift lines. They are to be placed across the slope to reduce the potential for erosion, with diversion into stable vegetated areas or other stabilized outlet. All water bars shall be installed at a 2% slope and particular attention shall be paid to proper spacing specifications as follows:

Slope (%)	Water Bar Spacing (ft.)		
<5	125		
5 to 10	100		
10 to 20	75		
20 to 35	50		
>35	25		

(Source: New York State Standards and Specifications for Erosion and Sediment Control, 2016)

Rock outlet protection using construction-generated rock will be installed at the ends of water bars when natural areas appear not to be adequate.

 Trench Plugs – Sand bags or gravel bags will be employed in open utility trenches longer than 300 feet. Compost filter socks of suitable size are an acceptable alternative to sand bags or gravel bags.

Soil Stabilization

- **Temporary Seeding** Seed and mulch inactive areas with bare soil within 3 days of disturbance unless construction will resume in that area within 2 days. Seed with annual rye mixture at 30 pounds per acre. For late fall or early winter seeding seed with winter rye at a rate of 100 pounds per acre. Mulch areas with straw at a rate of 2 tons per acre.
- Permanent Seeding and Mulching Maintain existing vegetation outside of marked limits of disturbance. Soils disturbed for construction of ski trails and lifts shall be permanently stabilized by successfully establishing an herbaceous ground cover.

Seeding – A commercially available native seed mixture appropriate to the climate shall be used to stabilize disturbed areas to be re-vegetated. Seed may be applied by a number of suitable means including broadcasting, hydro-seeding, or incorporated as part of a geotextile (i.e. Green & Bio Tech SureTurf 1000 and 4000 Seeded Mat System ®, BIOMAT ® seeded mats).

Mulching – Broadcast seeded areas shall also be mulched. Broadcast seeded areas shall be mulched with invasive species free hay or straw at a rate of 2 to 3 bales per thousand square feet (100-120 bales per acre). Mulch shall be secured in place by either driving over the mulched area with a tracked vehicle or by applying a non-asphaltic tackifier.

Hydro-seeded areas shall contain a mix of wood cellulose mulch applied during the hydro-seeding process. Wood cellulose mulch shall be applied at a rate of 35 pounds per thousand square feet (2,000 pounds per acre). A non-asphaltic tackifier will be included with the hydro-mulch application.

Soil Restoration

As directed by the Qualified Inspector, areas of compacted soils that are to be seeded should be restored to improve the quality of the seed bed. The top four (4) to six (6) inches of soil shall be loosened using hand or mechanical means prior to applying seed. Also, as directed by the Qualified Inspector, finished grades consisting of exposed subsoils may require soil amendment or topsoil in order to provide a suitable seed bed.

Sediment Control

• **Silt Fence** – Where appropriate, silt fence (standard or reinforced) shall be installed along topographic contours. Use of silt fence is appropriate where there is no concentration of water flowing to the barrier and where the drainage area for overland flow does not exceed ½ acre per 100 feet of fence. Additionally, maximum allowable slope lengths contributing runoff to a silt fence shall be as follows:

Slope Steepness	Standard Maximum Slope Length (ft.)	Reinforced Maximum Slope Length (ft.)
<50:1	300	N/A
50:1 to 10:1	125	250
10:1 to 5:1	100	150
5:1 to 3:1	60	80
3:1 to 2:1	40	70
>2:1	20	30

(Source: New York State Standards and Specifications for Erosion and Sediment Control, 2016)

- Silt fence structures should be installed anywhere sediment retention is needed in and around a construction site.
- Perpendicular to slopes or parallel to contour.
- At the toe of highly erodible slopes.
- Around culverts and storm water drainage systems.
- Adjacent to lakes, streams or creeks.

Maintenance – Silt fences should be inspected periodically for damages such as tearing by equipment, animals, or wind and for the amount of sediment which has accumulated. Removal of the sediment is generally necessary when it reaches 1/3 the height of the silt fence. In situations where access is available, machinery can be used; otherwise, it must be removed manually. The key elements to remember are:

- The sediment deposits should be removed when heavy rain or high water is anticipated.
- The sediment removed should be placed in an area where there is no danger of erosion.
- The silt fence should not be removed until adequate vegetation ensures no further erosion of the disturbed slopes. Generally, the fabric is cut at ground level, the wire and posts removed, the sediment spread, and seeding and mulch is applied immediately.

Reinforced silt fence should be installed at the base of temporary stockpiles. The reinforced silt fence is designed to hold heavier loads. Falling debris from stockpiles may be caught by the reinforced silt fence where standard silt fence could fail.

 Straw Bale Dikes – Straw bale dikes may be used as a substitute for silt fence ONLY where shallow depth to rock precludes the proper installation of silt fence. Straw bale dikes shall NOT be used where there is concentrated flow. Straw bale dikes shall NOT be used where more than 3 months of erosion and sediment control is required unless bales are replaced or an additional parallel row of bales is installed prior to the original straw bales being in place for 3 months. Length of slope above the straw bale dike shall not exceed the following:

	Maximum		
Slope	Slope		
Steepness	Length (ft.)		
2:1	25		
3:1	50		
4:1	75		

(Source: New York State Standards and Specifications for Erosion and Sediment Control, 2016)

Straw bale dikes require more maintenance and degrade much more rapidly. Straw bale dikes offer a more standalone practice that may be less dependent on the required staking. Staking is required for both silt fence and straw bale dikes. Both practices are require to be buried in the ground, although silt fence is required a six inch burial as opposed to a four inch burial trench for straw bale dikes. If neither application is applicable, sediment may be captured by using aproned Triangular Silt Dikes.

Installation specifications:

- Each bale shall be embedded in the soil a minimum of 4 inches.
- Bales shall be placed in a row with ends tightly abutting the adjacent bales.
- Bales shall be securely anchored in place by stakes driven through the bales. The first stake in each bale shall be driven toward the previously laid bale to force bales together.
- Inspection shall be frequent and repair or replacement shall be made promptly as needed.

Ski Trail Construction

Erosion and sediment control practices for trail construction will be conducted similarly as it has been done in previous trail construction projects with much success. ORDA staff is experienced in ski trail and lift construction including erosion control techniques. They will use the following measures to mitigate the potential impacts of trail construction.

Limit individual disturbance areas to less or equal to 1 acre at any time.

- Tree trunks will be removed and used on site either as part of trail construction or cut up and used for firewood.
- Logs will be used on constructed trails to create cribbing to help stabilize the down gradient slope.
- Where possible, tree stumps will be cut flush to the ground to minimize the
 impact to the existing root systems and to allow the quick establishment of
 vegetation. Emphasis to minimize cutting, filling and grubbing operations on
 slopes over 25 percent will be made.
- Grubbed stumps will be buried within the trail as part of trail construction (filling low spots, etc.)
- Branches and tops will be chipped with chips broadcast into adjoining wooded areas. Chip piles shall not be created in wooded areas.
- Install sediment and erosion control practices.
- On constructed trails, which involved cut/fill operations, exposed earth areas will be contained by diverting clean runoff from the uphill side with water bars as much as practicable.
- Silt fence and/or chip berms on the downhill side will be utilized to filter the runoff from the raw site.
- During final grading, all water bars will be repaired in order to effectively intercept and divert water from new trails and lift areas.
- Areas where finish grade has been established will be seeded and mulched within 3 days. No areas shall be left with raw earth exposed for more than 7 days.

Lift Terminals Construction

Lift terminal construction is located in flat to low slope areas and are limited to approximately ¼ acre in size. E&SC practices include silt fence, upgradient water bars, and vegetative stabilization. RECP will be installed on the graded outruns of the upper lift terminals.

Lift Line Construction

The scope of lift line construction operations is similar, but less intense, than most trail clearing operations. Construction of the lift line corridors will involve:

- Cutting trees to provide a 60 feet wide area with sufficient clearance.
- Stumps are cut flush to the ground.
- Grading operations are limited to the areas immediately around lift tower footings and where vehicle access is required. In these locations E&SC practices include silt fence, upgradient water bars, and vegetative stabilization.
- Ground cover vegetation will be undisturbed to the extent possible.

- Areas requiring site disturbance will be stabilized using practices described above.
- Wooded areas which are cut will be allowed to naturally fill in with brushy type growth where no ski trails or service driveways are to be created.

Linear Utilities

Linear utilities include underground water pipe, air lines, and electric lines. Erosion from pipeline construction will be minimized by limiting the length of the open trench to 1200' for a period not to exceed 10 days. Sand or gravel bags trench plugs will be placed in sloped trenches at a minimum of 300' intervals to slow the velocity of stormwater runoff that may enter the trench.

Areas where finish grade has been established will be seeded and mulched within 3 days. No areas shall be left with raw earth exposed for more than 10 days.

3. Topography and Slope

Potential Impacts

See Figure 29, Topography and Management Actions.

Very limited grading is required for new ski trails, trail widening or ski lifts. Trails are laid out to follow natural fall lines. Lift grading is limited to the upper and lower terminals and at the tower foundations.


Grading will be required to create the building pad for the groomer garage as well as for sections of the shuttle lane. See **Figure** 14 Master Plan – Approved and Proposed Actions (Base Lodge) and **Figure** 26, Shuttle Lane Plan.

Significant grading (excavation) is proposed for the enlargement of the snowmaking reservoir.

Impacts associated with grading involve erosion and sediment control (see the previous section) and protection of water resources (see the following sections).

Mitigation Measures

No mitigation measures beyond those described in the previous section and in the following section are required.



Water Resources

Potential Impacts

See **Figure** 30, Surface Water, Wetland Resources, and Proposed Actions.

Identified potential impacts to surface water are (1) sedimentation of eroded soils, (2) increased stormwater runoff with accompanying loadings (nutrients, dissolved solids, etc.), and (3) exposure of disturbed soils in the snowmaking reservoir expansion area along with separating clean inflow waters from the active construction areas during reservoir excavation.

Mitigation Measures


Those measures that will be implemented to prevent erosion and subsequent sedimentation were described previously in the Soils section.


The new management actions include only two actions that will introduce significant amounts of new impervious surfaces that will increase stormwater runoff. These are the new groomer garage and those portions of the shuttle lane that will be outside of existing parking areas and drives. A Stormwater Management Report has been prepared for these two actions. See **Appendix** 7.

The Project has been designed in accordance with Chapter 4 of the NYSDEC Stormwater Management Design Manual (SWMDM), and NYSDEC's General Permit GP-0-15-002 for construction activities. Stormwater calculations were performed utilizing widely accepted engineering methodologies, including TR-55, and the stormwater modeling computer program HydroCAD (version 10.00) produced by HydroCAD Software Solutions, LLC.

Under the watershed's proposed condition, all stormwater from the Project will continue to discharge to the same point as in the existing condition (Analysis Points 1 & 2). The total watershed has generally remained unchanged, as is shown on the drawing "W-2 Proposed Conditions Watershed Map" contained in **Appendix** 7. To meet NYSDEC requirements (see Section 5.0 NYSDEC Design Criteria in **Appendix** 7) a bioretention basin and wet swale have been incorporated into the stormwater management design to mitigate the quality and quantity of stormwater runoff discharged from the Project Site.

For the snowmaking reservoir expansion, see **Figure** 31, Snowmaking Reservoir Construction Sequencing. First the reservoir will be fully drained. See the photo below.








Development Authority 2634 Main Street Lake Placid, New York 12946

Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement



31



Mostly drained snowmaking reservoir September 9, 2017

Once the reservoir is drained a haul road stabilized outlet will be created in the southeast corner of the reservoir where remnants of a haul road currently exist. Next, a rip rap stream channel will be constructed to convey water from the main reservoir stream inlet to the outlet structure. The intent is to isolate and pass through reservoir inflow from the inlet while the reservoir is being excavated. Two 24 foot wide haul roads would then be constructed in order to remove excavated materials from the north and south ends of the reservoir. Excavation work will proceed from west to east. Once excavation is complete, the outlet valve will be closed and the reservoir will be allowed to gradually fill. This gradual filling should allow for the settling of solids that become suspended during pond refilling. Exposed soils will be mostly fine sands that will tend not to stay in suspension as compared to silts or clays.

5. Wetlands

Potential Impacts

None of the new management actions proposed in the UMP Amendment will impact wetlands. Avoidance of wetland impacts in the areas of the grooming garage, the shuttle lane and the snowmaking reservoir was accomplished by field evaluation for the presence of wetlands and then designing these components to avoid wetlands. Periphery wetlands at the snowmaking reservoir will experience temporary hydrological alteration when the reservoir is emptied. This will not significantly impact wetlands since the effects will be temporary and since these wetlands have persisted when the reservoir has regularly been emptied in the past for inspection and maintenance purposes. Additional information regarding wetland avoidance can be found in Section 6, Alternatives.

Mitigation Measures

No significant adverse impacts have been identified, therefore, no mitigation measures are required.

6. Climate and Air Quality

Potential Impacts

No new permanent sources of air emissions are proposed as part of this UMP.

Gore Mountain Ski Center has a current NYSDEC Air Quality Permit for which they are compliant.

Construction activities that can take place after this UMP amendment is adopted may result in localized increases in dust levels. However, areas of proposed construction are located within the interior of the Intensive Use Areas, so no offsite areas will be affected.

Many ORDA venues exist within the boundaries of State protected lands and the impact of climate change on our environment is recognized. ORDA will be a leader in environmental stewardship with consistent commitment to sustainability, responsible development practices, and continuous communication with DEC, APA, and other regulatory agencies to ensure we are taking the appropriate measures.

Mitigation Measures

No significant adverse impacts have been identified, therefore, no mitigative measures are necessary.

B. Biological Resources

1. Vegetation

Potential Impacts

See Figure 32, Vegetation and Management Actions.


Tree clearing associated with the new management actions includes 18.1 acres for downhill ski trails (9.4 on the current Intensive Use Area lands and 8.7 acres in the lands that would be added from the VMWF reclassification), 9.2 acres for trail widening, 3.1 acres for ski lifts, 0.8 acres for the groomer garage, and 6.5 acres for the shuttle lane. An area around maintenance and Lifts 9A and 9B previously approved in 1995 is no longer proposed. The 7.3 acres of clearing in this area is no longer proposed.

Appendix 8 contains an accounting of the numbers of trees proposed to be cut. These data are summarized in **Table** 7 below.

Table 7
Tree Cutting by Location and Community Type

				Total
Location	Community	Action(s)	Acreage	Trees
Gore Mtn IUA	B (mixed hardwood)	Burnt Ridge Trail (partial)	4.2	1,565
Gore Mtn IUA	E (mixed hardwood)	Burnt Ridge Trail (partial) + Trails 11A, 1N- P	6.9	4,447
Gore Mtn IUA	Q (pioneer hardwood)	Twister Widening	1.1	415
Gore Mtn IUA	P (northern hardwood)	Various	15.4	3315
			SUBTOTAL	9,742
Land Reclassif.	E (mixed hardwood)	Lift 12 and Trails 12	10.2	6,574
			TOTAL	16,316

A total of 9,742 trees are proposed to be cut on lands that are currently classified as Intensive Use Area. Approximately 25% of these will be 3-4"dbh and the remainder will be >4" dbh. (Gore Mountain UMP documents, starting with the 1995 Update and Amendment (in Appendix 21), have used the 3-4" and >4" breakdown of trees to be cut.)



Activities shown on lands that could get added to the Intensive Use Area from VMWF would require the cutting of 6,574 trees. Approximately 44% of these would be 3-4"dbh and the remainder would be >4" dbh.

To put these tree cutting numbers in perspective, the total amount of lands affected in the table above is 10.2 acres in the intensive use area which totals approximately 3,755 acres. The amount of affected land is less than 1% (0.7%).

There is no tree cutting proposed above 2,800 feet in elevation or in any areas of Mountain Spruce-fir forest.

All tree cutting will be done in compliance with the DEC tree cutting policy LF-91-2.

No rare, threatened or endangered plant species will be impacted.

Mitigation Measures

Only areas absolutely necessary for construction of ski trails, ski lifts, and other proposed improvements will be cleared of vegetation. All other areas will be maintained in a natural state.

Erosion control measures will be used on cleared areas with disturbed soils to avoid affecting adjacent vegetation by erosion or siltation. Erosion-control devices to be used will include filter fabric fences and staked straw bale filters.

Upon the completion of clearing of new ski trails and ski lift corridors, they will be seeded with grass mixtures to promote rapid revegetation. Areas disturbed for any other improvements will also be landscaped and revegetated as soon as practicable.

Plants used to revegetate disturbed areas and planted as part of landscaping will be species which are indigenous to the region.

No clear-cutting of trees to develop panoramic views is proposed. Views will be framed or filtered by existing vegetation.

Continue to train staff working at Gore Mountain unit to identify and document the location of key invasive plant species.

Work towards a complete comprehensive inventory of the presence and extent of invasive plants in the unit.

Eliminate any identified populations of invasive plant species that are discovered in the unit. These actions may be carried out by DEC personnel or by members of APIPP or other volunteers under supervision of DEC through an Adopt-a-Natural Resource Agreement.

Gore Mountain Section V - 14

Wildlife

Potential Impacts

The actions proposed in this UMP are expected to have minimal impacts on wildlife. Proposed management actions are spread over the landscape of the existing developed ski trails and lifts. New management actions are proposed at low elevations on the mountain.

Trail widening projects, including the green trails, involve existing trails. This will result in the loss of some currently treed areas along the edge of existing ski trails and move the forest edge slightly outward.

Replacing and relocation the Sunway Lift will occur in the immediate vicinity of the existing lift.

The new lift 9B will parallel the existing Lower Sunway trail and much of it will occur in an already cleared area.

Enlarging the snowmaking reservoir will entail converting 1.6 acres of shoreline wooded areas to open water.

The new groomer garage will require some tree removal in an area that has existing work roads on two sides and an existing ski trail on a third side.

The NYSEF building expansion will occur in a grassy area immediately adjacent to the existing building.

The improvements associated with the dedicated shuttle lane take place in and around existing parking areas and the existing access road and will have minimal wildlife habitat impact.

Mitigation Measures

No significant adverse impacts have been identified, therefore, no mitigation measures are required.

3. Fisheries

Potential Impacts

The only proposed management action that involves aquatic resources is the expansion of the snowmaking reservoir.

Significant adverse impacts to fisheries resources are not expected to occur as a result of reservoir drawdown for construction of the expansion. There may be some temporary short-term impacts to the fisheries resource within the reservoir proper, but these resources have

developed and persisted while the reservoir is regularly drained for inspection and maintenance activities. Downstream fisheries will not be impacted since water will continue to pass through the pond as described previously above and in Section 4.

Mitigation Measures

See the earlier section entitled Water Resources for a description of how the flow of clean inflow through the pond will be maintained in the snowmaking reservoir during the expansion process. The same section describes how the reservoir will be allowed to fill gradually after expansion is complete in order to allow for settling out of suspended solids within the reservoir before the reservoir begins to flow over the spillway.

4. Unique Areas

Potential Impacts

There are no unique biological areas present.

Mitigation Measures

No significant adverse impacts have been identified, therefore, no mitigation measures are required.

5. Critical Habitat

Potential Impacts

See **Figure** 33, Potential Bicknell's Thrush Habitat and Management Actions. No new management actions are proposed to occur above 2,800 feet in elevation. There will no impact to the Adirondack Sub Alpine Forest Bird Conservation Area.

Mitigation Measures


Any carryover actions from previous UMPs that require construction activities above 2,800 feet in elevation will not commence prior to August 1 of any year.

C. Human Resources

1. Visual Resources

Potential Impacts

The actions proposed in this UMP are expected to have minimal visual impacts. The existing ski area is already visible from some area roadways. Proposed actions are spread across the landscape of the existing developed ski trails and lifts. New management actions are proposed at low elevations on the mountain.



Trail widening projects involve existing trails. For any trails that are currently visible from off site, the visual effect of minor widenings will be essentially imperceptible.

Replacing and relocating the Sunway Lift will occur in the immediate vicinity of the existing lift.

The new lift 9B will be low on the mountain and will parallel the existing Lower Sunway trail. The widening of the green trails will occur at low elevations not visible from off site.

The snowmaking reservoir is not visible from outside the Intensive Use Area.

The new groomer garage will be located in a low elevation wooded area. Although it will be visible on-site, it will not be visible from off site

The NYSEF building is not visible from off site.

The improvements associated with the dedicated shuttle lane take place in and around existing parking areas and the existing access road that are not visible from off site.

Mitigation Measures

No significant adverse impacts have been identified, therefore, no mitigation measures are required.

2. Transportation

Potential Impacts

The proposed management actions do not include any significant expansion of mountain facilities, such as the addition of a new pod of ski trails, that would result in significant increases in peak hour traffic generation.

Mitigation Measures

No significant impacts have been identified, therefore, no mitigation measures are required.

3. Community Services

Potential Impacts

The project primarily involves improvements to existing facilities designed to retain the existing skier base and increase the future number of skiers, hikers and bikers at Gore Mountain. It is anticipated that there will be a minor incremental increase in demand for community services such as fire, police, rescue, solid waste and health care due to the gradual increase in the number of visitors to the mountain. Many of the improvements are designed to build visitation during the off-seasons of spring, summer and fall thereby distributing the potential impacts

Gore Mountain Section V - 17

over a 12 month period. The Ski Center presently makes very little demand on most services and the increase in such demand is anticipated to be small and can be accommodated by the service providers.

The North Creek Health Center was developed and the Warrensburg Health Center was recently expanded to respond to the growing need for services in local communities and businesses in the region. The potential long-term and incremental increase in visitors may increase the demand for medical care slightly and these facilities are capable of meeting any increased demand. The Glens Falls Hospital is also prepared to handle a minor increase in patients to the emergency room.

The extra revenue derived from EMS calls from skiers, hikers and mountain bikers helps offsets the year-round costs and therefore has a positive impact on the people who live and pay taxes in Johnsburg.

Mitigation Measures

No mitigation measures are necessary since no negative impacts have been identified.

4. Local Land Use Plans

Potential Impacts

The actions in the UMP Update are consistent with local planning documents including the 2005 Johnsburg Comprehensive Plan and the 2007 Town of Johnsburg Zoning Law/LLUP that serve to guide community planning. Both documents seek to forge stronger links between the Gore Mountain Ski Resort, the North Creek Ski Bowl, and the hamlet of North Creek, all of which are goals of Gore Mountain, ORDA and this UMP Amendment.

The UMP Amendment contains specific actions designed to encourage skiers to use both ski areas thereby increasing the overall number of skiers at both Gore Mountain and the Ski Bowl. ORDA has cooperated with North Creek in developing hiking, cross-country ski and mountain bike trails with the goal of connecting Ski Bowl Park and Gore Mountain lands.

The actions on State land authorized by this UMP Amendment will not have any effects on adjoining or nearby private lands inconsistent with local land use controls such as the Johnsburg Zoning Law and the North Creek Action Plan that serve to guide community planning. The districts and densities outside of the hamlet are exactly matched to the official APA Land Use Map. Gore Mountain Ski Center is entirely within the Intensive Use Area which was created intentionally for such a special use. Both documents seek to forge stronger links between the ski center and community, which are also goals of ORDA and this UMP Update.

While the improvements and expansion of skier facilities on the mountain will not directly affect planning and zoning in the community, it will create the potential for new skiers who will

require services in and around the hamlet of North Creek and some may choose to buy or build a second home in the area. Linkage and added amenities at Gore Mountain and Ski Bowl will also stimulate additional skier visits to the area and ultimately increase the number of consumers at local businesses. These are potential positive impacts for the local economic base and will serve to stabilize certain businesses, expand some businesses and create new businesses.

Mitigation Measures

No mitigation measures are necessary since no negative impacts have been identified.

5. Historical and Archaeological Resources

Potential Impacts

Appendix 3 contains a November 9, 2017 letter from NYS Office of Parks Recreation and Historic Preservation stating that there will be no impacts to archeological or historic resources.

Mitigation Measures

No mitigation measures are necessary since no negative impacts have been identified.

SECTION VI ALTERNATIVES

A. Alternative Trail Improvements

There are limited alternatives to the trail construction and trail widening proposed within this UMP Amendment.

When evaluating potential trail connections that would provide an alternative intermediate route from Burnt Ridge back to the Base Area on days when Echo is closed due to ski racing, three (3) separate alternatives were considered before determining the preferred route. The first alternative considered starting the new trail from the top part of Echo on skiers left, then running it generally parallel to Echo before connecting back to Echo at the bottom where the trail turns north into the base area. This alternative was not pursued primarily due to the frequency of steep and difficult terrain. The terrain was not suitable as intermediate terrain and would have resulted in extensive construction efforts to achieve a desired grade and alignment.

The second alternative considered starting the new trail from the top part of Echo, on skier's right at the first bend, then running southeast and connecting to Twister. While the terrain in this area was suitable as intermediate terrain with appropriate construction efforts, the trail would not have been able to be open on days where ski race training was occurring on Twister, which closes Twister to the skiing public. As a result this trail would not have provided a reliable intermediate connection from Burnt Ridge to the Base Area, and the length of new trail would've been shorter than desired, providing only a short section of new skiing terrain.

The third and preferred alternative connects from the top of Sagamore on skier's right, and continues southeast to the bottom of Echo where it turns towards the base area. This alternative was selected due to the suitability of terrain as intermediate terrain, the ability to connect to and utilize a previously approved trail (not yet constructed), that provides an option to ski back to the bottom of Burnt Ridge, the length of new skiing terrain offered by this alignment, and ability to provide the desired connection from the top of Burnt Ridge back to the base area on days when Echo is closed due to racing.

B. Alternative Lift Configurations

The expanded beginner terrain could conceivably be served by just the replacement and relocation of the Sunway Lift (lift 3) with the addition of the new lift 9B.

The relocated Sunway lift, in and by itself, could continue to serve the existing beginner terrain along with those beginner trail improvements proposed in this UMP Amendment. However, beginner skiers would still be faced with terrain that they may find too challenging. As discussed previously in this document, skiers that offload at the top of the Sunway Lift, even though it is being relocated primarily for skier safety reasons, need to begin skiing on more challenging (steeper) terrain than what is present lower on the Sunway trails.

Gore Mountain Section VI - 1

By providing the new Lift 9B which offloads lower on the mountain, the beginning skier has the option of choosing this lift as the first one they ride, as opposed to using the Sunway lift. By using Lift 9B and skiing the easier terrain on Lower Sunway, beginning skiers can then gain confidence and experience that they may otherwise need to ski the terrain served by the higher up Sunway Lift.

C. Alternative Parking/Circulation Improvements

An alternative to the currently proposed shuttle system was proposed in the 2005. The currently proposed shuttle route involves less construction in currently wooded areas and would be less impacting than the alternative proposed in 2005. The 2005 alternative include more "overland" travel between the parking lots and the base lodge than what is currently proposed. The current alternative more closely follows the existing access roads and perimeters of the existing parking lots.

D. Alternative Appurtenances

The primary new management action appurtenances in this UMP Amendment are the relocated groomer garage and an expanded snowmaking reservoir.

Groomer Garage

The alternative of locating the new garage to the east and downhill of the existing work road, which would place it slightly closer to the existing maintenance complex, was examined. Field study showed that there are wetlands and some surface waters south of the work road which make this alternative location undesirable.

The alternative of locating the groomer garage a little more to the south was also examined in the field. This area has slightly steeper and irregular topography in comparison to the proposed location. This would likely result in a greater area of site disturbance in order to construct the garage. This alternative location would also increase the overall footprint of the maintenance complex which would result in a slight decrease in operational efficiency.


Snowmaking Reservoir

Figures 34 through 39 illustrate the options (alternatives) that were evaluated. Each alternative is described below.

The existing snowmaking reservoir covers approximately 5.2 acres with approximately 19 Mgal of storage.

Alternative 1 (**Figure** 34) involves maintaining the existing 5.2 acre foot print and grading the reservoir sideslopes to all be 3:1. This would increase the storage capacity by 4.5 Mgal to 23.5 Mgal.

Gore Mountain Section VI - 2







Olympic Regional **Development Authority**


2634 Main Street Lake Placid, New York 12946



Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement




Scale:	1"=60
Design:	МЈТ
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037








Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement




Date: Scale:	November 6, 2017 1"=60"
Design:	МЈТ
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037








Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement



Date:	November 6, 2017
Scale:	1"=60"
Design:	МЈТ
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037










Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

Date:	November 6, 2017
Scale:	1"=60"
Design:	МЈТ
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037











Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement



Scale:	1"=60"
Design:	МЈТ
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037










Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

Snowmaking Reservoir Expansion - Alternative 6



Scale:	1"=60"
Design:	МЈТ
Drawn:	KMK
Ch'k'd:	KJF
Project No.:	2015037

Alternative 2 (**Figure** 35) involves the 3:1 slopes from Alternative 1 and expanding the pond to the west in the area of the primary inlet. This would be the one of most "constructable" alternatives. This expansion would have increased the reservoir surface by approximately 2.6 acres and added an additional storage volume of 15.3 Mgal for a total reservoir volume of 38.8 Mgal, close to the desired 40 Mgal. However, as shown on **Figure** 35, this alternative would require some extensive material alteration to the wetlands delineated around the reservoir.

Alternative 3 (**Figure** 36) is a variation on Alternative 2 and would have involved additional expansion in the southwest corner of the reservoir. This alternative would provide to 40.8 Mgal of storage, but would continue to require material alteration of wetlands.

Alternative 4 (**Figure** 37) is another variation on Alternative 2 and would have involved additional expansion in the northwest portion of the reservoir. The results would have been a storage capacity of 39.6 Mgal and material alteration of wetlands.

Alternative 5 (**Figure** 38) is a variation of Alternative 2 that only involves the expansion on the northwest corner of the reservoir. Storage volume would be 33.3 Mgal, it would avoid the wetlands in the main inlet area, but there are wetlands separate from and to the south of the reservoir that would be affected.

Alternative 6 (**Figure** 39) is a variation on Alternatives 1, 3 and 4. Under this alternative the storage volume would be increased to 30.1 Mgal and material alteration of wetlands is avoided.

E. The No-Action Alternative

If the no-action alternative were pursued, none of the new management actions proposed in this UMP Amendment would be given consideration. Any management actions approved in earlier adopted UMPs, but not yet constructed/implemented, could remain in effect and can continue to be implemented.

The no-action alternative could mean that the following goals set by ORDA for Gore Mountain may not be attainable:

- Gore Mountain will seek to modernize facilities at Gore in order to enhance the guest experience, improve skier safety, and increase local and regional economic benefits, while maintaining environmental quality.
- Gore Mountain will seek to increase the capacity of the ski area in concert with other modernization objectives in order to provide a higher quality skiing experience.
- Gore Mountain will seek to improve its economic return by making the mountain more attractive to skiers, and thus increasing ticket sales.

Gore Mountain Section VI - 3

- Gore Mountain will seek to improve skier safety and enjoyment by widening certain trails and improving certain trail intersections.
- Gore Mountain will seek to improve trail selection and create a better balance among trails in order to appeal to a greater cross-section of the skiing market by increasing the number of trails for the beginning and advanced skier.
- Gore Mountain will seek to develop new summer and fall usage of the Ski Center to provide greater year-round use of the facility by the public, consistent with Article 14 and the SLMP.
- Gore Mountain will implement a capital improvements program to achieve the above objectives.
- Gore Mountain will seek to improve infrastructure reliability in order to reduce the high frequency of breakdown, excessive staffing requirements and consequent financial drain.
- Gore Mountain will seek to reduce its operations and maintenance costs by replacing outdated and aged equipment.

SECTION VII SUMMARY OF UNAVOIDABLE ADVERSE ENVIRONMENTAL IMPACTS

Some of the potential environmental impacts of the proposed project cannot be prevented or reasonably avoided.

7.1 Construction Phase

Construction activities inevitably result in temporary impacts including: visual, noise, vibrations, dust, fumes and odors.

During construction, while vegetation is disturbed there is an increased risk of erosion during stormwater events and a resulting adverse impact in surface water quality. As a result, the water quality in nearby receiving waters may be impacted during the course of construction due to possible erosion of excavated areas. Preparation of project-specific Stormwater Pollution Prevention Plan (SWPPP) for construction activities using the mitigation measures described in Section V.A.2 will minimize these impacts.

Construction will involve clearing of vegetation for the construction of trails, buildings, shuttle lanes and other proposed facilities. Clearing results in habitat loss that could increase runoff and adversely impact wildlife. (See Section 2 for an explanation of the Environmental Setting, and Section 5 for Potential Impacts and Mitigation Measures) While there will be tree cutting required for ski trails, tree cutting is minimized to the extent feasible and the footprint of the proposed trails are within State constitutional limits.

There may be a localized impact to air quality from dust during construction, however, this potential impact will be temporary and will not extend outside of the Intensive Use Area.

7.2 Operational Phase

There will be an incremental increased use of surface water resources for snowmaking water supply. Previous UMP studies have demonstrated that the Hudson River source capacity can easily provide additional water without any significant adverse impacts.

Wildlife may be impacted as a result of permanent removal of vegetation. As previously stated, tree cutting required for the construction of new ski trails and for trail widening is within constitutional limits.

Slightly increased attendance and operational activities as a result of the project will cause a corresponding slight increase in traffic levels, but peak hour traffic is not expected to significantly increase. The use of the shuttle system could also possible counteract slight increases in attendance by extending the duration of arrival and departures thus reducing peak traffic levels.

Gore Mountain Section VII - 1

SECTION VIII IRREVERSIBLE AND IRRETRIEVABLE COMMITMENTS OF RESOURCES

The extent to which a proposed action may cause permanent loss of one or more environmental resources should be identified as specifically as possible based upon available information. Resources which should be considered include natural and man-made resources that would be consumed, converted or made unavailable for further uses due to construction, operation, or use of the proposed project, whether those losses would occur in the immediate future, or over the long term.

The management actions contained in this UMP Amendment do not involve any significant, irreversible or irretrievable commitment of natural resources under the footprint of the proposed new or widened ski trails or the new or relocated ski lifts. The footprint of the new groomer garage and expansion of the NYSEF building represent a small commitment of these areas to built structures.

Site work would involve the removal of existing vegetation and would disturb on-site soils. It is not believed that such impacts are significant. No rare, threatened or endangered species are known to inhabit the site.

There would be a commitment of raw materials for construction of the structures, including concrete, steel, gravel, and wood. Energy resources would be required for the construction, operation and maintenance of the expanded facility.

Gore Mountain Section VIII - 1

SECTION IX GROWTH INDUCING, SECONDARY AND CUMULATIVE IMPACTS

This section evaluates the effects of the proposed ski area improvements as they relate to the potential for such improvements to stimulate secondary impacts including an increase in local population, demand for support facilities and commercial and residential development. These secondary impacts would occur if the economic stimuli from the project generated economic activity that would result in significant growth in local populations, labor pools or demands on local services which is not expected to occur.

While the economic effect of the proposed management actions is expected to be positive, growth inducing and secondary impacts are expected to be minimal. The proposed management actions are not geared towards significantly increasing attendance at Gore Mountain. Instead, the proposed improvements are aimed retaining existing skiers and at enhancing beginner facilities to introduce more people to skiing and snowboarding and hopefully recruiting new future participants in the sports at Gore Mountain. Other improvements are geared to improving existing guest services and improving mountain operations which are not necessarily intended to cause significant increases in attendance. Spending in the local community by an increased number of patrons will provide a positive economic stimulus, but since most of the skiers will be day-visitors, the level of spending would not result in the increase in local business that occurred after the major expansion from the activities included in the 1995 UMP.

The proposed project may have some minor influence on the second home market in the nearby towns. The improvements at the Ski Center may improve the desirability of second homes in the area. This increase in desirability may translate to a slight increase in demand for, and price of, vacation homes in the area. However, this increase in demand is expected to be very minor because the Ski Center has already been in operation for many years and the incremental change in recreational facilities as a result of this project will be relatively small.

ORDA is currently contemplating simultaneous improvements on Town of Johnsburg owned lands at the North Creek Ski Bowl, outside of the Intensive Use Area. Because these actions are not within the Intensive Use Area, they are not covered within this UMP Amendment. Instead, these actions will be subject to APA review under section 814 of the Adirondack Park Agency Act and also subject to review under SEQRA. In order to make the requisite assessment of cumulative impacts, this UMP Amendment/GEIS is accompanied by two companion documents which will be referred to as Part B and Part C (Part A being the UMP/GEIS). Part B is the Notice of Intent to the APA required under section 814 APA Act, including accompanying SEQRA documentation. Part C is the cumulative impact assessment of the actions proposed within the Intensive Use Area and the actions proposed at the Ski Bowl.

SECTION X EFFECTS ON THE USE AND CONSERVATION OF ENERGY

Recent past activities and future activities being undertaken at Gore Mountain will have a positive effect on the use and conservation of energy.

In the construction phase, additional energy will be consumed primarily in the form of fossil fuels to power the required construction equipment and to transport construction workers to and from the site. This will result in a temporary increase in the use of energy.

Gore is contracting two 25-year solar power purchase agreements, which combine into a massive 5.325 MW system. Using remote net metering, 85% of Gore's electrical is poised to be offset. In cooperation with Borrego Solar, Gore Mountain is efficiently harvesting sunlight for its energy needs, utilizing 14,589 ground-mounted solar panels across 20 acres of otherwise fallow farmland. The electricity generated credits Gore's meter at a rate higher than power that is traditionally produced, while providing a cleaner, more sustainable source of energy to its electric distribution zone. The agreement is projected to save Gore Mountain approximately \$10 million over the life of the contract, while offsetting 113,919 tons of carbon dioxide, 71,634 pounds of nitrogen oxide emissions, and 131,835 pounds of sulfur. Gore's purchase agreement received support from Governor Cuomo's NY-Sun incentive through the New York State Energy Research and Development Authority (NYSERDA).

In June 2016 Gore Mountain issued a Sustainability Analysis a copy of which is in **Appendix** 9. This analysis contained a section on electricity and fuel, including the following.

Diesel is used for powering maintenance equipment, snowmaking compressors and grooming equipment and for operating ski lifts during power outages. Trucks and buses are also fueled by diesel. Off-road diesel use has been reduced significantly over the last 8 years and that trend will continue. On-road diesel has had a slight average increase over the past 8 years due, primarily, to an increase in vehicles, including the shuttle bus fleet which has been accommodating the growing number of guests. Gore is actively investigating modernization of existing fleets with new technologies including electric grooming machines and hybrid buses.

Gasoline is used to operate snowmobiles for ski patrol and snowmaking as well as vehicles for travel to trade shows, meetings and conferences. There has been a slight downward trend in gasoline use over the last 8 years.

Gore Mountain propane usage had a dramatic increase after the 2007/2008 fiscal year due to the addition of the Northwoods Lodge, conversion of the base lodge's heat from fuel oil, and the addition of two more commercial kitchens. Propane is used to heat almost all of Gore Mountain's buildings, with the exception of Saddle Lodge which uses a wood stove and electric heat. The usage trend for propane is relatively flat and primarily dependent on the weather. A green heat initiative is targeted for future improvement in propane use reduction.

While electricity powers the lifts at Gore Mountain, the largest use of it is for snowmaking compressors and pumps. Gore has substantially reduced the amount of kilowatt hours (kWh) used during the last four fiscal years and the plan is to maintain this trend by continuing to replace traditional snowmaking with modernized, high efficiency guns. Gore is also modernizing their compressors with improved, more efficient drives and changing most lighting to motion sensing and high efficiency bulbs or LEDs.

Gore Mountain Section X - 2

Appendix 1 SEQRA Full Environmental Assessment Form Parts 1, 2 and 3

Full Environmental Assessment Form Part 1 - Project and Setting

Instructions for Completing Part 1

Part 1 is to be completed by the applicant or project sponsor. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification.

Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information; indicate whether missing information does not exist, or is not reasonably available to the sponsor; and, when possible, generally describe work or studies which would be necessary to update or fully develop that information.

Applicants/sponsors must complete all items in Sections A & B. In Sections C, D & E, most items contain an initial question that must be answered either "Yes" or "No". If the answer to the initial question is "Yes", complete the sub-questions that follow. If the answer to the initial question is "No", proceed to the next question. Section F allows the project sponsor to identify and attach any additional information. Section G requires the name and signature of the project sponsor to verify that the information contained in Part 1 is accurate and complete.

A. Project and Sponsor Information.

Gore Mountain Intensive Use Area 2017 Unit Management Plan (UMP) Amendment Project Location (describe, and attach a general location map):			
Project Location (describe, and attach a general location map):			
Peaceful Valley Road, T/O Johnsburg, Warren County			
Brief Description of Proposed Action (include purpose or need):			
The following new Management Actions will be included in the UMP:Widen Sunway an pottom of Rumor from Lies to the other side of Hawkeye, Create a beginner/intermedia Create a beginner/intermediate trail connection in the vicinity of the Abenaki and Barke Trail, Verify current mileage of existing ski trails, Add new triple or quad chair (Lift 9B) cower Sunway, Replace and relocate existing Sunway Lift (Lift 3) with a triple or quad to land past the top of Otter Slide, Modify 1995-approved shuttle lane separated from a parking, Expand NYSEF building, Reconfigure 1995-approved maintenance complex to Examine the possibility of enlarging the snowmaking reservoir, Install new 24 inch grav Construct a single track bike trail loop for Town trail at the top of Little Gore, Develop a Intensive Use Area, Vanderwhacker Wild Forest and Siamese Wilderness which could	te trail on Echo connecting to the ater Glades, Reestablish alpine from Northwoods Lodge up Low to the south along the old Gond and independent of main traffic to locate groomer garage and furity water line from the snowmal hiking center, Land classification	he base area in the cut above Gully, e skiing on a portion of Rabbit Pond wer Sunway to just past the bend in lola line extending the upper terminal route and circulation route and leling adjacent to Sunway trail, king reservoir to the pump house, on exchange between Gore Mountain	
Name of Applicant/Sponsor:	Telephone: (518) 302	2-5332	
NYS Olympic Regional Development Authority	E-Mail: bhammond@	E-Mail: bhammond@orda.org	
Address: Olympic Center, 2634 Main Street			
City/PO: Lake Placid	State: NY	Zip Code: 12946	
Project Contact (if not same as sponsor; give name and title/role):	Telephone:	,	
Robert Hammond, Director of Environmental, Planning and Construction	E-Mail:	E-Mail:	
Address:	,		
City/PO:	State:	Zip Code:	
Property Owner (if not same as sponsor):	Telephone: (518) 402	2-9405	
State of New York	E-Mail: LF.Lands@d	lec.ny.gov	
Address: Governor Alfred E Smith Office Building			
City/PO: Albany	State: NY	Zip Code: 12239	

B. Government Approvals

B. Government Approvals assistance.)	s, Funding, or Spor	nsorship. ("Funding" includes grants, loans, ta	ax relief, and any othe	r forms of financial
Government I	Entity	If Yes: Identify Agency and Approval(s) Required	Applicati (Actual or	
a. City Council, Town Boar or Village Board of Trust				
b. City, Town or Village Planning Board or Comm	□Yes ☑ No nission			
c. City Council, Town or Village Zoning Board of	□Yes ☑ No Appeals			
d. Other local agencies	□Yes☑No			
e. County agencies	<u></u> Yes ∠ No			
f. Regional agencies	Z Yes□No	NYS APA - APSLMP Compliance	2017	
g. State agencies	∠ Yes □No	NYSDEC - UMP Approval	2017	
h. Federal agencies	□Yes☑No			
i. Coastal Resources.i. Is the project site with	iin a Coastal Area, o	or the waterfront area of a Designated Inland W	/aterway?	□Yes ∠ No
ii. Is the project site locaiii. Is the project site with		with an approved Local Waterfront Revitaliza Hazard Area?	tion Program?	□ Yes ✓ No □ Yes ✓ No
C. Planning and Zoning				
C.1. Planning and zoning				
only approval(s) which mus • If Yes, complete se	st be granted to enabections C, F and G.	mendment of a plan, local law, ordinance, rule ble the proposed action to proceed? helplete all remaining sections and questions in I	-	□Yes ☑ No
C.2. Adopted land use plan	ns.			
a. Do any municipally- adop where the proposed action	•	lage or county) comprehensive land use plan(s) include the site	Z Yes□No
		ecific recommendations for the site where the p	proposed action	∠ Yes□No
	Area (BOA); design	ocal or regional special planning district (for exated State or Federal heritage area; watershed		∠ Yes□No
c. Is the proposed action loc or an adopted municipal If Yes, identify the plan(s):		ially within an area listed in an adopted municin plan?	ipal open space plan,	□Yes Z No

C.3. Zoning	
a. Is the site of the proposed action located in a municipality with an adopted zoning law or ordinance. If Yes, what is the zoning classification(s) including any applicable overlay district? N/A, lands of NYS	✓ Yes No
b. Is the use permitted or allowed by a special or conditional use permit? N/A	□Yes□No
	Yes ☑ No
If Yes, i. What is the proposed new zoning for the site?	
C.4. Existing community services.	
a. In what school district is the project site located? Johnsburg Central	
b. What police or other public protection forces serve the project site? NYS Police, Warren County Sherriff	
c. Which fire protection and emergency medical services serve the project site? Johnsburg FD	
d. What parks serve the project site? Adirondack State, Town Ski Bowl	
D. Project Details	
D.1. Proposed and Potential Development	
a. What is the general nature of the proposed action (e.g., residential, industrial, commercial, recreational; if mixed, in components)? Recreational	nclude all
b. a. Total acreage of the site of the proposed action? +/-3,766 acres b. Total acreage to be physically disturbed? +/-39 acres	
c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor?	
c. Is the proposed action an expansion of an existing project or use? i. If Yes, what is the approximate percentage of the proposed expansion and identify the units (e.g., acres, miles, however, square feet)? Units:	✓ Yes No Dusing units,
d. Is the proposed action a subdivision, or does it include a subdivision? If Yes,	□Yes ☑ No
<i>i.</i> Purpose or type of subdivision? (e.g., residential, industrial, commercial; if mixed, specify types)	
iii. Number of lots proposed?	□Yes□No
iv. Minimum and maximum proposed lot sizes? Minimum Maximum	
e. Will proposed action be constructed in multiple phases? i. If No, anticipated period of construction: ii. If Yes: 60 months	Z Yes□No
Total number of phases anticipated	
 Anticipated commencement date of phase 1 (including demolition) April month 2018 year Anticipated completion date of final phase Nov month 2023 year 	
Generally describe connections or relationships among phases, including any contingencies where progress determine timing or duration of future phases:	of one phase may
Sequence of implementing management actions will be contingent upon funding availability and ORDA construction priorities at the tim	ne.

f Does the project	ct include new resi	idential uses?			☐Yes Z No
1 0	bers of units prop				
ii 1es, snow nun	One Family	Two Family	Three Family	Multiple Family (four or more)	
	One runny	<u>rwo</u> runny	Tince Tunniy	Manage runny (roar or more)	
Initial Phase					
At completion					
of all phases					
D 4	1 1 1	* 1	1 (1	1' ' ' ' ' '	
If Yes, New groo	omer garage and exp	pansion of NYSEF build	al construction (including	ding expansions)?	Z Yes□No
	of structures				
ii. Dimensions (iii. Approximate	in feet) of largest extent of building	proposed structure: g space to be heated	<u>1 story</u> height; or cooled:	75 width; and120 length 12,125 total square feet	
h. Does the propo	osed action include	e construction or oth	er activities that will	result in the impoundment of any	Z Yes □No
				agoon or other storage?	
		an existing reservoir us		8	
		_		al water for snowmaking	
		ncipal source of the		Ground water Surface water strea	ms Other specify:
			hdrawn from the Hudso		
iii. If other than v	vater, identify the	type of impounded/	contained liquids and	d their source.	
				<u>e by 11</u> million gallons; surface area: _	increase by 7.5 acres
				s height; 100,exist length	
vi. Construction	method/materials	for the proposed da	m or impounding str	ructure (e.g., earth fill, rock, wood, con	crete):
earth (exists)					
D.2. Project Op	erations				
a. Does the propo	sed action include	e any excavation, mi	ining, or dredging, di	uring construction, operations, or both?	✓ Yes No
(Not including	general site prepa	ration, grading or in	stallation of utilities	or foundations where all excavated	
materials will i	remain onsite)				
If Yes:					
<i>i</i> . What is the pu	irpose of the excar	vation or dredging?	enlarge snowmaking re	servoir	
				be removed from the site?	
			cy (will remain within the		
	nat duration of tim	•			
			e excavated or dreds	ged, and plans to use, manage or dispos	e of them.
			as general fill within the		
	•	g or processing of ex	cavated materials?		☐Yes ✓No
If yes, descri	be				·····
v. What is the to	otal area to be dred	lged or excavated?		7.5 acres	
		•		<u>1</u> acres	
			or dredging?	<u>30</u> feet	
	avation require bla				✓ Yes No
	_	_	oir will be drained prior t		
Reservoir will allowe	d to slowly refill after	excavation is complet	ed. There will be no ou	tflow from the reservoir until it is full.	
b. Would the pro	posed action cause	e or result in alteration	on of, increase or dec	crease in size of, or encroachment	✓ Yes No
•	ng wetland, water	body, shoreline, bea	ch or adjacent area?		
If Yes:					
<i>i</i> . Identify the v	vetland or waterbo	dy which would be	affected (by name, v	vater index number, wetland map numb	er or geographic
			intain. Formerly the No	rth Creek Reservoir. Outflow from the reser	voir forms Roaring
	Brook. Wetland impa	cts avoided.			

ii. Describe how the proposed action would affect that waterbody or wetland, e.g. excavation, fill, placement alteration of channels, banks and shorelines. Indicate extent of activities, alterations and additions in squa Excavation within the existing reservoir and beyond the existing footprint to increase current storage capacity from the existing footprint in the existing fo	are feet or acres:
iii. Will proposed action cause or result in disturbance to bottom sediments? If Yes, describe:	☐ Yes Z No
iv. Will proposed action cause or result in the destruction or removal of aquatic vegetation?If Yes:	☐ Yes ✓ No
acres of aquatic vegetation proposed to be removed:	
 expected acreage of aquatic vegetation remaining after project completion: purpose of proposed removal (e.g. beach clearing, invasive species control, boat access): 	
- purpose of proposed removal (e.g. beach clearing, invasive species control, boat access).	
proposed method of plant removal:	
if chemical/herbicide treatment will be used, specify product(s): v. Describe any proposed reclamation/mitigation following disturbance:	
Gradually refilling the reservoir allowing suspended solids to settle out prior to discharge from the reservoir.	
c. Will the proposed action use, or create a new demand for water?	☐Yes Z No
If Yes:	
i. Total anticipated water usage/demand per day: gallons/day	
<i>ii.</i> Will the proposed action obtain water from an existing public water supply? If Yes:	□Yes □No
Name of district or service area:	
Does the existing public water supply have capacity to serve the proposal?	☐ Yes ☐ No
• Is the project site in the existing district?	☐ Yes ☐ No
 Is expansion of the district needed? 	☐ Yes ☐ No
 Do existing lines serve the project site? 	☐ Yes ☐ No
iii. Will line extension within an existing district be necessary to supply the project? If Yes:	□Yes □No
Describe extensions or capacity expansions proposed to serve this project:	
Source(s) of supply for the district:	
<i>iv</i> . Is a new water supply district or service area proposed to be formed to serve the project site? If, Yes:	☐ Yes ☐No
Applicant/sponsor for new district:	
Date application submitted or anticipated:	
 Proposed source(s) of supply for new district: v. If a public water supply will not be used, describe plans to provide water supply for the project: 	
v. If a public water supply will not be used, describe plans to provide water supply for the project:	
vi. If water supply will be from wells (public or private), maximum pumping capacity: gallons/minu	
d. Will the proposed action generate liquid wastes?	☐ Yes Z No
If Yes: Sanitary wastewater generation is not expected to exceed current levels.	
i. Total anticipated liquid waste generation per day: gallons/dayii. Nature of liquid wastes to be generated (e.g., sanitary wastewater, industrial; if combination, describe all of the combination o	components and
approximate volumes or proportions of each):	
	
iii. Will the proposed action use any existing public wastewater treatment facilities?If Yes:	□Yes □No
Name of wastewater treatment plant to be used:	
Name of district: Describe a winting and the description of	
 Does the existing wastewater treatment plant have capacity to serve the project? Is the project site in the existing district? 	□ Yes □No □ Yes □No
 Is expansion of the district needed? 	☐ Yes ☐No

 Do existing sewer lines serve the project site? 	□Yes□No
 Will line extension within an existing district be necessary to serve the project? 	□Yes□No
If Yes:	
Describe extensions or capacity expansions proposed to serve this project:	
iv. Will a new wastewater (sewage) treatment district be formed to serve the project site?	□Yes□No
If Yes:	
Applicant/sponsor for new district: Description Description	
Date application submitted or anticipated:	
• What is the receiving water for the wastewater discharge?	aifring managed
receiving water (name and classification if surface discharge, or describe subsurface disposal plans):	enying proposed
receiving water (name and classification if surface discharge, of describe subsurface disposal plans).	
vi. Describe any plans or designs to capture, recycle or reuse liquid waste:	
e. Will the proposed action disturb more than one acre and create stormwater runoff, either from new point	✓ Yes □ No
sources (i.e. ditches, pipes, swales, curbs, gutters or other concentrated flows of stormwater) or non-point	
source (i.e. sheet flow) during construction or post construction?	
If Yes: ! How much immersions confess will the preject exacts in relation to total size of preject pages?	
 i. How much impervious surface will the project create in relation to total size of project parcel? Square feet or1.3 acres (impervious surface) 	
Square feet or acres (impervious surface) Square feet or 3766 acres (parcel size)	
ii. Describe types of new point sources. N/A	
u. Describe types of new point sources.	
iii. Where will the stormwater runoff be directed (i.e. on-site stormwater management facility/structures, adjacent p	properties.
groundwater, on-site surface water or off-site surface waters)?	: · · · · · · · · · · · · · · · · · · ·
on-site stormwater management practices	
If to surface waters, identify receiving water bodies or wetlands:	
Will stormwater runoff flow to adjacent properties?	☐ Yes ✓ No
<i>iv.</i> Does proposed plan minimize impervious surfaces, use pervious materials or collect and re-use stormwater?	✓ Yes No
f. Does the proposed action include, or will it use on-site, one or more sources of air emissions, including fuel	□Yes Z No
combustion, waste incineration, or other processes or operations?	
If Yes, identify: Fuel combustion is not expected to exceed current levels	
i. Mobile sources during project operations (e.g., heavy equipment, fleet or delivery vehicles)	
ii. Stationary sources during construction (e.g., power generation, structural heating, batch plant, crushers)	
iii. Stationary sources during operations (e.g., process emissions, large boilers, electric generation)	
ui. Stationary sources during operations (e.g., process emissions, rarge boners, electric generation)	
g. Will any air emission sources named in D.2.f (above), require a NY State Air Registration, Air Facility Permit,	□Yes Z No
or Federal Clean Air Act Title IV or Title V Permit?	
If Yes:	
i. Is the project site located in an Air quality non-attainment area? (Area routinely or periodically fails to meet	□Yes□No
ambient air quality standards for all or some parts of the year)	
ii. In addition to emissions as calculated in the application, the project will generate:	
•Tons/year (short tons) of Carbon Dioxide (CO ₂)	
•Tons/year (short tons) of Nitrous Oxide (N ₂ O)	
•Tons/year (short tons) of Perfluorocarbons (PFCs)	
•Tons/year (short tons) of Sulfur Hexafluoride (SF ₆)	
Tons/year (short tons) of Carbon Dioxide equivalent of Hydroflourocarbons (HFCs)	
Tons/year (short tons) of Hazardous Air Pollutants (HAPs)	

h. Will the proposed action generate or emit methane (includandfills, composting facilities)? If Yes: Existing sewage treatment plant emissions are not anticitive.		∐Yes √ No
i. Estimate methane generation in tons/year (metric):ii. Describe any methane capture, control or elimination m electricity, flaring):	easures included in project design (e.g., combustion to	generate heat or
i. Will the proposed action result in the release of air pollut quarry or landfill operations? If Yes: Describe operations and nature of emissions (e.g., d., d., d., d., d., d., d., d., d., d		∏Yes ∏ No
j. Will the proposed action result in a substantial increase in new demand for transportation facilities or services? If Yes: i. When is the peak traffic expected (Check all that apply Randomly between hours of to to to):	∏Yes ∏ No
iii. Parking spaces: Existingiv. Does the proposed action include any shared use parkingv. If the proposed action includes any modification of exists	Proposed Net increase/decreaseng? sting roads, creation of new roads or change in existing	☐Yes ☐ No
vi. Are public/private transportation service(s) or facilitiesvii Will the proposed action include access to public transpor or other alternative fueled vehicles?viii. Will the proposed action include plans for pedestrian or pedestrian or bicycle routes?	portation or accommodations for use of hybrid, electric	☐Yes☐No ☐Yes☐No ☐Yes☐No
 k. Will the proposed action (for commercial or industrial proposed for energy? N/A, not commercial or industrial. If Yes: i. Estimate annual electricity demand during operation of energy. 	the proposed action:	
ii. Anticipated sources/suppliers of electricity for the proje other):iii. Will the proposed action require a new, or an upgrade to		/local utility, or
1. Hours of operation. Answer all items which apply. i. During Construction: • Monday - Friday: 6:00 - 6:00 • Saturday: 6:00 - 6:00 • Sunday: 6:00-6:00 • Holidays: 6:00-6:00	 ii. During Operations: Monday - Friday: 6:00-8:00 Saturday: Sunday: Holidays: 6:00-8:00 6:00-8:00 	

m. Will the proposed action produce noise that will exceed existing ambient noise levels during construction, operation, or both? If yes:	☑ Yes □ No
 i. Provide details including sources, time of day and duration: Construction noise from vehicles and power equipment. Construction will be during daytime hours and will occur in spring, sur 	mmer and fall.
ii. Will proposed action remove existing natural barriers that could act as a noise barrier or screen?Describe:	☐ Yes ☑ No
n Will the proposed action have outdoor lighting? If yes: i. Describe source(s), location(s), height of fixture(s), direction/aim, and proximity to nearest occupied struct Building mounted exterior lighting at the one story groomer garage to light immediate surroundings, nearest occupied structure.	
 acre intensive use area ii. Will proposed action remove existing natural barriers that could act as a light barrier or screen? Describe: 	☐ Yes ☑ No
o. Does the proposed action have the potential to produce odors for more than one hour per day? If Yes, describe possible sources, potential frequency and duration of odor emissions, and proximity to ne occupied structures:	☐ Yes ☑ No earest
p. Will the proposed action include any bulk storage of petroleum (combined capacity of over 1,100 gallons) or chemical products 185 gallons in above ground storage or any amount in underground storage? If Yes: A new diesel fuel storage tank will be installed near the relocated groomer garage. i. Product(s) to be stored diesel fuel ii. Volume(s)8,000 per unit timeweek (winter) (e.g., month, year) iii. Generally describe proposed storage facilities: above ground with containment	☑ Yes □No
q. Will the proposed action (commercial, industrial and recreational projects only) use pesticides (i.e., herbicides) during construction or operation? If Yes: i. Describe proposed treatment(s):	des, Yes No
 ii. Will the proposed action use Integrated Pest Management Practices? r. Will the proposed action (commercial or industrial projects only) involve or require the management or disposed of solid waste (excluding hazardous materials)? N/A, not commercial or industrial 	☐ Yes ☐No posal ☐ Yes ☐No
If Yes: i. Describe any solid waste(s) to be generated during construction or operation of the facility: • Construction: tons per (unit of time) • Operation: tons per (unit of time) ii. Describe any proposals for on-site minimization, recycling or reuse of materials to avoid disposal as solid • Construction:	
• Operation:	
 iii. Proposed disposal methods/facilities for solid waste generated on-site: Construction: 	
Operation:	

s. Does the proposed action include construction or modification of a solid waste management facility? Yes No If Yes:				
i. Type of management or handling of waste proposed for the site (e.g., recycling or transfer station, composting, landfill, or				
other disposal activities):				
ii. Anticipated rate of disposal/processing:	1 //1 1			
 Tons/month, if transfer or other non-c Tons/hour, if combustion or thermal t 		at, or		
iii. If landfill, anticipated site life:				
t. Will proposed action at the site involve the commercial		ge, or disposal of hazardous	☐Yes Z No	
waste?	generalien, wealthen, store	.ge, or disposar of nazardous		
If Yes:				
<i>i</i> . Name(s) of all hazardous wastes or constituents to be	generated, handled or mana	iged at facility:		
ii. Generally describe processes or activities involving h	azardous wastes or constitu	ents:		
iii. Specify amount to be handled or generated to	ons/month			
iv. Describe any proposals for on-site minimization, reco	ycling or reuse of hazardous	constituents:		
v. Will any hazardous wastes be disposed at an existing	offsite hazardous waste fac	ility?	□Yes□No	
If Yes: provide name and location of facility:				
If No: describe proposed management of any hazardous v	vastes which will not be ser	t to a hazardous waste facility	<i>I</i> *	
E. Site and Setting of Proposed Action				
E.1. Land uses on and surrounding the project site				
a. Existing land uses.i. Check all uses that occur on, adjoining and near the	project site			
☐ Urban ☑ Industrial ☐ Commercial ☐ Resid		al (non-farm)		
✓ Forest ☐ Agriculture ☐ Aquatic ✓ Other	(specify): Town Park			
ii. If mix of uses, generally describe:				
1. Total constant and the second constant and the				
b. Land uses and covertypes on the project site. Land use or	Comment	A A ft	Classes	
Covertype	Current Acreage	Acreage After Project Completion	Change (Acres +/-)	
Roads, buildings, and other paved or impervious	11010480	Troject compressor	(Figure 17)	
surfaces	34.2	35.5	+1.3	
Forested	2844	2845	-39	
Meadows, grasslands or brushlands (non- agricultural including abandoned agricultural)	273.7 (ski trails)	301.0	+27.3	
agricultural, including abandoned agricultural) • Agricultural				
(includes active orchards, field, greenhouse etc.)	0	0	0	
Surface water features	10 /	-		
(lakes, ponds, streams, rivers, etc.)	19 (reservoir)	30	+11	
Wetlands (freshwater or tidal)	180	180	0	
Non-vegetated (bare rock, earth or fill)	375 (rock)	375 (rock)	0	
• Other				
Describe:				

c. Is the project site presently used by members of the community for public recreation? i. If Yes: explain: 4-season day use recreation area	✓ Yes No
d. Are there any facilities serving children, the elderly, people with disabilities (e.g., schools, hospitals, licensed day care centers, or group homes) within 1500 feet of the project site? If Yes, i. Identify Facilities:	☐ Yes No
e. Does the project site contain an existing dam?	✓ Yes No
If Yes:	<u>. 105110</u>
<i>i</i> . Dimensions of the dam and impoundment:	
• Dam height: 32 feet	
• Dam length: 100 feet	
• Surface area: 5.2 acres	
• Volume impounded:	
iii. Provide date and summarize results of last inspection:	
10/18/17 inspection - no issues with seepage, wet areas, toe drain, flow, pool level, slides/cracks/rodent activity/vegetation, concrete	or vandalism
f. Has the project site ever been used as a municipal, commercial or industrial solid waste management facility, or does the project site adjoin property which is now, or was at one time, used as a solid waste management facil If Yes:	□Yes ☑ No ity?
i. Has the facility been formally closed?	☐Yes☐ No
If yes, cite sources/documentation:	
<i>ii.</i> Describe the location of the project site relative to the boundaries of the solid waste management facility:	
iii. Describe any development constraints due to the prior solid waste activities:	
g. Have hazardous wastes been generated, treated and/or disposed of at the site, or does the project site adjoin property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes:	☐ Yes No
i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred	ed:
h. Potential contamination history. Has there been a reported spill at the proposed project site, or have any remedial actions been conducted at or adjacent to the proposed site?	☐ Yes ✓ No
If Yes:	
<i>i.</i> Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site Remediation database? Check all that apply:	□Yes□No
Yes – Spills Incidents database Provide DEC ID number(s):	
☐ Yes – Environmental Site Remediation database Provide DEC ID number(s):	
ii. If site has been subject of RCRA corrective activities, describe control measures:	
iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database?	☐ Yes ✓ No
If yes, provide DEC ID number(s):	
iv. If yes to (i), (ii) or (iii) above, describe current status of site(s):	
•	

v. Is the project site subject to an institutional control			□Yes☑No
 If yes, DEC site ID number:			
Describe any use limitations:Describe any engineering controls:			
Will the project affect the institutional or eng			□Yes□No
Explain:			
r · ·			
E.2. Natural Resources On or Near Project Site			
a. What is the average depth to bedrock on the project		≥6 feet	
b. Are there bedrock outcroppings on the project site?			✓ Yes No
If Yes, what proportion of the site is comprised of bed	rock outcroppings?	10-20 %	
c. Predominant soil type(s) present on project site:	Hermon-Lymon- Rock Outcrop	50 %	
JF (%) F	Marlow bouldery fine loamy sand	15 %	
	multiple others	35_%	
d. What is the average depth to the water table on the p	project site? Average:	eet	
e. Drainage status of project site soils: Well Draine	d: <u>20</u> % of site		
	Well Drained: 20 % of site		
	60_% of site		
f. Approximate proportion of proposed action site with	n slopes: ✓ 0-10%:	<5_% of site	
	10-15%:		
	✓ 15% or greater:	<u>>80</u> % of site	
g. Are there any unique geologic features on the project If Yes, describe: Gore Mountain, Barton Garnet Mine - Gor	ct site? e Mountain		✓ Yes No
h. Surface water features.			
<i>i.</i> Does any portion of the project site contain wetland ponds or lakes)?	ls or other waterbodies (including sti	reams, rivers,	✓ Yes No
<i>ii.</i> Do any wetlands or other waterbodies adjoin the pr	roject site?		✓ Yes No
If Yes to either <i>i</i> or <i>ii</i> , continue. If No, skip to E.2.i.			
iii. Are any of the wetlands or waterbodies within or a	adjoining the project site regulated by	y any federal,	Z Yes□No
state or local agency?		, ,	
iv. For each identified regulated wetland and waterboom			
	, 941-1256, 941-1257, 941-12		
Lakes or Ponds: Name Former North Creek	Reservoir eral Waters,	Classification	
Wetlands: Name Federal Waters, Federal Wa	eral Waters, Federal Waters,	Approximate Size APA v	vetland (in a
• Wetland No. (if regulated by DEC)	t recent compilation of NVS water of	uality impaired	☐Yes Z No
waterbodies?	t recent compliation of 1413 water q	uanty-impaired	
If yes, name of impaired water body/bodies and basis:	for listing as impaired:		
i. Is the project site in a designated Floodway?			□Yes ☑ No
j. Is the project site in the 100 year Floodplain?			□Yes Z No
k. Is the project site in the 500 year Floodplain?			□Yes ☑ No
l. Is the project site located over, or immediately adjoi If Yes:	ning, a primary, principal or sole sou	rce aquifer?	✓ Yes □No
i. Name of aquifer: Principal Aquifer			
1			

m. Identify the predominant wildlife species		roject site:	
small and large mammals migratory bird species	resident bird species reptiles and amphibians		
migratory bird species	reptiles and amphibians		
n. Does the project site contain a designated of If Yes: i. Describe the habitat/community (composition)		•	□Yes☑No
 ii. Source(s) of description or evaluation: iii. Extent of community/habitat: Currently: Following completion of project as Gain or loss (indicate + or -): o. Does project site contain any species of pleendangered or threatened, or does it contains 	proposed:ant or animal that is liste	acres acres acres d by the federal government or NY	∕S as
p. Does the project site contain any species of special concern?	of plant or animal that is	listed by NYS as rare, or as a spec	ies of ✓Yes□No
q. Is the project site or adjoining area current If yes, give a brief description of how the pro No affect on recreation on adjoining forest preserve	posed action may affect	that use:	
E.3. Designated Public Resources On or N	laar Project Site		
a. Is the project site, or any portion of it, loca Agriculture and Markets Law, Article 25- If Yes, provide county plus district name/nu	ted in a designated agric AA, Section 303 and 304	4?	<u> </u>
b. Are agricultural lands consisting of highly <i>i</i> . If Yes: acreage(s) on project site? <i>ii</i> . Source(s) of soil rating(s):	<u> </u>		
c. Does the project site contain all or part of Natural Landmark? If Yes: i. Nature of the natural landmark: ii. Provide brief description of landmark, in	Biological Community	☐ Geological Feature	□Yes ☑No
d. Is the project site located in or does it adjo If Yes: i. CEA name: ii. Basis for designation:			
iii. Designating agency and date:			

e. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district which is listed on, or has been nominated by the NYS Board of Historic Preservation for inclusion on, the State or National Register of Historic Places? If Yes:	☐ Yes No
i. Nature of historic/archaeological resource: Archaeological Site Historic Building or District	
ii. Name:	
f. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?	Z Yes □No
g. Have additional archaeological or historic site(s) or resources been identified on the project site? If Yes: i. Describe possible resource(s): ii. Basis for identification:	□Yes ☑No
h. Is the project site within fives miles of any officially designated and publicly accessible federal, state, or local scenic or aesthetic resource? If Yes:	☑ Yes □ No
 i. Identify resource: NYSAPA Scenic Vistas: (1) Back to Sodom Road, North Creek; Goodman Road, Bakers Mills ii. Nature of, or basis for, designation (e.g., established highway overlook, state or local park, state historic trail or etc.): NYSAPA Scenic Vista iii. Distance between project and resource: 1 mile, 3 miles respectively miles. 	scenic byway,
 i. Is the project site located within a designated river corridor under the Wild, Scenic and Recreational Rivers Program 6 NYCRR 666? If Yes: i. Identify the name of the river and its designation: 	☐ Yes ✓ No
ii. Is the activity consistent with development restrictions contained in 6NYCRR Part 666?	□Yes□No
F. Additional Information Attach any additional information which may be needed to clarify your project. If you have identified any adverse impacts which could be associated with your proposal, please describe those in measures which you propose to avoid or minimize them.	npacts plus any
G. Verification I certify that the information provided is true to the best of my knowledge. Applicant/Sponsor Name 2080x1 Whatuaco Date 11/15/17	
Signature Title Dir. EMI, RAKI, CONT	-)



Disclaimer: The EAF Mapper is a screening tool intended to assist project sponsors and reviewing agencies in preparing an environmental assessment form (EAF). Not all questions asked in the EAF are answered by the EAF Mapper. Additional information on any EAF question can be obtained by consulting the EAF Workbooks. Although the EAF Mapper provides the most up-to-date digital data available to DEC, you may also need to contact local or other data sources in order to obtain data not provided by the Mapper. Digital data is not a substitute for agency determinations.



B.i.i [Coastal or Waterfront Area]	No
B.i.ii [Local Waterfront Revitalization Area]	No
C.2.b. [Special Planning District]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.1.h [DEC Spills or Remediation Site - Potential Contamination History]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.1.h.i [DEC Spills or Remediation Site - Listed]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.1.h.i [DEC Spills or Remediation Site - Environmental Site Remediation Database]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.1.h.iii [Within 2,000' of DEC Remediation Site]	No
E.2.g [Unique Geologic Features]	Yes
E.2.g [Unique Geologic Features]	Gore Mountain, Barton Garnet Mine - Gore Mountain
E.2.h.i [Surface Water Features]	Yes
E.2.h.ii [Surface Water Features]	Yes
E.2.h.iii [Surface Water Features]	Yes - Digital mapping information on local and federal wetlands and waterbodies is known to be incomplete. Refer to EAF Workbook.
E.2.h.iv [Surface Water Features - Stream Name]	941-1261, 941-759.1, 941-1256, 941-1257, 941-1254, 941-1253, 941-764, 941-1270
E.2.h.iv [Surface Water Features - Stream Classification]	C(T), A(T)
E.2.h.iv [Surface Water Features - Wetlands Name]	Federal Waters, APA Wetland

E.2.h.iv [Surface Water Features - Wetlands Size]	APA Wetland (in acres):6.21409633, APA Wetland (in acres):4.79873642, APA Wetland (in acres):0.22157542, APA Wetland (in acres):0.11314292, APA Wetland (in acres):0.97567625, APA Wetland (in acres):0.11314292, APA Wetland (in acres):3.68782457, APA Wetland (in acres):0.665199621, APA Wetland (in acres):2.75641089, APA Wetland (in acres):0.15746727, APA Wetland (in acres):3.09193233, APA Wetland (in acres):0.15746727, APA Wetland (in acres):3.09193233, APA Wetland (in acres):0.17833215, APA Wetland (in acres):0.52714323, APA Wetland (in acres):0.17833215, APA Wetland (in acres):0.55871848, APA Wetland (in acres):0.180906611, APA Wetland (in acres):0.55871848, APA Wetland (in acres):1.24054127, APA Wetland (in acres):0.29332836, APA Wetland (in acres):1.37974599, APA Wetland (in acres):0.29332836, APA Wetland (in acres):1.5876402, APA Wetland (in acres):0.76184601, APA Wetland (in acres):0.56578412, APA Wetland (in acres):1.589638, APA Wetland (in acres):0.36642493, APA Wetland (in acres):1.589638, APA Wetland (in acres):0.36642493, APA Wetland (in acres):1.2665104, APA Wetland (in acres):0.37089597, APA Wetland (in acres):0.37089597, APA Wetland (in acres):0.37089597, APA Wetland (in acres):0.55756, APA Wetland (in acres):0.37089597, APA Wetland (in acres):0.557268, APA Wetland (in acres):0.37089597, APA Wetland (in acres):0.557268, APA Wetland (in acres):0.37389597, APA Wetland (in acres):0.55721268, APA Wetland (in acres):0.37389597, APA Wetland (in acres):0.357407738, APA Wetland (in acres):0.37389597, APA Wetland (in acres):0.357407738, APA Wetland (in acres):0.35867203, APA Wetland (in acres):0.3573274925, APA Wetland (in acres):0.35867203, APA Wetland (in acres):0.35867203, APA Wetland (in acres):0.35867203, APA Wetland (in acres):0.35867203, APA Wetland (in acres):0.37327507, APA Wetland (in acres):0.3388445, APA Wetland (in acres):0.37327507, APA Wetland (in acres):0.33864945, APA Wetland (in acres):0.57713933455, APA Wetland (in acres):0.577139334, APA Wetland (in acres):0.57713933, APA Wetland (in acre
E.2.h.v [Impaired Water Bodies]	No
E.2.i. [Floodway]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.2.j. [100 Year Floodplain]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.2.k. [500 Year Floodplain]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.2.I. [Aquifers]	Yes
E.2.I. [Aquifer Names]	Principal Aquifer
E.2.n. [Natural Communities]	No
E.2.o. [Endangered or Threatened Species]	No

E.2.p. [Rare Plants or Animals]	Yes
E.3.a. [Agricultural District]	No
E.3.c. [National Natural Landmark]	No
E.3.d [Critical Environmental Area]	No
E.3.e. [National Register of Historic Places]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.3.f. [Archeological Sites]	Yes
E.3.i. [Designated River Corridor]	No

	Agency Use Only [If applicable]
Project :	
Date:	

Part 2 is to be completed by the lead agency. Part 2 is designed to help the lead agency inventory all potential resources that could be affected by a proposed project or action. We recognize that the lead agency's reviewer(s) will not necessarily be environmental professionals. So, the questions are designed to walk a reviewer through the assessment process by providing a series of questions that can be answered using the information found in Part 1. To further assist the lead agency in completing Part 2, the form identifies the most relevant questions in Part 1 that will provide the information needed to answer the Part 2 question. When Part 2 is completed, the lead agency will have identified the relevant environmental areas that may be impacted by the proposed activity.

If the lead agency is a state agency and the action is in any Coastal Area, complete the Coastal Assessment Form before proceeding with this assessment.

Tips for completing Part 2:

- Review all of the information provided in Part 1.
- Review any application, maps, supporting materials and the Full EAF Workbook.
- Answer each of the 18 questions in Part 2.
- If you answer "Yes" to a numbered question, please complete all the questions that follow in that section.
- If you answer "No" to a numbered question, move on to the next numbered question.
- Check appropriate column to indicate the anticipated size of the impact.
- Proposed projects that would exceed a numeric threshold contained in a question should result in the reviewing agency checking the box "Moderate to large impact may occur."
- The reviewer is not expected to be an expert in environmental analysis.
- If you are not sure or undecided about the size of an impact, it may help to review the sub-questions for the general question and consult the workbook.
- When answering a question consider all components of the proposed activity, that is, the "whole action".
- Consider the possibility for long-term and cumulative impacts as well as direct impacts.

 Answer the question in a reasonable manner considering the scale and context of the project. 			
1. Impact on Land Proposed action may involve construction on, or physical alteration of, the land surface of the proposed site. (See Part 1. D.1) If "Yes", answer questions a - j. If "No", move on to Section 2.	ion may involve construction on, or physical alteration of, ace of the proposed site. (See Part 1. D.1)		YES
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may involve construction on land where depth to water table is less than 3 feet.	E2d	Ø	
b. The proposed action may involve construction on slopes of 15% or greater.	E2f		abla
c. The proposed action may involve construction on land where bedrock is exposed, or generally within 5 feet of existing ground surface.	E2a		Ø
d. The proposed action may involve the excavation and removal of more than 1,000 tons of natural material.	D2a	Ø	
e. The proposed action may involve construction that continues for more than one year or in multiple phases.	D1e		Ø
f. The proposed action may result in increased erosion, whether from physical disturbance or vegetation removal (including from treatment by herbicides).	D2e, D2q		Ø
g. The proposed action is, or may be, located within a Coastal Erosion hazard area.	B1i	Ø	
h. Other impacts: none identified		Ø	

2. Impact on Geological Features The proposed action may result in the modification or destruction of, or inhib.	it		
access to, any unique or unusual land forms on the site (e.g., cliffs, dunes, minerals, fossils, caves). (See Part 1. E.2.g) If "Yes", answer questions a - c. If "No", move on to Section 3.	□NO ☑ YES		YES
ij zes y answer questiens a er ij zie y mere en ie zeemen er	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. Identify the specific land form(s) attached: Gore Mountain	E2g	Ø	
b. The proposed action may affect or is adjacent to a geological feature listed as a registered National Natural Landmark. Specific feature:	E3c	Ø	
c. Other impacts:none identified		Ø	
3. Impacts on Surface Water The proposed action may affect one or more wetlands or other surface water bodies (e.g., streams, rivers, ponds or lakes). (See Part 1. D.2, E.2.h) If "Yes", answer questions a - l. If "No", move on to Section 4.	□no Z yes		
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may create a new water body.	D2b, D1h		
b. The proposed action may result in an increase or decrease of over 10% or more than a 10 acre increase or decrease in the surface area of any body of water.	D2b		Z
c. The proposed action may involve dredging more than 100 cubic yards of material from a wetland or water body.	D2a		Ø
d. The proposed action may involve construction within or adjoining a freshwater or tidal wetland, or in the bed or banks of any other water body.	E2h	Ø	
e. The proposed action may create turbidity in a waterbody, either from upland erosion, runoff or by disturbing bottom sediments.	D2a, D2h		Ø
f. The proposed action may include construction of one or more intake(s) for withdrawal of water from surface water.	D2c	Ø	
g. The proposed action may include construction of one or more outfall(s) for discharge of wastewater to surface water(s).	D2d	Ø	
h. The proposed action may cause soil erosion, or otherwise create a source of stormwater discharge that may lead to siltation or other degradation of receiving water bodies.	D2e		Z
 The proposed action may affect the water quality of any water bodies within or downstream of the site of the proposed action. 	E2h	Ø	
j. The proposed action may involve the application of pesticides or herbicides in or around any water body.	D2q, E2h	Ø	
k. The proposed action may require the construction of new, or expansion of existing,	D1a, D2d	abla	

wastewater treatment facilities.

1. 0	Other impacts: none identified		Ø	
4.	Impact on groundwater The proposed action may result in new or additional use of ground water, or may have the potential to introduce contaminants to ground water or an aquife (See Part 1. D.2.a, D.2.c, D.2.d, D.2.p, D.2.q, D.2.t) If "Yes", answer questions a - h. If "No", move on to Section 5.	□NO ✓ YES		
		Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
	The proposed action may require new water supply wells, or create additional demand on supplies from existing water supply wells.	D2c		
	Water supply demand from the proposed action may exceed safe and sustainable withdrawal capacity rate of the local supply or aquifer. Cite Source:	D2c	Ø	
	The proposed action may allow or result in residential uses in areas without water and sewer services.	D1a, D2c	Ø	
d.	The proposed action may include or require wastewater discharged to groundwater.	D2d, E2l		
	The proposed action may result in the construction of water supply wells in locations where groundwater is, or is suspected to be, contaminated.	D2c, E1f, E1g, E1h	Ø	
	The proposed action may require the bulk storage of petroleum or chemical products over ground water or an aquifer.	D2p, E2l	Ø	
	The proposed action may involve the commercial application of pesticides within 100 feet of potable drinking water or irrigation sources.	E2h, D2q, E2l, D2c	☑	
h.	Other impacts: none identified			
_				
5.	Impact on Flooding The proposed action may result in development on lands subject to flooding. (See Part 1. E.2) If "Yes", answer questions a - g. If "No", move on to Section 6.	✓ NO YES		
		Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a.	The proposed action may result in development in a designated floodway.	E2i		
b. '	The proposed action may result in development within a 100 year floodplain.	E2j		
c.	The proposed action may result in development within a 500 year floodplain.	E2k		
	The proposed action may result in, or require, modification of existing drainage patterns.	D2b, D2e		
e. ′	The proposed action may change flood water flows that contribute to flooding.	D2b, E2i, E2j, E2k		
	f there is a dam located on the site of the proposed action, is the dam in need of repair, or upgrade?	E1e		

	1		
g. Other impacts:			
6. Impacts on Air The proposed action may include a state regulated air emission source. (See Part 1. D.2.f., D,2,h, D.2.g) If "Yes", answer questions a - f. If "No", move on to Section 7.	✓NO YES		YES
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
 a. If the proposed action requires federal or state air emission permits, the action may also emit one or more greenhouse gases at or above the following levels: i. More than 1000 tons/year of carbon dioxide (CO₂) ii. More than 3.5 tons/year of nitrous oxide (N₂O) iii. More than 1000 tons/year of carbon equivalent of perfluorocarbons (PFCs) iv. More than .045 tons/year of sulfur hexafluoride (SF₆) v. More than 1000 tons/year of carbon dioxide equivalent of hydrochloroflourocarbons (HFCs) emissions vi. 43 tons/year or more of methane 	D2g D2g D2g D2g D2g D2g D2h		
b. The proposed action may generate 10 tons/year or more of any one designated hazardous air pollutant, or 25 tons/year or more of any combination of such hazardous air pollutants.	D2g		
c. The proposed action may require a state air registration, or may produce an emissions rate of total contaminants that may exceed 5 lbs. per hour, or may include a heat source capable of producing more than 10 million BTU's per hour.	D2f, D2g		
d. The proposed action may reach 50% of any of the thresholds in "a" through "c", above.	D2g		
e. The proposed action may result in the combustion or thermal treatment of more than 1 ton of refuse per hour.	D2s		
f. Other impacts:			
7. Impact on Plants and Animals The proposed action may result in a loss of flora or fauna. (See Part 1. E.2. n If "Yes", answer questions a - j. If "No", move on to Section 8.	□NO	✓ YES	
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may cause reduction in population or loss of individuals of any threatened or endangered species, as listed by New York State or the Federal government, that use the site, or are found on, over, or near the site.	E2o	Ø	
b. The proposed action may result in a reduction or degradation of any habitat used by any rare, threatened or endangered species, as listed by New York State or the federal government.	E2o	Ø	
c. The proposed action may cause reduction in population, or loss of individuals, of any species of special concern or conservation need, as listed by New York State or the Federal government, that use the site, or are found on, over, or near the site.	E2p	Ø	
d. The proposed action may result in a reduction or degradation of any habitat used by any species of special concern and conservation need, as listed by New York State or the Federal government.	E2p		Ø

e. The proposed action may diminish the capacity of a registered National Natural Landmark to support the biological community it was established to protect.	Е3с	Ø	
f. The proposed action may result in the removal of, or ground disturbance in, any portion of a designated significant natural community. Source:	may result in the removal of, or ground disturbance in, any ed significant natural community.		
g. The proposed action may substantially interfere with nesting/breeding, foraging, or over-wintering habitat for the predominant species that occupy or use the project site.	E2m		Ø
h. The proposed action requires the conversion of more than 10 acres of forest, grassland or any other regionally or locally important habitat. Habitat type & information source:		Ø	
i. Proposed action (commercial, industrial or recreational projects, only) involves use of herbicides or pesticides.	D2q		
j. Other impacts: none identified			
8. Impact on Agricultural Resources The proposed action may impact agricultural resources. (See Part 1. E.3.a. a	and b.)	✓NO	YES
If "Yes", answer questions a - h. If "No", move on to Section 9.			
If Tes, answer questions a - n. If No, move on to Section 9.	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may impact soil classified within soil group 1 through 4 of the NYS Land Classification System.	Part I	small impact	to large impact may
a. The proposed action may impact soil classified within soil group 1 through 4 of the	Part I Question(s)	small impact may occur	to large impact may occur
 a. The proposed action may impact soil classified within soil group 1 through 4 of the NYS Land Classification System. b. The proposed action may sever, cross or otherwise limit access to agricultural land 	Part I Question(s)	small impact may occur	to large impact may occur
 a. The proposed action may impact soil classified within soil group 1 through 4 of the NYS Land Classification System. b. The proposed action may sever, cross or otherwise limit access to agricultural land (includes cropland, hayfields, pasture, vineyard, orchard, etc). c. The proposed action may result in the excavation or compaction of the soil profile of 	Part I Question(s) E2c, E3b E1a, Elb	small impact may occur	to large impact may occur
 a. The proposed action may impact soil classified within soil group 1 through 4 of the NYS Land Classification System. b. The proposed action may sever, cross or otherwise limit access to agricultural land (includes cropland, hayfields, pasture, vineyard, orchard, etc). c. The proposed action may result in the excavation or compaction of the soil profile of active agricultural land. d. The proposed action may irreversibly convert agricultural land to non-agricultural uses, either more than 2.5 acres if located in an Agricultural District, or more than 10 	Part I Question(s) E2c, E3b E1a, Elb E3b	small impact may occur	to large impact may occur
 a. The proposed action may impact soil classified within soil group 1 through 4 of the NYS Land Classification System. b. The proposed action may sever, cross or otherwise limit access to agricultural land (includes cropland, hayfields, pasture, vineyard, orchard, etc). c. The proposed action may result in the excavation or compaction of the soil profile of active agricultural land. d. The proposed action may irreversibly convert agricultural land to non-agricultural uses, either more than 2.5 acres if located in an Agricultural District, or more than 10 acres if not within an Agricultural District. e. The proposed action may disrupt or prevent installation of an agricultural land 	Part I Question(s) E2c, E3b E1a, Elb E3b E1b, E3a	small impact may occur	to large impact may occur
 a. The proposed action may impact soil classified within soil group 1 through 4 of the NYS Land Classification System. b. The proposed action may sever, cross or otherwise limit access to agricultural land (includes cropland, hayfields, pasture, vineyard, orchard, etc). c. The proposed action may result in the excavation or compaction of the soil profile of active agricultural land. d. The proposed action may irreversibly convert agricultural land to non-agricultural uses, either more than 2.5 acres if located in an Agricultural District, or more than 10 acres if not within an Agricultural District. e. The proposed action may disrupt or prevent installation of an agricultural land management system. f. The proposed action may result, directly or indirectly, in increased development 	Part I Question(s) E2c, E3b E1a, E1b E3b E1b, E3a El a, E1b C2c, C3,	small impact may occur	to large impact may occur
 a. The proposed action may impact soil classified within soil group 1 through 4 of the NYS Land Classification System. b. The proposed action may sever, cross or otherwise limit access to agricultural land (includes cropland, hayfields, pasture, vineyard, orchard, etc). c. The proposed action may result in the excavation or compaction of the soil profile of active agricultural land. d. The proposed action may irreversibly convert agricultural land to non-agricultural uses, either more than 2.5 acres if located in an Agricultural District, or more than 10 acres if not within an Agricultural District. e. The proposed action may disrupt or prevent installation of an agricultural land management system. f. The proposed action may result, directly or indirectly, in increased development potential or pressure on farmland. g. The proposed project is not consistent with the adopted municipal Farmland 	Part I Question(s) E2c, E3b E1a, Elb E3b E1b, E3a El a, E1b C2c, C3, D2c, D2d	small impact may occur	to large impact may occur

9. Impact on Aesthetic Resources The land use of the proposed action are obviously different from, or are in sharp contrast to, current land use patterns between the proposed project and a scenic or aesthetic resource. (Part 1. E.1.a, E.1.b, E.3.h.)	✓NO □YES]YES
If "Yes", answer questions a - g. If "No", go to Section 10.			
ij Tes , unswer questions u g. ij Tro , go to section To.	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. Proposed action may be visible from any officially designated federal, state, or local scenic or aesthetic resource.	E3h		
b. The proposed action may result in the obstruction, elimination or significant screening of one or more officially designated scenic views.	E3h, C2b		
c. The proposed action may be visible from publicly accessible vantage points: i. Seasonally (e.g., screened by summer foliage, but visible during other seasons) ii. Year round	E3h		
d. The situation or activity in which viewers are engaged while viewing the proposed action is:i. Routine travel by residents, including travel to and from workii. Recreational or tourism based activities	E3h E2q, E1c		
e. The proposed action may cause a diminishment of the public enjoyment and appreciation of the designated aesthetic resource.	E3h		
f. There are similar projects visible within the following distance of the proposed project: 0-1/2 mile 1/2 -3 mile 3-5 mile 5+ mile	D1a, E1a, D1f, D1g		
g. Other impacts:			
10. Impact on Historic and Archeological Resources The proposed action may occur in or adjacent to a historic or archaeological resource. (Part 1. E.3.e, f. and g.) If "Yes", answer questions a - e. If "No", go to Section 11. YES			YES
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may occur wholly or partially within, or substantially contiguous to, any buildings, archaeological site or district which is listed on or has been nominated by the NYS Board of Historic Preservation for inclusion on the State or National Register of Historic Places.	E3e		
b. The proposed action may occur wholly or partially within, or substantially contiguous to, an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory.	E3f		
c. The proposed action may occur wholly or partially within, or substantially contiguous to, an archaeological site not included on the NY SHPO inventory. Source:	E3g		

d. Other impacts:			
If any of the above (a-d) are answered "Moderate to large impact may e. occur", continue with the following questions to help support conclusions in Part 3:			
 The proposed action may result in the destruction or alteration of all or part of the site or property. 	E3e, E3g, E3f		
ii. The proposed action may result in the alteration of the property's setting or integrity.	E3e, E3f, E3g, E1a, E1b		
iii. The proposed action may result in the introduction of visual elements which are out of character with the site or property, or may alter its setting.	E3e, E3f, E3g, E3h, C2, C3		
11. Impact on Open Space and Recreation The proposed action may result in a loss of recreational opportunities or a reduction of an open space resource as designated in any adopted municipal open space plan. (See Part 1. C.2.c, E.1.c., E.2.q.) If "Yes", answer questions a - e. If "No", go to Section 12.	√ N0) [YES
	Relevant	No, or	Moderate
	Part I Question(s)	small impact may occur	to large impact may occur
a. The proposed action may result in an impairment of natural functions, or "ecosystem services", provided by an undeveloped area, including but not limited to stormwater storage, nutrient cycling, wildlife habitat.	D2e, E1b E2h, E2m, E2o, E2n, E2p		
b. The proposed action may result in the loss of a current or future recreational resource.	C2a, E1c, C2c, E2q		
c. The proposed action may eliminate open space or recreational resource in an area with few such resources.	C2a, C2c E1c, E2q		
d. The proposed action may result in loss of an area now used informally by the community as an open space resource.	C2c, E1c		
e. Other impacts:			
12. Impact on Critical Environmental Areas The proposed action may be located within or adjacent to a critical environmental area (CEA). (See Part 1. E.3.d) If "Yes", answer questions a - c. If "No", go to Section 13.	✓ NO) [YES
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may result in a reduction in the quantity of the resource or characteristic which was the basis for designation of the CEA.	E3d		
b. The proposed action may result in a reduction in the quality of the resource or characteristic which was the basis for designation of the CEA.	E3d		
c. Other impacts:			

13. Impact on Transportation The proposed action may result in a change to existing transportation systems. (See Part 1. D.2.j) YES			
If "Yes", answer questions a - f. If "No", go to Section 14.	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. Projected traffic increase may exceed capacity of existing road network.	D2j		
b. The proposed action may result in the construction of paved parking area for 500 or more vehicles.	D2j		
c. The proposed action will degrade existing transit access.	D2j		
d. The proposed action will degrade existing pedestrian or bicycle accommodations.	D2j		
e. The proposed action may alter the present pattern of movement of people or goods.	D2j		
f. Other impacts:			
14. Impact on Energy The proposed action may cause an increase in the use of any form of energy. (See Part 1. D.2.k) If "Yes", answer questions a - e. If "No", go to Section 15.			
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action will require a new, or an upgrade to an existing, substation.	D2k	Ø	
b. The proposed action will require the creation or extension of an energy transmission or supply system to serve more than 50 single or two-family residences or to serve a commercial or industrial use.	D1f, D1q, D2k	Ø	
c. The proposed action may utilize more than 2,500 MWhrs per year of electricity.	D2k	Ø	
d. The proposed action may involve heating and/or cooling of more than 100,000 square feet of building area when completed.	D1g	Ø	
e. Other Impacts:none identified		Ø	
	<u> </u>	<u> </u>	<u> </u>
15. Impact on Noise, Odor, and Light The proposed action may result in an increase in noise, odors, or outdoor lighting. ✓ NO YES (See Part 1. D.2.m., n., and o.) If "Yes", answer questions a - f. If "No", go to Section 16.			
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may produce sound above noise levels established by local regulation.	D2m		
b. The proposed action may result in blasting within 1,500 feet of any residence, hospital, school, licensed day care center, or nursing home.	D2m, E1d		
c. The proposed action may result in routine odors for more than one hour per day.	D2o		

d. The proposed action may result in light shining onto adjoining properties.	D2n		
e. The proposed action may result in lighting creating sky-glow brighter than existing area conditions.	D2n, E1a		
f. Other impacts:			
16. Impact on Human Health The proposed action may have an impact on human health from exposure to new or existing sources of contaminants. (See Part 1.D.2.q., E.1. d. f. g. and h.) If "Yes", answer questions a - m. If "No", go to Section 17.			
	Relevant Part I Question(s)	No,or small impact may cccur	Moderate to large impact may occur
a. The proposed action is located within 1500 feet of a school, hospital, licensed day care center, group home, nursing home or retirement community.	E1d		
b. The site of the proposed action is currently undergoing remediation.	E1g, E1h		
c. There is a completed emergency spill remediation, or a completed environmental site remediation on, or adjacent to, the site of the proposed action.	Elg, Elh		
d. The site of the action is subject to an institutional control limiting the use of the property (e.g., easement or deed restriction).	Elg, Elh		
e. The proposed action may affect institutional control measures that were put in place to ensure that the site remains protective of the environment and human health.	Elg, Elh		
f. The proposed action has adequate control measures in place to ensure that future generation, treatment and/or disposal of hazardous wastes will be protective of the environment and human health.	D2t		
g. The proposed action involves construction or modification of a solid waste management facility.	D2q, E1f		
h. The proposed action may result in the unearthing of solid or hazardous waste.	D2q, E1f		
i. The proposed action may result in an increase in the rate of disposal, or processing, of solid waste.	D2r, D2s		

j. The proposed action may result in excavation or other disturbance within 2000 feet of

k. The proposed action may result in the migration of explosive gases from a landfill

1. The proposed action may result in the release of contaminated leachate from the

a site used for the disposal of solid or hazardous waste.

m. Other impacts:

site to adjacent off site structures.

project site.

E1f, E1g

E1f, E1g

D2s, E1f,

E1h

D2r

17. Consistency with Community Plans The proposed action is not consistent with adopted land use plans. (See Part 1. C.1, C.2. and C.3.)	✓NO		YES
If "Yes", answer questions a - h. If "No", go to Section 18.			
	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action's land use components may be different from, or in sharp contrast to, current surrounding land use pattern(s).	C2, C3, D1a E1a, E1b		
b. The proposed action will cause the permanent population of the city, town or village in which the project is located to grow by more than 5%.	C2		
c. The proposed action is inconsistent with local land use plans or zoning regulations.	C2, C2, C3		
d. The proposed action is inconsistent with any County plans, or other regional land use plans.	C2, C2		
e. The proposed action may cause a change in the density of development that is not supported by existing infrastructure or is distant from existing infrastructure.	C3, D1c, D1d, D1f, D1d, Elb		
f. The proposed action is located in an area characterized by low density development that will require new or expanded public infrastructure.	C4, D2c, D2d D2j		
g. The proposed action may induce secondary development impacts (e.g., residential or commercial development not included in the proposed action)	C2a		
h. Other:			
18. Consistency with Community Character The proposed project is inconsistent with the existing community character. (See Part 1. C.2, C.3, D.2, E.3) If "Yes", answer questions a - g. If "No", proceed to Part 3.	✓NO) <u></u>	YES
zy zez , mane. questions a g. zy zne , precedule z anve.	Relevant Part I Question(s)	No, or small impact may occur	Moderate to large impact may occur
a. The proposed action may replace or eliminate existing facilities, structures, or areas of historic importance to the community.	E3e, E3f, E3g		
b. The proposed action may create a demand for additional community services (e.g. schools, police and fire)	C4		
c. The proposed action may displace affordable or low-income housing in an area where there is a shortage of such housing.	C2, C3, D1f D1g, E1a		
d. The proposed action may interfere with the use or enjoyment of officially recognized or designated public resources.	C2, E3		
e. The proposed action is inconsistent with the predominant architectural scale and character.	C2, C3		
f. Proposed action is inconsistent with the character of the existing natural landscape.	C2, C3 E1a, E1b E2g, E2h		
	Ezg, Ezn		<u> </u>

	Agency Use Only [IfApplicable]
Project:	
Date:	

Full Environmental Assessment Form Part 3 - Evaluation of the Magnitude and Importance of Project Impacts and Determination of Significance

Part 3 provides the reasons in support of the determination of significance. The lead agency must complete Part 3 for every question in Part 2 where the impact has been identified as potentially moderate to large or where there is a need to explain why a particular element of the proposed action will not, or may, result in a significant adverse environmental impact.

Based on the analysis in Part 3, the lead agency must decide whether to require an environmental impact statement to further assess the proposed action or whether available information is sufficient for the lead agency to conclude that the proposed action will not have a significant adverse environmental impact. By completing the certification on the next page, the lead agency can complete its determination of significance.

Reasons Supporting This Determination:

To complete this section:

- Identify the impact based on the Part 2 responses and describe its magnitude. Magnitude considers factors such as severity, size or extent of an impact.
- Assess the importance of the impact. Importance relates to the geographic scope, duration, probability of the impact
 occurring, number of people affected by the impact and any additional environmental consequences if the impact were to
 occur.
- The assessment should take into consideration any design element or project changes.
- Repeat this process for each Part 2 question where the impact has been identified as potentially moderate to large or where
 there is a need to explain why a particular element of the proposed action will not, or may, result in a significant adverse
 environmental impact.
- Provide the reason(s) why the impact may, or will not, result in a significant adverse environmental impact
- For Conditional Negative Declarations identify the specific condition(s) imposed that will modify the proposed action so that no significant adverse environmental impacts will result.
- Attach additional sheets, as needed.
- (1) Construction on steep slopes for such things as trail construction, trail widening and lift construction has the potential for significant impacts to land (erosional soil loss) and to water (sedimentation). The impact potential is exacerbated by the multi-year, multi-phase construction activities that would be proposed under the pending unit management plan amendment.
- (2) Expansion of the snowmaking reservoir has the potential for significantly impacting downstream water quality during and after construction. Use of spoils from the reservoir excavation as fill elsewhere within the intensive use area could cause significant impacts similar to those described in (1) above.
- (3) The project site is located over a principal aquifer. Adding additional underground petroleum storage has the potential for causing significant localized impacts to groundwater.
- (4) Bicknell's thrush is a species of special concern in New York State and portions of the intensive use area are within a State-designated Bird Conservation Area. Construction activities in and around areas of Bicknell's thrush breeding and/or nesting could have a significant impact on this species.

Determination of Signi	ificance - Type 1 and Unlisted Actions
SEQR Status: Type 1	Unlisted
Identify portions of EAF completed for this Project:	Part 1 Part 2 Part 3

Upon review of the information recorded on this EAF, as noted, plus this additional support information
and considering both the magnitude and importance of each identified potential impact, it is the conclusion of the NYS Olympic Regional Development Authority as lead agency that:
A. This project will result in no significant adverse impacts on the environment, and, therefore, an environmental impact statement need not be prepared. Accordingly, this negative declaration is issued.
B. Although this project could have a significant adverse impact on the environment, that impact will be avoided or substantially mitigated because of the following conditions which will be required by the lead agency:
There will, therefore, be no significant adverse impacts from the project as conditioned, and, therefore, this conditioned negative declaration is issued. A conditioned negative declaration may be used only for UNLISTED actions (see 6 NYCRR 617.d).
C. This Project may result in one or more significant adverse impacts on the environment, and an environmental impact statement must be prepared to further assess the impact(s) and possible mitigation and to explore alternatives to avoid or reduce those impacts. Accordingly, this positive declaration is issued.
Name of Action: Gore Mountain Intensive Use Area 2017 Unit Management Plan (UMP) Amendment
Name of Lead Agency: NYS Olympic Regional Development Authority
Name of Responsible Officer in Lead Agency: Robert Hammond
Title of Responsible Officer: Director of Environmental, Planning and Construction
Signature of Responsible Officer in Lead Agency:
Signature of Preparer (if different from Responsible Officer) Date:
For Further Information:
Contact Person: Robert Hammond
Address: Director of Environmental, Planning and Construction
Telephone Number: (518) 302-5332
E-mail: bhammond@orda.org
For Type 1 Actions and Conditioned Negative Declarations, a copy of this Notice is sent to:
Chief Executive Officer of the political subdivision in which the action will be principally located (e.g., Town / City / Village of) Other involved agencies (if any) Applicant (if any) Environmental Notice Bulletin: http://www.dec.ny.gov/enb/enb.html

Appendix 2 ORDA/NYSDEC Consolidation Agreement

AGREEMENT CONSOLIDATING THE MANAGEMENT AGREEMENTS FOR THE GORE MOUNTAIN SKI CENTER, THE WHITEFACE MOUNTAIN SKI CENTER AND MEMORIAL HIGHWAY, AND THE MOUNT VAN HOEVENBERG RECREATION AREA

THIS CONSOLIDATION AGREEMENT is made by and between the NEW YORK

STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION ("DEPARTMENT") and
the OLYMPIC REGIONAL DEVELOPMENT AUTHORITY ("ORDA").

RECITALS:

- A. The DEPARTMENT and ORDA, pursuant to the provisions of Section 2614 of the Public Authorities Law, entered into an agreement dated April 1, 1984, authorizing ORDA to use, operate, maintain and manage the Gore Mountain Ski Center Area, and entered into an agreement dated October 4, 1982, authorizing ORDA to use, operate, maintain and manage the Whiteface Mountain Ski Center and Memorial Highway, and the Mount Van Hoevenberg Recreation Area (hereinafter referred to collectively as "the Agreements");
- B. The parties previously amended the Agreements several times, with the last amendment occurring on June 12, 2013;
- C. The parties also entered into a Memorandum of Understanding effective December 15, 1984, that established methods and procedures to implement the foregoing Agreements (hereinafter "MOU"), and amended the MOU on March 11, 1991; and
- D. The parties find it in their mutual interests to consolidate the Agreements and make other amendments necessary for their implementation.

NOW, THEREFORE, the parties hereby agree as follows:

- 1. Except as otherwise specified in this Consolidation Agreement, all terms and conditions of the Agreements as amended are hereby ratified and affirmed, and shall remain in full force and effect. Copies of the Agreements are attached hereto as Attachment 1, and a copy of the MOU is attached hereto as Attachment 2. In the event of any conflict between the Agreements and this Consolidated Agreement, this Consolidated Agreement shall control.
- 2. Section 10 of the April 1, 1984 agreement relating to management of the Gore Mountain Ski Center Area, and Section 11 of the October 4, 1982 agreement relating to management of the Whiteface Mountain Ski Center and Memorial Highway, and the Mount Van Hoevenberg Recreation Area, which pertain to unit management planning are amended to read as follows:

"Unit Management Plans.

A. General Guidelines

(1) In consultation with the DEPARTMENT, ORDA shall prepare and periodically amend Unit Management Plans ("UMP") for the facilities at the Gore Mountain Ski Center Area, Whiteface Mountain Ski Center and Memorial Highway, and the Mount Van Hoevenberg Recreation Area ("Facilities"), which ORDA manages pursuant to this agreement, as outlined in Section I, Introduction, Unit Management Plan Development of the Adirondack Park State Land Master Plan ("APSLMP"). The UMPs will contain an inventory of the natural resources, Facilities and public use of the Facilities; establish goals and objectives for the future use and management of the Facilities; evaluate alternative plans for the provision

and management of public use of the Facilities and an assessment of the environmental impacts of each alternative; establish preferred management options for the Facilities in fulfillment with ORDA's legislative mandate through a procedure involving the participation of interested citizens, user groups and adjacent local governments; describe the specific management goals and policies which are incorporated in the preferred management plan; describe any specific physical development or improvement projects required by the UMP, including a priority schedule for the completion of each project and estimated costs thereof; provide a priority schedule for the removal and/or termination of any nonconforming uses; and describe procedures for the continued monitoring of the UMP's implementation. A UMP cannot amend the APSLMP and as finally adopted shall be in conformance with the general guidelines and criteria of the APSLMP. Any issues with respect to conformance of a proposed UMP with the APSLMP will be resolved and any necessary amendments to the APSLMP acted on prior to ORDA providing the DEPARTMENT with a proposed Final UMP to pass on to Adirondack Park Agency ("Agency") for final review.

(2) Annually, ORDA shall provide the DEPARTMENT with a schedule for the preparation and/or revision of any UMP or UMP amendment proposed to be undertaken by ORDA with respect to any of the Facilities and shall promptly advise the DEPARTMENT of any changes thereto.

(3) To identify significant issues and constraints, scheduling, data needs, and public involvement, ORDA will consult with the DEPARTMENT prior to undertaking the preparation of a UMP or UMP amendment.

B. Staff Consultation

ORDA will consult with the DEPARTMENT in the preparation and/or revision of a UMP as follows:

- (1) ORDA will provide written notification to the DEPARTMENT before the development of a written draft of a UMP update and/or amendment is prepared and will not undertake the preparation and/or revision of any UMP without written notice to the DEPARTMENT of the intent to do so.
- (2) The Regional Director of the DEPARTMENT's Region 5 office in Ray
 Brook or the Director's designee shall be the DEPARTMENT's contact
 for formal communications between ORDA and the DEPARTMENT.
- (3) ORDA's President/CEO or the President/CEO's designee will be the contact for formal communications between ORDA and the DEPARTMENT.
- (4) ORDA shall request the official designation of a representative of the DEPARTMENT to assist ORDA with preparation and/or revision of UMPs. The DEPARTMENT will ask the Agency to designate a representative to assist ORDA with preparation and/or revision of UMPs.
- (5) To assist the planning team in the development of individual UMPs,
 ORDA shall send drafts to the DEPARTMENT and consult with the
 DEPARTMENT on conformance issues.

- (6) The DEPARTMENT will participate in planning team discussions, review preliminary UMP drafts, and comment on UMP text and proposed management actions.
- ORDA staff will consult with the DEPARTMENT during the drafting of UMPs and UMP Amendments. DEPARTMENT staff will review preliminary draft UMPs and provide comment on SLMP conformance issues. This internal, informal, deliberative process is ordinarily exempt from the Freedom of Information Law (FOIL).
- (8) DEPARTMENT staff will participate in public information sessions and conduct field inspections with the planning teams.
- (9) In the preparation of UMPs, ORDA will normally serve as lead agency for State Environmental Quality Review (SEQR), and the DEPARTMENT and the Agency will participate in the SEQR process as involved agencies.

C. <u>UMP Review</u>

INITIAL DRAFT UMP:

(1) ORDA will provide DEPARTMENT with fourteen review copies of an internal "Initial Draft" of the UMP or UMP amendment for the Facilities, including alternative management objectives, where appropriate, for review and comment, prior to the completion of a draft plan for public review (the "Public Draft"). The DEPARTMENT will provide seven of the drafts to the Agency for review. The DEPARTMENT will work with ORDA to best ensure that the fourteen review copies are distributed on a media such as CD's and Data Sticks, so that ORDA complies with the

- intent and the spirit of Executive Order No. 4: Establishing a State Green Procurement and Agency Sustainability Program (2008).
- (2) The Initial Draft UMP will contain all the elements specified in the APSLMP, including all required inventories, statement of alternative management objectives, administrative actions, schedules for UMP implementation and all information, text, maps and appendices which are intended for inclusion in the Public Draft.
- (3) The DEPARTMENT shall be the primary contact with the Agency, with assistance from ORDA as requested by the DEPARTMENT, with respect to any UMPs for the Facilities, utilizing applicable provisions set forth in the UMP section of the March, 2010 Memorandum of Understanding between the Agency and the DEPARTMENT concerning implementation of the APSLMP or any such subsequent MOU.

PUBLIC DRAFT UMP:

- (1) The Public Draft which ORDA provides to the DEPARTMENT for release by the DEPARTMENT for public review and comment will contain appropriate SEQRA documents.
- ORDA will provide copies of the Public Draft to the DEPARTMENT for release to Agency members, the Agency's Executive Director and the Agency's State Land staff. Upon release of the Public Draft,

 DEPARTMENT staff, with assistance from ORDA staff as requested, will

provide a presentation to the Agency on the proposed management actions contained in the Public Draft and provide a written submission to the Agency discussing the DEPARTMENT's position on key APSLMP conformance issues.

(3) If the initially released Public Draft is revised, subsequent drafts will be entitled "Revised Public Draft" and dated appropriately.

FINAL UMP:

- After completion of public review and comment on a UMP, ORDA shall prepare a response to public comments, necessary SEQR documentation and a proposed Final UMP, and provide them to the DEPARTMENT.

 After the Commissioner of the DEPARTMENT ("Commissioner") approves the proposed Final UMP, the DEPARTMENT will transmit the proposed Final UMP to the Agency.
- (2) The proposed Final UMP will be in a form proposed for approval by the Commissioner.
- (3) DEPARTMENT staff, with such assistance from ORDA staff as may be requested, will make a presentation on the proposed Final UMP to the Agency as a "first reading" and prior to formal approval by the Agency for APSLMP conformance.
- (4) Following the conformance determination by the Agency and subsequent approval of a UMP by the Commissioner, the DEPARTMENT shall

publish a notice of approval of the Final UMP in the Environmental Notice Bulletin.

(5) The approved UMP shall contain a copy of the Agency resolution on APSLMP conformance and the Commissioner's approval memorandum.

A copy of the Final UMP as approved by the Commissioner will be provided by the DEPARTMENT to ORDA and the Agency for their respective files.

D. <u>UMP Amendments</u>

Any modification involving new or expanded improvements to an adopted UMP prior to the periodic five-year update must be processed as an Amendment to the UMP following the procedure for original UMP preparation set forth above."

- 3. This Consolidation Agreement shall commence on the date it is signed by both parties and shall remain in effect for a term of twenty years.
- 4. The MOU as amended on March 11, 1991, shall remain in full force and effect and shall not be affected by this Consolidation Agreement, except that in the case of any inconsistency between this Consolidation Agreement and the MOU concerning unit management planning this Consolidation Agreement shall control.

IN WITNESS WHEREOF, the parties hereto have caused these present to be signed.

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

BY: Joseph J. Martens
(Commissioner

0/30/13 Date

OLYMPIC REGIONAL DEVELOPMENT AUTHORITY

President and CEO

Date

EDMS #471942 v. 7

FIRST AMENDMENT TO CONSOLIDATION AGREEMENT (DEC No.CA00488)

THIS AGREEMENT is made by and between the NEW YORK STATE

DEPARTMENT OF ENVIRONMENTAL CONSERVATION ("DEPARTMENT") and the

OLYMPIC REGIONAL DEVELOPMENT AUTHORITY ("ORDA").

- A. WHEREAS, the DEPARTMENT has administrative jurisdiction over the Gore Mountain Ski Center Area, the Whiteface Mountain Ski Center and Memorial Highway, and the Mount Van Hoevenberg Recreation Area;
- B. WHEREAS, pursuant to the provisions of Public Authorities Law Section 2614, the DEPARTMENT entered into various cooperative agreements authorizing ORDA to use, operate, maintain and manage these facilities;
- C. WHEREAS, by instrument dated November 11, 2013, the parties consolidated their various agreements concerning ORDA's use, operation, maintenance, and management of Gore Mountain Ski Center Area, Whiteface Mountain Ski Center and Memorial Highway, and the Mount Van Hoevenberg Recreation Area (hereinafter referred to as "Consolidation Agreement");
- D. WHEREAS, the Parties may by mutual agreement amend the Consolidation Agreement pursuant to the underlying agreements;
- E. WHEREAS, the Consolidation Agreement has a term of 20 years, and will expire November 11, 2033; and
- F. WHEREAS, the parties have determined it is in their interest to amend the Consolidation Agreement by extending its term to 25 years.

NOW, THEREFORE, the parties hereby agree as follows:

- 1. Section three of the Consolidation Agreement is amended to provide that it shall terminate on December 31, 2040, unless modified in writing by the parties.
- 2. All other terms all terms and conditions of the Consolidation Agreement shall remain in full force and effect.

IN WITNESS WHEREOF, the parties hereto have caused these present to be signed.

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

BY: `

Joseph J Martens

OLYMPIC REGIONAL DEVELOPMENT AUTHORITY

RY.

Ted Blazer

President and CEO

Data

EDMS #534278

MEMORANDUM OF UNDERSTANDING

BETWEEN

THE DEPARTMENT OF ENVIRONMENTAL CONSERVATION


AND

THE OLYMPIC REGIONAL DEVELOPMENT AUTHORITY

THE DEPARTMENT OF ENVIRONMENTAL CONSERVATION ("DEC") and THE OLYMPIC REGIONAL DEVELOPMENT AUTHORITY ("ORDA") entered into the following agreements in connection with the transfer of the management of certain winter recreational facilities under DEC's care and custody, to ORDA:

- Agreement dated October 4, 1982, amended November 10, 1982 and amended April 1, 1984, in relation to Whiteface Mountain Ski Center and Memorial Highway, and Mt. Van Hoevenberg Recreation Area, and
- Agreement dated April 1, 1984, in relation to Gore Mountain Ski Center.

There are a number of provisions in the aforesaid agreements requiring that certain specific actions be taken from time-to-time by the parties, including compliance by ORDA with all applicable laws and implementing regulations, whether federal, state or local, in all its activities relating to the facilities subject to the aforesaid agreements. The purpose of this memorandum is to establish mutually agreeable methods and procedures by which certain managerial requirements contained in the aforesaid agreements



can be fulfilled in an orderly and efficient manner. It is the further purpose of this memorandum to establish the means for the implementation of the Unit Management Plans described in Section VII. hereof.

It shall be the responsibility of the signatories or their designees to generally administer the provisions of this Memorandum of Understanding. This memorandum amends and supersedes that certain existing Memorandum of Understanding between DEC and ORDA effective December 15, 1984, which established mutually agreeable methods and procedures for implementation of the aforesaid agreements between DEC and ORDA relating to Whiteface Mountain Ski Center and Memorial Highway, Mt. Van Hoevenberg Recreation Area and Gore Mountain Ski Center.

The aforesaid requirements contained in the aforesaid agreements are set forth below, together with the methods and procedures to be followed for their implementation.

Compliance with this memorandum and the individual Unit Management Plans for the above facilities shall occur immediately.

I. <u>Inspections</u>:

ORDA agrees to conduct a joint inspection of all facilities at least annually with the DEC. The ORDA also agrees that the DEC may conduct unannounced inspections of the facilities at any time in a reasonable manner.

Implementation:

Annually, during the month of July, joint inspections will be held at each of the facilities covered by the aforesaid agreements. The purpose of inspections shall be to document, in writing, compliance with all aspects of the agreements and with the aforesaid unit management plans. While the agreements allow for unannounced inspections, the parties shall enter into this agreement in the spirit of cooperation. DEC shall contact the ORDA Environmental Monitor and the Facility Manager to accompany the DEC staff only in connection with any non-regulatory or non-enforcement inspections of the facilities other than the annual inspection. Such non-regulatory or non-enforcement inspections, however, shall not be delayed due to the unavailability of said ORDA individuals. the event of an emergency situation involving a non-regulatory or non-enforcement matter, said ORDA personnel shall also be contacted to the extent practicable. In ORDA's case, the annual inspection and non-regulatory or non-enforcement inspections will be conducted by the Facility Manager and ORDA's Environmental Monitor. In DEC's case, all annual joint inspections will be coordinated by the Region 5 Supervisor of Natural Resources; all non-regulatory or non-enforcement inspections shall

be coordinated by the appropriate DEC program supervisor.

II. Maintenance:

ORDA agrees to maintain and keep the facilities, personal property and equipment in good repair. All mechanical equipment shall be maintained and operated in accordance with manufacturers' recommendations and applicable industrial code rules.

Implementation:

This will be discussed during the annual inspection trips. A paragraph in the inspection letter will reference compliance with this section. In the case of personal property and equipment, this provision means such personal property and equipment owned by DEC, and not such personal property and equipment independently acquired by ORDA.

III. Repairs:

ORDA also agrees to undertake any repairs or manner of repairs to the facilities, personal property and equipment which the DEC specifically requests, so long as the funds therefor are made available to ORDA.

Implementation:

Any requests from DEC to ORDA shall be in writing at the time of request. During the annual inspection trip, if there are projects that were requested during the previous year, their completion should be referenced in the inspection letter.

IV. Public Recreation:

ORDA agrees to continue providing the space, facilities and level of public recreation, including youth sports, training, promotion and programming, which were provided by DEC at each facility during calendar year 1981.

Implementation:

The Appendix/Exhibit listing the Recreation Program (See Appendix B of the aforesaid Whiteface Mountain Ski Center/Mt. Van Hoevenberg Recreation Area agreement, and Exhibit 3 of the aforesaid Gore Mountain Ski Center agreement.) will be reviewed during the annual inspection trip and a note of compliance will be placed in the inspection letter.

V. Existing Agreements:

ORDA agrees to comply with all agreements
to which DEC is a party concerning the
facilities which were in existence on the date on
which this Agreement was executed.

Implementation:

Each agreement listed in the Appendix/Exhibit

(See Appendix C of the aforesaid Whiteface

Mountain Ski Center/Mt. Van Hoevenberg Recreation

Area agreement, and Exhibit 4 of the aforesaid Gore

Mountain Ski Center agreement.) will be reviewed

during the annual inspection trip and will

be referenced in the inspection letter.

VI. <u>Capital Improvements:</u>

The DEC agrees that ORDA may undertake capital improvements to the facilities. ORDA agrees to obtain the prior written approval of DEC before undertaking any such improvements, and further agrees, if federal funds are to be sought for such improvement, to obtain the prior written approval of DEC of any application for such funds.

Implementation:

The Commissioner or his designee shall give written approval to each year's capital projects affecting

DEC's facilities before Board approval is obtained. Such action constitutes approval, within budget, to commence the project development process, including planning and design, Unit Management Plan planning, State Environmental Quality Review Act (SEQR) review, obtaining applicable regulatory approvals, and public bidding, etc., as necessary. ORDA shall also request prior written approval from the Commissioner or his designee for any federal funds sought to undertake such capital improvements. During the annual inspection trip, each capital improvement completed shall be listed in the inspection letter.

VII. Unit Management Plans:

Unit Management Plans, together with Final
Environmental Impact Statements, were prepared by
ORDA and DEC, in consultation with the APA, and
adopted by the Commissioner of Environmental
Conservation for the Mount Van Hoevenberg Recreation
Area on December 2, 1986; the Whiteface Mountain Ski
Center on May 19, 1987; and the Gore Mountain Ski
Center on November 18, 1987.

Implementation:

A. ORDA will provide DEC with specific notice prior to undertaking any management actions described in a

Unit Management Plan or in an amendment thereto for determination of consistency with the applicable
Unit Management Plan. (See Appendix I for Unit
Management Plan amendment process). Such notice
shall be given at least 30 days prior to the actual
undertaking of construction of the management
action. Such notice will include a project plan,
the appropriate environmental assessment as may be
required under SEQR, an erosion control plan for
any projects that may result in disturbance of
soils, together with the declaration of
significance. It is understood that DEC will be an
"involved agency" concerning these actions
throughout the SEQR process.

- B. ORDA shall comply with all formal DEC policies or delegations affecting Unit Management Plan compliance by DEC.
- C. The Unit Management Plans provide that the cutting of trees associated with the implementation of management actions will be in accordance with the established policies and procedures of the Commissioner of Environmental Conservation (See Appendix II Organization and Delegation Memorandum #84-06, as amended). The DEC procedures will be initiated by the Regional Forestry Manager for DEC upon notice by the ORDA facility manager

that tree cutting is contemplated in conjunction with a management action. The Regional Forestry Manager will inform the ORDA facility manager within five working days, in writing, as to whether the · cutting may proceed or that notice will be required in the Environmental Notice Bulletin ("ENB") and that the cutting will be reviewed pursuant to the DEC tree cutting policy. Should notice be required, ORDA will provide DEC with the appropriate ENB notice including the designated contact person. The DEC will then complete the notice requirements and inform ORDA as to the decision in writing upon completion of the review It is agreed that Environmental Notice Bulletin publication and DEC review will not be required in cases where the tree cutting was specifically described in the detail required by the DEC policy in the Unit Management Plan and noticed in the ENB in the process of adoption of the Unit Management Plan or an amendment thereto. Such notice must include a count of the number of trees to be removed which exceed three inches in diameter and the acreage of land involved. will such notice and review be required where a tree cut could constitute a "Type II Action" under the DEC rules and regulations governing the

implementation of SEQR (6 NYCRR 618.2). Any trees cut in accordance with this section can be removed from the premises in any manner deemed feasible by ORDA so long as such method is consistent with the guidelines of the State Land Master Plan, the Unit Management Plan, Article 8 of the ECL, and Division Direction Memorandum LF-84-2 dated May 31, 1984 and LF-84-2 Supplement dated July 3, 1986. (See Appendix III).

- D. A new structure or improvement not described in a Unit Management Plan, or in an amendment to a Unit Management Plan, cannot be undertaken or constructed. This provision, however, does not prevent ORDA from undertaking the construction of the following activities, provided that all conditions in Items A, B, and C above are fully complied with and implemented.
- 1. Ordinary maintenance, rehabilitation and minor relocation of conforming structures or improvements as defined and interpreted in the DEC-APA Memorandum of Understanding governing implementation of the State Land Master Plan (SLMP), as last amended on April 3, 1985.

- 2. A change in the use of a structure or improvement as described in a Unit Management Plan that is not inconsistent with the guidelines and criteria of the SLMP for intensive use areas,
- 3. Any facility or structure that is listed as a Type II Action in the DEC rules and regulations governing the implementation of SEQR (6 NYCRR 618.2) and, in particular, the construction and location of single, small, new or existing facilities or structures where the total area of the structure or expansion does not exceed 400 square feet and the surroundings are returned to their original condition after the construction/installation of the structure or facility.
- 4. Any project consisting solely of the cutting of not more than ten (10) trees more than 3 inches in diameter at breast height.
- 5. Any action deemed immediately necessary to insure public health or safety. In such cases DEC will be immediately notified of the situation and what the proposed or ongoing action consists of.
- E. The <u>Unit Management Plans will be administered</u> on a day-to-day basis by the Environmental Monitor for ORDA and the Region 5 Supervisor of Natural Resources for DEC. Notification of project

implementation, concerns dealing with potential environmental problems, requests for change in preapproved action plans, need for Unit Management Plan amendment and other similar communication will all take place between the Environmental Monitor for ORDA and the Region 5 Supervisor of Natural Resources for DEC. Agreements made by these individuals will be binding on both agencies. If agreement cannot be reached on a specific issue, the issue will be elevated in the respective agencies for resolution.

VIII. Removal of Property and Equipment:

No part of any facility, nor personal property or equipment of DEC used in connection therewith, shall be sold or removed from the facility without the prior written approval of DEC.

Implementation:

DEC currently maintains a computer program for the inventory of property. All DEC equipment transferred to ORDA is part of that inventory. DEC shall supply appropriate forms to ORDA and ORDA will advise DEC via the forms when equipment is surplused, destroyed or when new DEC equipment is acquired. DEC shall maintain the inventory and shall annually certify with ORDA that the list is

correct. Lead role in DEC for the above items is vested in the Division of Operations Central Office.

This Memorandum of Understanding will become effective upon its execution by each of the parties hereto.

DEPARTMENT OF ENVIRONMENTAL CONSERVATION

BY: Mraw Colling, Commissioner

Date March 11, 177/

OLYMPIC REGIONAL DEVELOPMENT AUTHORITY

BY: Wed Harkness

Ned Harkness, President, C.E.O.

Date March 8, 1991

APPENDIX I

REVISION/AMENDMENT TO UNIT MANAGEMENT PLANS

- 1. Any material modification or amendment to the unit management plans is to conform to the guidelines and criteria of the SLMP, and will be made following the same procedure prescribed in the master plan for original unit management plan preparation.
- 2. A proposed amendment will be presented in its complete form and content, including indication of the specific sections of the existing management plan being amended, and be accompanied by:
 - (A) An evaluation of whether or not the proposed amendment will require a reexamination of the inventory and assessment section of the plan.
 - (B) If the amendment represents a departure from the goals and objectives stated in the plan, a discussion of impacts of the new objectives on facilities, public use and resources of the unit.
 - (C) An assessment of whether or not the proposed amendment is consistent with carrying capacity of the area.
 - (D) A schedule for the implementation of proposed management actions.

Any action to amend a unit management plan in connection with a proposed management action is to be initiated no later than the required site-specific environmental assessment pursuant to SEQR.

ORDA and DEC will cooperate and provide such staff assistance as may be necessary in the preparation of amendments to the unit management plans. Both agencies will designate an appropriate representative to be the lead contact person in the matter. Division of Responsibility shall be as follows.

Develop and make appropriate revisions, in response to comments, to all documents. These will include the actual plan and accompanying SEQR.

Provide for public comment including hearings/ meetings. Make a record of comments and responses.

Print and distribute all draft and final documents.

Present draft documents to designated DEC contact for DEC review, including the SEQR committee, posting in the Environmental Notice Bulletin, APA review and DEC Commission's final approval.

DEC -

Provide assistance to designated ORDA representative on format and procedure.

Coordinate APA review and comments.

Coordinate DEC review, comments and final approval.

Coordinate all notices in the ENB.

APPENDIX II

MENCHANDUN FROM HENRY O. WILLIAMS, Commissioner

New York State

Fedanment of Environmentor Copyletyation

FEB 13 :: 1984

February 1.6, of 8.4 nmental Conservation Segment Figure 5 Page 100 Page 10

TO:

Executive Staff, Division and Regional Directors

FROM:

Hank William 17

RE:

ORGANIZATION AND DELEGATION MEMORANDUM #84-06

Purpose:

To establish a policy regarding the prohibition of cutting, removal or destruction of trees and other vegetation on all Forest Preserve lands pursuant to Article XIV of the Constitution of New York State.

Background:

Article XIV of the Constitution specifically states that the timber on the Forest Preserve shall not "...be sold, removed or destroyed." Over the years it has been necessary to occasionally cut trees in the interest of public safety, overall protection of the Preserve and for the development of facilities. Such cutting has been sanctioned through Consitutional Amendment or by Opinion of the Attorney General, who has interpreted the Constitution as allowing such cutting.

Policv:

(... i

Section 9-0105 of the Environmental Conservation Law provides that the Division of Lands and Forests has responsibility for the "care, custody and control" of the Adirondack and the Catskill Forest Preserve. In accordance with this responsibility, all construction of new facilities, empansion or modification of existing facilities and maintenance of facilities, that will result in the cutting, removal or destruction of vegetation on any of the lands constituting the Forest Preserve shall require approval of the Director of the Division of Lands and Forests in accordance with the following Procedure. However, under no circumstances will approval be granted for the cutting of trees for firewood, timber or other forest products purposes.

Procedure:

A. Construction of New Facilities and the Expansion or Modification of Existing Facilities

All projects that involve the cutting, removal or destruction of trees or other vegetation in the Forest Preserve must have approval from the Director of the Division of Lands and Forests to be applied for in the following manner:

1. Regional Facilities

Requests for approval will be submitted by the Regional Director to the Director of the Division of Lands and Forests

2. Non-Regionalized Facilities

Requests for approval will be submitted by the Director of the Division responsible for the facility to the Director of the Division of Lands and Forests

Requests for approval to cut, remove or destroy trees for the purpose of new construction, expansion or modification projects must be submitted in writing and include the following information:

- The location of the project including a map delineating the project
- A description of the project and its purpose
- A count, by species, of all trees to be cut, removed or destroyed
- A delineation of areas where vegetation, in addition to trees three inches or more in diameter, is to be disturbed
- A listing of any protected species of vegetation located within three hundred feet of the area to be disturbed during the project
- A description of measures to be taken to mitigate the impact on and restoration of vegetation, if appropriate, to the area impacted

All decisions to approve any cutting, removal or destruction of trees will be subject to individual SEQR determinations.

B. Routine Maintenance

Responsibility for approval of all routine maintenance projects involving the cutting, removal or destruction of trees or other vegetation is delegated to the Regional Forester for the region in which the project is to occur.

Routine maintenance projects include the following activities:

- Maintenance of foot trails, cross-country ski trails, etc., including "the cutting of the few trees necessary..."
 (1934 A.G. 268 January 18, 1934.)
- Boundary line surveys and the maintenance of such boundary lines as "an aid to the conservation work of the State...where the number of small trees utilized or removed...appear immaterial (1934 A.G. 309 September 20, 1934.)
- Removal of "dead timber, either standing or fallen...for fuel at the public camp sites...." (1934 A.G. 315 October 30, 1934.)
- Maintenance of scenic vistas along trails when "tree removal may not be sufficient to pass the point of immateriality." (1935 A.G. 27-January 17, 1935.)
- Removal of dead and hazardous trees in developed areas such as campgrounds and ski centers "that endanger people." (1935 A.G. 30 June 26, 1985.)
- Salvage of windfall timber when "such blowdown timber constitutes a fire hazard." (1950 A.G. 154 December 28, 1950.)

1. Regional Facilities

Requests for approval of routine maintenance projects will be made to the Regional Supervisor for Natural Resources who will direct them to the Regional Forester.

2. Non-Regionalized Facilities

Requests for approval of routine maintenance projects will be made by the facility manager to the Regional Director of the Region in which the facility is located, who will direct them to the Regional Forester.

Requests for approval of routine maintenance projects should be submitted in writing as soon in advance of the date of beginning of the maintenance work as possible and include a description of the project and its location. If prior written or verbal approval cannot be obtained, hazardous trees involving imminent danger to human safety or damage to facilities may be removed without prior approval. However, such action must be reported within 24 hours following removal of the tree(s).

HENCHARD IN FACTA

New York Erdra Recomment of Environmental Consendation July 29, 1986

TO: Executive Staff, Division and Regional Directors

FROM: Hank Wit

SUBJECT: Organization and Delegation Memorandum #84-06: Addendum

Background:

The above memorandum was promulgated on February 16, 1984 "To establish a policy regarding the prohibition of cutting, removal or destruction of trees and other vegetation on all Forest Preserve lands pursuant to Article XIV of the Constitution of New York State."

Since that time it has come to our attention that the procedures established in the memorandum do not include provision for adequate notice to the public as to the number of trees proposed to be cut and the size of the land area involved on specific projects.

Amendment:

Therefore, Part A. under <u>Procedure</u> of Memorandum #84-06 is amended and expanded by the addition of the following paragraph at the end of such Part A. on page 2. of such Memorandum.

Any construction or reconstruction activity involving land under the jurisdiction of the Department of Environmental Conservation within the Adirondack or the Catskill Park-regardless of the classification of such land--that is a Type I action or otherwise recuires notice in the Environmental Notice Bulletin will include information in such notice as to the (1) acreage or extent of the land area proposed to be involved and (2) number of trees in excess of three inches stump diameter proposed to be cut, removed or destroyed. A copy of such notice as it appeared in such Bulletin (with the date of the Bulletin noted) will be included and made a part of the information constituting the request for approval just above described.

HEMORANDUM 511-1

July 3, 1986

TO: Chief, Bureau of Preserve Protection and Management Regional Supervisors for Natural Resources

FROM: Norman J. VanValkenburgh

SUBJECT: DIVISION DIRECTION -- LF-84-2 Supplement TOPIC: Cutting, Removal or Destruction of Trees and Other Vegetation on Forast Preserve Lands

As you will recall, Commissioner Williams promulgated Organization and Dalegation Memorandum #84-06 on Fabruary 16, 1984 for the purpose of "...establish(ing) a policy regarding the prohibition of cutting, removal or destruction of trees and other vegetation on all Forest Preserve lands pursuant to Article XIV of the Constitution of New York State." In order to implement the provisions of #84-06, this Division issued procedures on May 31, 1984 under designation LF-84-2.

However, the question of whether or not live-standing trees could be cut and used for maintenance of trails including "the construction of structures such as foot bridges, dry treed and water bars" remained. Accordingly, an opinion on this question was formally requested of the Attorney General on November 8, 1965. A copy of such request is attached hereto for information and clarification purposes.

A reply from the Attorney General under date of June 24, 1986 has now been received. A copy of such Formal Opinion No. 86-F3, which allows for the "supervised selective cutting...of only those few scattered trees necessary for the maintenance of popular and steep trails to lessen soil compaction, erosion and the destruction of vegetation within other specified constraints and parameters, is attached and made a part of this memorandum.

With Formal Opinion No. 86-F3 in hand, it is appropriate to now revise Division Direction-LF-84-2 to incorporate those added authorities. Accordingly, paragraph 1 (page 4) of Part II of LF-84-2 is hereby deleted and the following substituted therefor:

 Maintenance of foot trails, snowmobile trails, cross-country ski trails, horse trails.

This includes projects that involve blowdown removal, hazard tree elimination (3° or more in diameter), problem tree removal (3° or more in diameter), mowing, etc.

Applications may be submitted by Area if appropriate (i.e., High Peaks Wilderness Area, St. Regis Canoe Area, Saranac Lake Wild Forest, Whiteface Mountain Intensive Use Area, etc.). Trails should be listed separately with the total length of the trail covered by a single Application, if appropriate, and in priority order of needed maintenance.

Live-standing trees may be cut or used for the construction of bridges, dry tread, waterbars or other minor trail structures only after considering the following alternatives and in accordance with the following conditions:

- A. Alternatives to any type of trail hardening or structural development must be considered, especially in wilderness areas where such structures diminish the character of the area. Such alternatives include the closing or limitation of use of a trail where the impact of such use is leading to degradation of the other resources and the character of the Forest Preserve. A second alternative is to relocate the trail in such a way that trail hardening would not be necessary.
- B. If, after considering the above alternatives, it is determined that structures are needed to protect the surface of the trail or the safety of the public, the following materials should be considered in order of priority:
 - 1. Native rock or stone from near the site.
 - 2. Native rock or stone from another location brought to the site.
 - 3. Peeled, but untreated timber or logs from another location brought to the site.

- 4. On-site trees in accordance with the conditions under C. following.
- C. If on-site trees are to be used, such use must be in accordance with the following conditions:
 - 1. The Regional Forester or his designated representative must approve all trees to be cut, after considering any other previous cutting that has been done in the area.
 - Cutting must be discreet with tops fully lopped and dispersed out of sight of the trails, and with stumps cut flush to the ground.
 - 3. Live trees must be between three to twelve __ inches in diameter (DSH), and must be at least 100 feet apart.
 - 4. Structures requiring the use of live on-site trees are not to be replaced more frequently than 7-10 years, which is the range of normal life expectancy.

Dead and downed material may be used for such purposes although consideration must be given to human safety and the longevity or life of such structures when such material is used.

Director of Lands and Forests,

Attachments

cc: D. Grant;

H. Doig

J. Corr

G. Colvin

G. Sovas

K. Wich

R. Bernhard

Regional Directors
Bureaus of Fish and Wildlife
Bureaus of Lands and Forests
Bureaus of Marine Resources
Bureaus of Mineral Resources

MENORAND M

May 31, 1984

TU: Chief, Bureau of Preserve Protection and Management Regional Supervisors for Natural Resources

FRCM: Norman J. Vanvalkenburgh

SHIMECT: DIVISION DIRECTION - LF-84-Z.

PURPOSE: The purpose of this momorandum is to establish administrative procedures for the implementation of Commissioner Williams' Organization and Delegation Mamorandum #84-06 relating to the construction of new facilities, the expansion or maxification of existing facilities and routine maintenance projects on lands of the Forest Preserve.

Such Organization and Delegation Memoranoum states, in part: P. M. SCHENDE "Section 9-0105 of the Environmental Conservation Law provides that the Division of Lancs and Forests has responsibility for the 'care, custody and control! of the Adironcack and the Catskill Forest Preserve. In accordance with this responsibility, all construction of new facilities, expansion or modification of existing facilities and maintenance of facilities, that will result in the cutting, removal or destruction of vegetation on any of the lands constituting the Forest Preserve shall require approval of the Director C: the Division of Lands and Forests.... In order to carry out this direction and policy, the succeeding procedures will be tollowed by regional and non-regionalized personnel in requesting approval for such projects on lancs of the Forest Preserve that involve the cutting, removal and/or destruction of vegetation. In all cases, the provisions and constraints of the Organization and Delegation Manorandum will be recognized and complied with.

Fig. I - Construction of New Facilities and the Expansion or Fooification of Existing Facilities

PRICESS AND CALENLAR

Uctober-November

Regional Operations
Supervisor or Emnager of
Non-Regionalized Facility

 Following conceptual agreeval of the project by the Regional and/or appropriate Central Divisional Utilias, prepares a

October-November (Cont'd)

Forest Preserve Project Fork Plan in the form attached hereto as Ampendix A for each projected project.

Pach such Plan shall include: (1) A description of the project and its purpose, (2) A sketch map delineating the project and showing its location, (3) A count by species and size class, of all trees to be cut, removed or destroyed, (4) Identification of any protected species of vegetation within 300' of the area to be disturbed, (5) A description of measures to be taken to mitigate the impact on vegetative cover, and (6) Proposed use of motorized equipment or motor vehicles, if any.

- 2. Submits completed Work Plan to the " The Regional Supervisor for Natural Resources.
 - 3. Reviews Work Plan for completeness and conformance to Delegation Memorandum #84-06 and forwards to the Regional Forester.

December

kegional Forester.

Regional Supervisor for Natural Resources

- 4. Enters receipt of Work Flan in Regional Isy of Forest Preserve Projects (See Appendix Brattached).
- 5. Reviews Forest Preserve Project Work Plan to determine if project is appropriate taking into consideration Forest Preserve land classification, Unit Management Plan goals and management objectives for the land area involved.
- Makes on—site field inspections as necessary and appropriate.
- 7. Insures that SECR requirements for each project have been addressed.
- Consults with Operations Supervisor or Facility Menager to effect any changes or modification to work Plan.
- 9. Signs work Plan signifying approval or indicates disapproval by stating reasons in Comments Section. If approved, forwards Work Plan through Regional Supervisor for Matural Resources to Regional Director or appropriate Division Director, in the case of non-regionalized facil-

December (cont'a)

ities. If disapproved, returns bork Plan to originator.

10. Campletes Regional Lag.

January

Regional Director or Director of Division responsible for Facility

- Reviews forest Preserve Project Work Plan.
- 12. Signs Fork Plan signifying approval or indicates disapproval by stating reasons in Comments section.
- 13. If approved, forwards work Plan to Dir- : ector of Lancs and Forests. If disapproved, returns Work Plan through Regional Supervisor for Natural Resources and Regional Forester to originator.

: February

Director of Lands and Forests

- 14. Effects review of Work Plan by appropriate Central Office staff to determine that Plan conforms to Division goals and is in keeping with responsibility for care, custody and control of lancs of the Forest Preserve.
- 15. Signs Work Plan signifying approval or indicates disapproval by stating reasons in Comments section.
- 16. Returns Work Plan to Regional Director or appropriate Division Director.

. .

march

Regional Director or Director of Division responsible for Facility 17. Distributes Nork Plan through Regional Supervisor for Ratural Resources and Regional Forester to originator.

Current Fiscal Year

Regional Operations Supervisor or Lanager or Non-Regionalized Facility

Regional Porester

- 18. Implements project in accordance with Work Plan approvals and conditions.
- 19. Ponitors implementation of Work Plan to insure conformance to approvals and conditions.

Current Fiscal Year (cont'd)

. 20: On completion of project, completes Inspection Report (See Appendix C attached) and retains in Project file.

PAKT II - Routine Maintenance Projects

PKCLLS

Application for routine maintenance projects on lands of the Porest Preserve shall be submitted on the form attached hereto as Appendix D as soon as possible in advance of the starting cate of the project. The Application should be directed to the Regional Supervisor for Natural Resources who will forward it to the Regional Forester. The Application will be reviewed as rapidly as possible by the Regional Forester and a determination made as to approval or ··-- disapproval.

When approvals have been granted, a copy of the Application will be forwarded to appropriate Regional Lance and Forests personnel to assure proper notification and provide for monitoring of the project.

Applicants should consider the following quicelines when submitting project requests:

Maintenance of foot trails, snowmobile trails, cross-country ski trails, horse trails, ctc.

This includes projects that involve blowdown removal, hazard tree elimination (3" or more in diameter), problem that removal (3" or more in diameter), mowing, etc.

Applications may be submitted by Area if appropriate (i.e., High Peaks Wilderness Area, St. Regis Canos Area, Saranac Lake Wild Forost, Whiteface Mountain Intensive Use Area, etc.). Trails should be listed separately with the total length of the trail covered by a single Application, if appropriate and in priority order of needed maintenance. It is clearly understopp that live stanning traces are not to be dut or used for construction of bridges, dry tread, water bars or other structures. Dead and downed material may be used for such purposes although consideration must be given to human safety and the longevity or life of such structures when such material is used.

Maintenance of reads, 'phone lines; power lines, ski lifts, comphill ski trails, cance carrys, parking areas, openings around buildings, scenic

this includes projects that involve the removal of hazardous, problem or coye trees 3" or more in diameter.

Projects should be listed individually but, several may be submitted on a single Application it they are similar in nature (i.e., 'phone lines A. B, & C). Tree dants are advisable where more than an excasional live tree must be cut to avoid potential damage to the facility or dustion. Felled trees may not be utilized for any purpose and should in the tree near the site so as not to interfere with the tacility and to the properties of the site.

kemoval of dead and hazardous trees in developed arear. the accomportunds and ski centers that cotentially encanger people.

This includes projects involving removal of duag and includes and inclu

Applications should be submitted separately for who included of simple Application. Tree counts should be included with the Application. Trees that are proposed to be removed should be flagged. Trees that are up and used for fuel at the facility, but for no other purposes.

4. Boundary line surveys and maintenance.

This includes all projects on lands of the forest Income whether come by Dapartment employees or by others under contract to II. Tepertment.

More than one survey project may be included on a : Included on : Included on a : Included on a : Included on

5. Salvage of winotall timber when such blowdown timber count Tites a fire hazard.

This includes projects of fire hazard circumstance: as should be submitted on Applications for each Area involved.

In any of the above situations, projects will be characteristics by the Regional Forester.

Director of Lines and tels

Attachments

cc:

D. Grant

H. Loiy

G. Colvin

G. Sovas

K. Wich

R. bernharu

kerional Directors

Eureaus of Fish and Wildlife

· bureaus of Lanas and Forests

Hureaus of Farine Jascurous

buresus of Mineral Resources

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION DIVISION OF LANGS AND FORESTS

Forest Preserve Project Work Plan . for

Construction of New Facilities and the Expansion or Accification of Existing Facilities

Region/Facility	Project Title & Location	Land Classification	Project No
	•		•
Pacariarias (Justifica			
Description & Justific Required Supporting Do	duments):	wan suppring recarred	am other
	وموالفات معاروا كالممالوا أوكانا الأ	ر الله الله الله الله الله الله الله الل	and the second second second second
	•	•	
•			••
Description of Use of	Motoriwed Equipment o	or Motor Vehicles, if	any:
•	•		
. •			•
•	•	•	•
	• 4	•	
Prepared By:	. Dats	≥:	
APPROVALS OR DISAPPROV	ALS	•	
	Cam	ments:	
Late:			
		•	•
Regional Forester			•
late:	The state of the s	•	• *
•			
Regional Supervisor to	Ľ.		
Natural Resources			
•		•	•
Date:			•
		•	•
Regional Director or			•
Division Director			
		•	
		•	•
Date: 1			•

·	; ·· :	٠,		<.,:		÷			··	· · · · · ·	; <u> </u>	,				·" •.		
	:		1:	L/66/19	÷		T.USEE	MICZ	L.P.	GFF!CE	1	518	523	147128	669	P.14	•	
D	•	•		: ,		incicaing · Disaρρτονal on							•			•	-	•
	en e	F. Y.	4.4.			. Approval or D Action	7,4 of	· • • • • •		(• •• • • • • • • • • • • • • • • • • • •		i Record Tiggi esercit	· .		•		
	٠.	RECTON			1. C	Approval or Disapproval	-	•				· · · · · · · · · · · · · · · · · · ·	•	•			•	
						Dates of Inspection	-		***	•		• •	• • •	e de la constante de la consta	•	e .		
	Tirers	;	•	Project: 	7777	Fací.						•				· .• -	١,	-
,	201 (2)3			Pr.0	ಕಾಯಾಗುಡ	inisi1	,							•				
9	REGIONAL LOG FRAFSTY PAFSERME PRÔJECTS	ť	A Company of the Comp		-	,						•	•			•		
	<u> </u>		*			Project Description						•	÷.			•	•	
				•	,	Project					•		-			•		
			,		•													
3		•				Originator									•	•.		
		٠.			ММН (колонице) по верто по вети по се	. Plan ived		years and the second and the										

11/05/1990 15:52 T.ULASEWICZ L.P. OFFICE 1 518 523 14712569 P.15 11/5P5CIION REFORM

FOREST PRESERVE PROJECT

PROJECT NO.:		,	
e de figura de la como br>A transferancia de la como de la c		•	
PROJECT LOCATION:		-	
PROJECT DESCRIPTION:	•		<u>=</u>
· (A.)		*	
	. *	•	ayanagarashainfinifininin seenaanaartimaan ariiittaan
TREES CUT (NO. & SPECIES):	andre i e e e e e e e e e e e e e e e e e e	*	
VEGETATION DISTURBED AND MITIGATING ACTIONS TA	iœa:		
	:	·	•
			•
CO-MENTS:			

•			

11/95/1990 15:52 T.ULFSEWICZ L.P. OFFICE 1 518 527 14712669 P.16 APPLICATION FOR POSTENE MAINTENANCE PROJECT

REGICA:		PROJECT: #
		• .
7 DDF 7CNNm NAUT		
APPLICANT NAME:		DATE OF APPLICATION:
engan kombooksi.		
ADDRESS:		OTHER CONTACT PERSON:
		·

	•	
	•	•
LCCNTION OF PROJ	ect/s:	
•		
		• •
	*	
· .		
DESCRIPTION OF P	ROJECT/S: (Attache	ed additional sheets if necessary) :
DESCRIPTION OF P	rOJECT/S: (Attache	ed additional sheets if necessary)
DESCRIPTION OF P	POJECT/S: (Attache	ed additional sheets if necessary)
DESCRIPTION OF P	rOJECT/S: (Attache	ed additional sheets if necessary)
DESCRIPTION OF P		ed additional sheets if necessary)
	₩	
WHO IS 'TO DO WOR	UK: NG DATE:	
WHO IS TO DO WOR	UK: NG DATE:	
WHO IS TO DO WOR	UK: NG DATE:	
WHO IS TO DO WOR ESTIMATED STARTIN	UK: NG DATE:	
WHO IS TO DO WOR	UK: NG DATE:	
WHO IS TO DO WOR ESTIMATED STARTIN	NG DATE:	
WHO IS TO DO WOR ESTIMATED STARTIN APPLICANT SIGNAT PROJECT ACTION:	NG DATE:	ESTIMATED COMPLETION DATE:
WHO IS TO DO WOR ESTIMATED STARTIN APPLICANT SIGNAT PROJECT ACTION:	NG DATE:	

Appendix 3 Correspondence

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

Division of Fish and Wildlife, New York Natural Heritage Program 625 Broadway, Fifth Floor, Albany, NY 12233-4757 P: (518) 402-8935 | F: (518) 402-8925 www.dec.ny.gov

September 26, 2017

Robert Fraser NYS Olympic Regional Development Authority 40 Long Alley Saratoga Springs, NY 12866

Re: Gore Mountain Ski Center

County: Warren Town/City: Johnsburg

Dear Mr. Fraser:

In response to your recent request, we have reviewed the New York Natural Heritage Program database with respect to the above project.

Enclosed is a report of rare animals that our database indicates occur in the vicinity of the project site.

For most sites, comprehensive field surveys have not been conducted; the enclosed report only includes records from our database. We cannot provide a definitive statement as to the presence or absence of all rare or state-listed species or significant natural communities. Depending on the nature of the project and the conditions at the project site, further information from on-site surveys or other sources may be required to fully assess impacts on biological resources.

Our database is continually growing as records are added and updated. If this proposed project is still under development one year from now, we recommend that you contact us again so that we may update this response with the most current information.

The presence of the animals identified in the enclosed report may result in this project requiring additional review or permit conditions. For further guidance, and for information regarding other permits that may be required under state law for regulated areas or activities (e.g., regulated wetlands), please contact the NYS DEC Region 5 Office, Division of Environmental Permits, as listed at www.dec.ny.gov/about/39381.html.

Sincerely,

Colleen Lutz

Assistant Biologist

New York Natural Heritage Program

1162





Report on Rare Animals, Rare Plants, and Significant Natural Communities

The following rare animal has been documented at the project site.

We recommend that potential onsite and offsite impacts of the proposed project on these species or communities be addressed as part of any environmental assessment or review conducted as part of the planning, permitting and approval process, such as reviews conducted under SEQR. Field surveys of the project site may be necessary to determine the status of a species at the site, particularly for sites that are currently undeveloped and may still contain suitable habitat. Final requirements of the project to avoid, minimize, or mitigate potential impacts are determined by the lead permitting agency or the government body approving the project.

The following animal, while not listed by New York State as Endangered or Threatened, is of conservation concern to the state, and considered rare by the New York Natural Heritage Program.

COMMON NAME SCIENTIFIC NAME NY STATE LISTING HERITAGE CONSERVATION STATUS

Bicknell's Thrush Catharus bicknelli Special Concern Imperiled in NYS

Breeding

Gore Mountain, on the project site, 0.25 mile northeast of the State Fire Tower, 2005-su: The birds were encountered in spruce/fir forest with a canopy height of 5 to 7 meters.

12171

This report only includes records from the NY Natural Heritage database. For most sites, comprehensive field surveys have not been conducted, and we cannot provide a definitive statement as to the presence or absence of all rare or state-listed species. Depending on the nature of the project and the conditions at the project site, further information from on-site surveys or other sources may be required to fully assess impacts on biological resources.

If any rare plants or animals are documented during site visits, we request that information on the observations be provided to the New York Natural Heritage Program so that we may update our database.

Information about many of the rare animals and plants in New York, including habitat, biology, identification, conservation, and management, are available online in Natural Heritage's Conservation Guides at www.guides.nynhp.org, from NatureServe Explorer at www.natureserve.org/explorer, and from USDA's Plants Database at http://plants.usda.gov/index.html (for plants).

9/26/2017 Page 1 of 1



ANDREW M. CUOMO

Governor

ROSE HARVEY
Commissioner

November 09, 2017

Mr. Robert Fraser Environmental Scientist The LA Group, P.C. 40 Long Alley Saratoga Springs, NY 12866

Re: APA

Gore Mountain Ski Center

793 Peaceful Valley Rd, Johnsburg, Warren County, NY

17PR07541

Dear Mr. Fraser:

Thank you for requesting the comments of the Office of Parks, Recreation and Historic Preservation (OPRHP). We have reviewed the project in accordance with the New York State Historic Preservation Act of 1980 (Section 14.09 of the New York Parks, Recreation and Historic Preservation Law). These comments are those of the OPRHP and relate only to Historic/Cultural resources. They do not include potential environmental impacts to New York State Parkland that may be involved in or near your project. Such impacts must be considered as part of the environmental review of the project pursuant to the State Environmental Quality Review Act (New York Environmental Conservation Law Article 8) and its implementing regulations (6 NYCRR Part 617).

Based upon this review, it is the New York State Office of Parks, Recreation and Historic Preservation's opinion that your project will have no impact on archaeological and/or historic resources listed in or eligible for the New York State and National Registers of Historic Places.

If further correspondence is required regarding this project, please be sure to refer to the OPRHP Project Review (PR) number noted above.

Sincerely,

Michael F. Lynch, P.E., AIA

Director, Division for Historic Preservation

Appendix 4 Adirondack Sub-alpine Forest Bird Conservation Area Description



Adirondack Sub-Alpine Forest Bird Conservation

Area

General Site Information: This BCA includes Adirondack Mountain summits above 2,800 feet - more specifically, those with dense subalpine coniferous forests favored by Bicknell's thrush. Bicknell's thrush prefers dense thickets of stunted or young growth of balsam fir and red spruce. Found less frequently in other young or stunted conifers, and heavy second growth of fir, cherry and birch.

Adirondack Sub-Alpine Forest BCA Management Guidance Summary

Site Name: Adirondack Sub-Alpine Forest Bird Conservation Area

State Ownership and Managing Agency: Department of Environmental Conservation

Location: Adirondack Mountain summits above 2,800 feet in Clinton, Essex, Franklin, Hamilton, and Warren counties. Surveyed and confirmed nesting locations for Bicknell's thrush (Atwood and Rimmer, et al. 1996) include: Mount Marcy, Algonquin Peak, Blue Mountain, Cascade Mountain, Giant Mountain, Kilburn Mountain, Hurricane Mountain, Lower Wolfjaw Mountain, Lyon Mountain, Mount Haystack, Phelps Mountain, Porter Mountain, Rocky Ridge Peak, Santanoni Peak, Snowy Mountain, Vanderwhacker Mountain, Wakely Mountain, Whiteface Mountain, and Wright Peak.

Size of Area: Approximately 69,000 acres

DEC Region: 5

Vision Statement: Continue to maintain the wilderness quality of the area, while facilitating recreational opportunities in a manner consistent with conservation of the unique bird species present

Key BCA Criteria: Diverse species concentration site; individual species concentration site; species at risk site (ECL §11-2001, 3.f, g, and h). Peaks over 2,800 feet with dense subalpine thickets provide habitat for a distinctive bird community, which includes Bicknell's thrush (special concern), blackpoll warbler and Swainson's thrush.

Critical Habitat Types: Dense subalpine coniferous thickets. To a lesser degree, young or stunted and heavy second growth of cherry or birch.

Operation and Management Considerations:

may have less stringent use limitations

- Identify habitat management activities needed to maintain site as a BCA.
 None identified for certain, although human access and acid rain could be impacting.
- Identify seasonal sensitivities; adjust routine operations accordingly.
 The BCA is comprised of lands that are within the Adirondack High Peaks Wilderness Area, and other lands within the broader Adirondack Forest Preserve. The Adirondack High Peaks Wilderness Area portion is subject to relatively stringent regulations and use limitations. Portions of the BCA that are not within the High Peaks Wilderness Area

Access to wilderness areas is completely limited to foot trails and non-motorized access, including horse trails. Access in wild forest and intensive use areas may include motorized forms of access. Examples include a road up Blue Mountain to transmitters, and a road up Whiteface. The road up Blue Mountain is used largely for administrative access to the transmitter towers. Whenever possible, routine maintenance on these towers or the access road should be scheduled outside the nesting season for Bicknell's thrush (May through July). The road up Whiteface sees considerable use by the public.

Trail and road maintenance activities have the potential to disturb nesting activities of high altitude birds (in particular, Bicknell's thrush). Whenever possible, routine maintenance should be planned so that it can be completed outside of the normal nesting season. Should maintenance be needed during the nesting season, the use of non-motorized equipment would help to minimize the impacts.

- Identify state activities or operations which may pose a threat to the critical habitat types identified above; recommend alternatives to existing and future operations which
 may pose threats to those habitats.
- Ensure that bird conservation concerns are addressed in the Adirondack Park State Land Master Plan, individual unit management plans, and other planning efforts. For those areas where plans have already been completed, incorporate concerns for subalpine bird communities at the earliest opportunity.

On May 18, 2000, Emergency Regulations were adopted for the High Peaks Wilderness Area, which comprises part of the BCA. These regulations prohibit camping above 4,000 feet; limit camping between 3,500 and 4,000 feet to designated areas; prohibit campfires above 4,000 feet, and require the leashing of pets above 4,000 feet.

• Identify any existing or potential use impacts; recommend new management strategies to address those impacts.
There has been little research on what effect normal use of hiking trails has on nesting birds. Recreational use in some areas of the BCA is relatively high. More research is needed on whether there is a significant impact to bird populations from the current level of human visitation. The Adirondack High Peaks Wilderness portions of the BCA are remote locations and access is largely limited to foot trails. Motorized vehicles are not normally allowed. Those areas of the BCA outside of the High Peaks Wilderness Area allow the use of motorized vehicles and have fewer restrictions on other uses. The Unit Management Planning process for these areas should assess the effects of current levels of recreational use, and the need for new trails (including placement, timing, and construction method) on subalpine bird species (in particular, Bicknell's thrush). Consideration should be given to prohibiting motorized vehicle access to subalpine forests above 2,800 feet.

Education, Outreach, and Research Considerations:

- Assess current access; recommend enhanced access, if feasible.
 Recreational use in some areas of the BCA is relatively high. Further study or research would help to assess impacts of recreational activities on nesting high altitude species. The need for protective measures will be discussed and incorporated as part of the planning process for the Adirondack Forest Preserve and Wilderness Areas that form the BCA, or at the earliest opportunity.
- Determine education and outreach needs; recommend strategies and materials.

 There is a need to identify to the public the distinctive bird community present in subalpine forests over 2,800 feet. The potential impacts of human intrusion need to be portrayed to the public, and a "please stay on the trails" approach may be beneficial. Continue partnerships with the National Audubon Society, High Peaks Audubon Society, Adirondack Mountain Club and other groups involved in education and conservation of birds of the Adirondack High Peaks.
- Identify research needs; prioritize and recommend specific projects or studies.
 Acid rain deposition may be having an impact on nesting success of songbirds at high elevations by causing die-offs of high altitude conifer forests, and killing snails and other sources of calcium needed for egg production. More research is needed on this. The curtailment of sulphur dioxide emissions and the reduction of acid rain is currently

a significant New York State initiative.

A detailed inventory and standardized monitoring of special concern species is needed for the area. In particular, all peaks above 2,800 feet should be surveyed for Bicknell's thrush.

The impact of the current levels of human use on nesting success needs to be assessed.

Contacts:

DEC Region 5 Wildlife Manager, 518-897-1291

DEC Region 5 Forester, 518-897-1276

Sources

Atwood, J. L., C. C. Rimmer, K. P. McFarland, S. H. Tsai, and L. R. Nagy. 1996. Distribution of Bicknell's thrush in New England and New York. Wilson Bulletin 108(4):650-661.

Bull, John L. 1998. Bull's Birds of New York State. Comstock Publishing Associates, Ithaca, NY.

NYSDEC Division of Lands and Forests. 1999. High Peaks Wilderness Complex Unit Management Plan. NYSDEC, Albany, NY.

Rimmer, C. C., Atwood, J., and L. R. Nagy. 1993. Bicknell's Thrush - a Northeastern Songbird in Trouble? Vermont Institute of Natural Science, Woodstock, VT.

State of New York Endangered Species Working Group. 1996. Species Dossier for Bicknell's Thrush. New York State Department of Environmental Conservation.

Wells, J. V. 1998. Important Bird Areas in New York State. National Audubon Society, Albany, NY.

Date BCA Designated: 11/16/01

Date MGS Prepared: 12/6/01

Appendix 5 Trail Inventory and Analysis

Trail Inventory and Analysis



November, 2017 Updated Feb 23, 2018

Prepared for:



NYS Olympic Regional Development Authority 2634 Main Street Lake Placid, NY 12946

Prepared by:

The LA Group, Landscape Architecture and Engineering, P.C. 40 Long Alley, Saratoga Springs, New York 12866 (518) 587-8100 www.thelagroup.com



Introduction

The following Trail Inventory and Analysis was performed as part of ORDA's and Gore Mountain's ongoing efforts to update and maintain the calculated ski trail mileage that currently exists on the mountain. The last update was performed in 2005 and since that time improved technology and high definition aerial photography has been made readily available. This provides the opportunity for a more detailed refinement of the trail mileage calculations that were presented in previous Unit Management Plans (UMP's). A similar update is being performed for Whiteface Mountain and it is anticipated the same update will be performed for Belleayre Mountain when that UMP is next amended.

The analysis below calculates trail width in accordance with existing legislation and documents the methodology used. A brief summary of previous calculations found in existing Unit Management Plans and related amendments is provided, along with additional description of all ski area appurtenances considered as part of this effort. Findings are summarized at the end of the analysis.

1.0 Background: New York State Constitution, Article XIV (Conservation)

1.1 History of Legislation Pertaining to Gore Mountain

Article 14, Section 1 of the New York State Constitution is the "forever wild" clause protecting state Forest Preserve lands. On November 4, 1941, the clause was amended by a vote of the People of the State of New York authorizing the:

"constructing and maintaining [of] not more than twenty miles of ski trails thirty to eighty feet wide on the north, east and northwest slopes of Whiteface Mt. in Essex County."

In 1944 the New York State Legislature created the Whiteface Mountain Authority from the Whiteface Mountain Highway Commission (Chapter 691 of the Laws of 1944). The new Authority assumed the responsibility for the Whiteface Mountain Memorial Highway and was additionally given the authority to:

"Acquire, construct, reconstruct, equip, improve, extend, operate and maintain ski trail developments"

at Whiteface Mountain, Gore Mountain and Old Forge. As such, "ski trail development" was further defined to mean:



"ski trails, ski tows, open slopes made available for skiing, and all such appurtenances, facilities and related developments as in the judgment of the Authority may be necessary for the promotion, use and enjoyment of the ski trails." (Laws of 1944 ch. 691, §1; Public Authorities Law §101 (repealed 1974).

In 1960 the Whiteface Mountain Authority was renamed the Adirondack Mountain Authority. In 1968 the Adirondack Mountain Authority ceased to exist and the New York State Department of Environmental Conservation was given the responsibility to continue development, maintenance and operation of the ski areas. Following the 1980 Winter Olympics in Lake Placid, the Olympic Regional Development Authority (ORDA) was created in 1982 and assumed the responsibility to continue development, maintenance and operation of Whiteface and the other remaining Olympic venues. A DEC/ORDA MOU in 1984 transferred Gore Mountain to ORDA's Management. Belleayre Mountain transitioned from New York State Department of Environmental Conservation to ORDA management in November, 2012.

The original authorization to develop Gore Mountain allowed for constructing, maintaining and operating not more than 30 miles of ski trails thirty to eighty feet wide on Gore and Pete Gay Mountains. In 1987 the "forever wild" clause of the New York State Constitution was again amended authorizing Gore Mountain to construct, maintain and operate:

"Not more than forty miles of ski trails thirty to two hundred feet wide, together with appurtenances thereto, provided that no more than eight miles of such trails shall be in excess of one hundred twenty feet wide, on the slopes of Gore and Pete Gay Mountains . . ."

1.2 Collaboration and Consultation with State Agencies

In addition to the enabling legislation found in Article 14, Section 1 of the New York State Constitution and the several amendments to that document that were approved by the People of the State of New York, interpretations and actual application of legislation pertaining to the development, maintenance and operation of ski trails on "forever wild" lands have been made which are pertinent to understanding what is allowed. The single most comprehensive interpretation of the legislation was made by New York State Department of Environmental Conservation (DEC) attorney Philip H. Gitlen in a February 17, 1977 memorandum pertaining to the proposed expansion and improvements to Whiteface Mountain in anticipation of hosting the 1980 Winter Olympics.



In this memorandum Mr. Gitlen opined extensively on the calculation procedure for allowed trail widths at Whiteface Mountain as allowed by the legislation and as historically developed at the ski area.

The first condition in this memorandum relates to trail width where two or more trails join together. In this instance Mr. Gitlen observed that "where two or more trails join together they were often developed so as to be a multiple of allowable 80 ft. width . . ." Several trails were found to be 200 to 300 feet wide. From this observation Mr. Gitlen concluded that "where two or more trails join together a multiple of the constitutionally imposed width limitation may be allowable."

Secondly, Mr. Gitlen observed that "trails which have lifts associated with them are often considerably wider than the constitutionally stated maximum width of 80 feet." From this observation Mr. Gitlen concluded that "where a chair lift bisects a trail, an allowance for the width of the chair lift may be allowed in addition to the constitutional requirements for trail widths." He further justified this conclusion stating that "this has the beneficial effect of limiting the amount of new clearing required for chair lifts and enhancing the visual appearance of the ski center. (NYS DEC) staff has advised that clearing for a chair lift would be at least thirty to fifty feet".

With respect to the constitutional limitation which limits the total mileage of trails, when discussing the construction of the new Giant Slalom trail at Whiteface Mr. Gitlen stated that "...the construction of this ski trail will not violate the express limitation on the allowable length of trails to be developed. This is so even if one considers areas where two trails join together as separate trails for the mileage computation".

Lastly, Mr. Gitlen recognized the fact that snowmaking pipelines and grooming equipment are necessities of a modern ski area. As such, he opined that an allowance in trail width should be made. "... for access by modern snow grooming machinery without creating an unsafe condition for the recreational skier, and provision of adequate means of access for use and maintenance of the snow making systems to be installed without decreasing the safety afforded the recreational skier."

In conclusion, Mr. Gitlen found that "several working rules may be derived from both the past history of Whiteface Mountain and the requirements attendant with the development of a modern ski center." They are:



- Where a lift bisects a trail, an allowance for the clearing required for the lift must be made. In such cases, a minimum of 30 additional feet of clearing is required for the lift line.
- 2. Where trails join together or at the junction of two trails a multiple of the 80 foot width is allowable; and
- 3. Sufficient clearing adjacent to ski trails can be allowed for the purposes of installing and maintaining snowmaking systems, an appurtenance to a modern ski center.

With the creation of the Adirondack Park Agency, (APA) the Adirondack Park State Land Master Plan, (APSLMP) adopted in 1971, provided guidelines for the preservation, management and use of State-owned lands by State agencies in the Adirondack Park. The Gore Mountain Ski Center land is classified under the APSLMP as an "Intensive Use Area." The APSLMP provides that the primary management guideline for Intensive Use Areas is to provide the public opportunities for a variety of outdoor recreational pursuits in a setting and on a scale in harmony with the relatively wild and undeveloped character of the Adirondack Park.

The Adirondack Park Agency Act (Section 816) directs the NYSDEC to develop, in consultation with the APA, individual Unit Management Plans (UMPs) for each unit of land under its jurisdiction that is classified in the Adirondack Park State Land Master Plan. Unit Management Plans must conform to the guidelines and criteria set forth in the State Land Master Plan.

Gore Mountain Ski Center opened in 1964 and early management was under the direction of the NYSDEC. Management was delegated to the Olympic Regional Development Authority (ORDA) on April 1, 1984, through an agreement with NYSDEC which was authorized by Chapter 99 of the Laws of 1984 (Article 8, title 28, Section 2614, Public Authorities Law). This agreement transferred to ORDA the responsibility for the use, operation, maintenance and management of the ski area. Under the agreement, ORDA is to cooperate with NYSDEC to complete and periodically update the UMP for the ski area. A UMP for Gore was completed in 1987 and subsequently amended three times. A major re-write of the UMP was completed in 1994/1995 which included an extensive "Master Plan" for the expansion of Gore Mountain. It has subsequently been updated in a UMP for years 2002-2007. The most recent amendment to the 2002-2007 UMP was in 2005.

Concurrent with the preparation of each UMP has been the preparation of a Generic Environmental Impact Statement (GEIS). Each UMP/GEIS has been

publically noticed and made available for Agency and public comment. Public hearings were held on each UMP/GEIS.

All previous UMP/GEIS documents included proposed new ski trail development. Mileage calculations were included in each document and the increase in approved trail mileage was reviewed and approved by the DEC and APA for each UMP/GEIS.

2.0 Trail Width and Length Rules Established for Gore Mountain

ORDA has maintained a calculation of trail widths and overall length of trails at Gore Mountain since it began managing the mountain in 1984. These trail widths and lengths have been reported in each UMP since the original 1987 version and have subsequently been approved, each time, by the DEC and APA.

As previously stated, Gore Mountain is authorized, at this time, to maintain and operate "not more than forty miles of ski trails thirty to two hundred feet wide, together with appurtenances thereto, provided that no more than eight miles of such trails shall be in excess of one hundred twenty feet wide . . ."

Based on an understanding of Article 14, Section 1 of the New York State Constitution, the "forever wild" clause, and Amendments as approved by the People of the State of New York and interpretations made by DEC, especially NYSDEC Attorney Mr. Philip Gitlen, Esq., and actual historic practice of implementing the legislation, Gore Mountain has applied the following rules for the measurement of trail widths and length:

- 1. Where a lift bisects a trail, allowances for the clearing required for the lift can be made. These clearing allowances are not included in the trail width calculation. Based on today's lift safety standards, Gore Mountain should apply a clearing allowance of forty feet for a double chair lift and surface lift and sixty feet for a triple chair lift, quad chair lift and gondola to accommodate chair/cab swing due to wind and avoid hazardous trees in case of a tree blow down. This is in accordance with Mr. Gitlen's rule that ". . . a minimum of 30 additional feet clearing is required for the lift line."
- 2. For the purpose of calculating width, where two or more trails join together to create a wider, single open slope, the slope may be counted as a single trail, or as a multiple of the constitutionally imposed width limitation. At the time of Mr. Gitlen's conclusion the constitutionally imposed width limitation was 80 feet. As a result of the 1987 Amendment to the NYS Constitution the current width limitation is both 120 feet and 200 feet. Therefore if an area where two or more trails join together exceeds 120 feet in width but is less than 200 feet, Gore Mountain may elect to count this as a single trail segment within the allowable 8

miles of trails over 120 feet in width, or as multiple trails, each with the 120 feet width limitation. In the case where it is counted as multiple trails, the mileage of each trail shall count toward the maximum allowable trail length. This is in accordance with Mr. Gitlen's conclusions.

- 3. Where snowmaking systems exist on a ski trail, a clearing allowance of 10 feet can be applied to allow for the installation and operation of snowmaking systems. This clearing allowance does not get included in the width calculation for trails with snowmaking systems. This is in accordance with Mr. Gitlen's rule..." sufficient clearing adjacent to ski trails can be allowed for the purposes of installing and maintaining snowmaking systems, an appurtenance to a modern ski center." Based on discussion presented by Mr. Gitlen, a 10' width allowance for snowmaking was proposed as a suitable width at that time. In previous UMP documents, a 15' clearing allowance for snowmaking was determined to be sufficient and applied where applicable. For the purpose of this analysis, the more conservative 10' allowance is applied. The same allowance could be applied to similar infrastructure adjacent to trails such as power lines, for the same reasons; to allow room for safe installation and maintenance of an appurtenance, with the realized benefit of consolidating clearing for both trails and utilities in a single location.
- 4. "Glades" are not included in trail length computations since no portion of a "glade" has 30 feet of cleared area or would be considered an "open slope". A glade exists as a wooded area that is available for skiing. It is not a traditional 'alpine trail', which is developed by shaping/grading terrain, clearing swaths of trees and creating a specific linear edge or cleared area that results in a consistent trail width. It is ungroomed, natural wooded terrain subject to natural snow and weather conditions.
- 5. "Work Roads" are not included in trail length computations since they are not maintained for skiing, but are used for trail maintenance and grooming access. Similarly, areas adjacent to trails where snowmaking equipment is staged or temporarily stored shall not be included in calculated trail width.
- 6. "Queuing/Trail Access areas" are not included in the trail length computation since they are not defined ski trails. These areas are typically adjacent to lodges, ski patrol buildings and other appurtenant buildings and lift terminals. They are used by skiers to take their skis on or off, adjust their gear, or wait in line to load lifts or unload from lifts. They are also used by mountain staff and maintenance crews for access and maintenance to appurtenant structures. These areas are considered 'appurtenant' areas.

7. Only ski trails on "intensive use area" lands are included in the trail length computations. Trails in the Historic North Creek Ski Bowl that are on Town of Johnsburg controlled lands are not subject to inclusion in the trail length calculations, since they are not located on State owned Forest Preserve Lands.

3.0 Ski Trail Inventory

3.1 Summary of Previous Trail Development/Approval by UMP

Gore Mountain has been in a continuous mode of upgrading its trail system since 1984 when ORDA began managing the ski area. This included simple safety and widening improvements that did not increase trail length, as well as the development of new trails.

A review of past UMP's indicates the following progress in trail development at Gore Mountain. The 1987 UMP reported a total of 41 existing trails with a total length of 16.5 miles on 172 acres of terrain. Between 1987 and 1995, 3.05 miles of new trails were developed bringing the total trail length to 19.55 miles and 46 trails on 187.7 acres of terrain.

The 1995 UMP approved the construction of up to 28.5 miles of trails, an increase of 8.95 miles. Between 1995 and the issuance of the 2002-2007 UMP a total of 5.55 miles of new trails were constructed. This brought the total constructed trail length to 25.1 miles, existing as 50 trails on 249.5 acres of terrain.

The 2002-2007 UMP approved an additional 5.4 miles of trails bringing the total approved trail length to 33.9 miles. The 2005 UMP Amendment approved a net increase of 1.5 additional miles, bringing the total length of trails approved for construction under Gore's UMP to 35.4 miles.

3.2 Trail Length Calculation Methodology

Technological advances including the utilization of high resolution aerial photography that is available today, along with the application of the rules and criteria established in Section 2, allows for a more detailed refinement of the trail mileage calculations that were presented in previous Unit Management Plans.

Current trail mileage of developed ski trails was calculated for Gore Mountain using the most recently available aerial photography. This includes aerials provided by the NY Statewide Digital Orthoimagry Program and NYS Office of Cyber Security, Spring 2013 natural color imagery (image pixel size of 2' and

horizontal accuracy within 4' at the 95% confidence level), and High Definition (4K UHD) natural color imagery available from Google Earth, imagery date September 2015. The aerial imagery was imported into both GIS and AutoCAD software allowing spatial data such as length and width of each trail to be collected not only for historically built trails, but also for the most recent improvements. Active ski trails were identified and verified using current Gore Mountain trail map guides which promote and advertise the skiable terrain at Gore Mountain, information from the Gore Mountain General Manager and first-hand knowledge of the mountain gained through site visits. Ski lifts, work roads, snowmaking and other appurtenances were also identified and accounted for using the same sources noted above, along with background information and mapping included in previous UMPs and Amendments.

Building on the inventory above, trails were then measured and categorized as being less than 30 feet wide, 30 to 120 feet wide and 120 to 200 feet wide. The seven (7) rules noted in Section 2.0 above were used as the guiding principles for this effort. While applying these rules, the following assumptions and/or determinations were made in regard to the measurement and categorization of each trail.

- While the presence of a ski lift and/or snowmaking apparatus on a trail would allow clearing widths in excess of the 120' and 200' limit, (a width allowance) to accommodate a "safety and maintenance zone", analysis indicated that applying a width allowance did not affect or change the width categorization of a trail.
- 2. In accordance with Rule 7 in Section 2.0 above, only trails on Forest Preserve lands classified as Intensive Use were included in the final mileage calculation. Trails in the historic North Creek Ski Bowl on Town Park lands are excluded from the mileage total.
- 3. In accordance with Rule 6 in Section 2.0 above, skier queuing areas were identified, mapped and excluded from the mileage calculation.
- 4. In accordance with Rule 4 in Section 2.0 above, glades were excluded from the total mileage calculation.
- 5. In accordance with Rule 5 in Section 2.0 above, work roads and/or areas that remain open for grooming access, work or emergency access and not offered for skiing by the public were excluded from the mileage calculation. A good example of this is the abandoned ski trail Lower Tannery, which remains in use as a work road and emergency egress route for the ski patrol but is not available for the public to ski.



6. Appurtenant cleared areas that are independent of ski trails such as electric line routes, other utility line routes and the abandoned gondola route were excluded from the mileage calculation since they are not maintained and offered for skiing. Appurtenant cleared areas that include the infrastructure above and are offered for skiing are included in the calculations.

4.0 Trail Length Summary

Figure 1, "Gore Mountain, Ski Trail Inventory," illustrates the existing ski trails at Gore Mountain for the Winter 2016/2017 ski season.

Final trail length measurements were made electronically using AutoCAD Civil 3D-2014 and GIS software. Table 1, "Gore Mountain Trail Inventory," presents the results of the inventory and mileage measurement for each trail. The Table lists each trail by name, indicates if a ski lift and/or snowmaking exists on a trail, and presents lengths of each trail by width (less than 30 feet wide, 30 feet to 120 feet wide and 120 feet to 200 feet wide. Key totals are summarized below:

 Total constructed trail length 0-200 feet in width at Gore Mountain, including the Ski Bowl trails on Town Lands is 29.9 miles. A breakdown by trail difficulty is as follows:

a)	Easier	5.1 mi	17% of total
b)	More Difficult	17.3 mi	58% of total
c)	Most Difficult	6.5 mi	22% of total
d)	Experts Only	1.0 mi	3% of total

- 2. Net constructed trail length for trails 0-200 feet wide on "Intensive Use" lands (excluding trails on town park lands in the North Creek Ski Bowl) is 27.43 miles.
- 3. Total trail length by width on "Intensive Use" lands is as follows:

a) Under 30 feet wide	1.31 miles
b) 30 feet to 120 feet wide	25.69 miles
c) 120 feet to 200 feet wide	0.42 miles

As stated above the total constructed trail length 0 -200 feet wide on Intensive Use lands is 27.43 miles. Based on updated calculations using the rules and methodology presented in Sections 2 and 3 above, 32.85 miles are approved to be constructed. This is less than the 35.40 miles noted as approved in the most



recent UMP amendment.¹ Gore Mountain is authorized to operate up to 40 miles of ski trails, and therefore has 7.15 miles of trails available for future planning and approval.

Additionally, up to 8 miles are authorized to be greater than 120' wide. Currently 0.42 miles of existing trails are greater than 120', which is 7.58 miles less than the 8 miles authorized.

Notes for Reference:

Existing glades at Gore Mountain on Intensive Use Lands are calculated at a total of 7.89 miles. 2.94 miles of this total are located within previously approved trails. If adding glades to the 32.85 miles of constructed and previously approved trails, the 2.94 miles of glades within previously approved trails are not counted, as they would then be counted twice. If adding the remaining 4.95 miles of glades (7.89-2.94), to the 32.85 miles of constructed and previously approved trails, the total is 37.80 miles.

According to Article XIV, ski trails include areas 30-200 feet wide. At Gore Mountain, 1.31 miles of trails are less than 30 feet wide. Should trails less than 30 feet wide be excluded from the total length calculation, then Gore would have 31.54 miles of constructed and approved trails out of the 40 mile maximum.

G:\Proj-2015\201537_Gore_Mountain_2015\201537-04_UMP Work Gore and Ski Bowl\2015037-004Admin\05Reports\TrailAnalysis\Gore MtnTrail Analysis_2017.docx

¹ It's important to clarify that even though the mileage reported above is less than what was previously reported the <u>areas</u> approved for trail construction in the 2005 UMP have not changed. The calculation methodology, applied rules and criteria and high resolution aerial imagery used in this inventory are more detailed than those used previously, and therefore have resulted in a different total mileage.





		T				Trail Length on	Trail Length on	Trail Length on
		Gross Trail		Trail Length on		"Intensive Use" Lands	"Intensive Use" Lands	"Intensive Use" Lands
Trail Pod #	Trail Name	Length (LF)	"Intensive Use" Lands	Town Lands	Width Allowances	(under 30' wide)	(30'-120' wide)	(120'-200' wide)
1H 1F	1A 2B	825	825 357	0	S	0	825	0
3F	3B	357 1,952	1,952	0		0	357 1,952	0
12F	46ER	3,260	1,952	3,260	S L1	0	1,932	0
9A Lower	Bear Cub Run	608	608	3,200	-	0	608	
WORKRD	Cedar's Traverse	3,514	3,514	0	S	0	3,514	0
7A	Chatiemac	3,119	3,119	0		100	3,019	
6B-UP, 2K	Cloud	3,486	3,486	0		0	3,486	C
N/A	Crystal	157	157	0		157	0	0
3C-UP	Cutoff	922	922	0	-	0	922	O
7E	Dell	344	344	0	-	0	344	0
7N-Q(b)	Double Barrel (Looker's Right)	780	780	0	-	0	780	O
11N	Eagle's Nest Crossover	4,082	4,082	0	S	0	4,082	(
11A, 1N-P	Echo	5,735	5,735	0	S	0	5,320	415
C4	Farview	965	965	0		0	846	119
10G-Upper, C6	Foxlair	1,870	1,870	0		0	1,747	123
7B	Hawkeye	1,939	1,939	0		0	1,939	(
7F	Headwaters	2,740	2,740	0	S	0	2,740	0
11B-UP, M8	Hedges	1,489	1,489	0	-	1,000	489	C
12G Lower	Hudson	2,403	0	2,403	S	0	0	C
6H	Hullabloo	1,173	1,173	0		0	1,173	(
3G	Jamboree Jibland	1,619 318	1,619 318	0		0	1,619	318
N/A N/A		434	434	0		175	0 259	318
7N-M	Jug Handle Lies	1,109	1,109	0		0	1,109	
6K	Little Cloud	364	364	0		0	364	
3C-LOW	Little Dipper	993	993	0	S	0	993	
N/A	Little Gore Crossover	770	0	770	-	0	0	
2K	Lower Cloud Traverse	655	655	0	S	0	655	
6G	Lower Darby	1,019	1,019	0		0	1,019	0
1C (1D-1NR)	Lower Sleighride	1,817	1,817	0		0	1,817	0
6F	Lower Steilhang	1,246	1,246	0		0	1,246	C
3A	Lower Sunway	3,769	3,769	0	S	0	3,769	(
10C-LOW	Lower Uncus	794	794	0	S	0	794	0
2J-UP	Lower Wood In Traverse	1,115	1,115	0	-	450	665	0
M2	Mica	444	444	0	-	219	225	0
12D	Moxham	2,877	368	2,509	-	0	368	0
2D	North Star	1,803	1,803	0	S	0	1,803	0
6E, 7N-O	Open Pit	972	972	0	S	0	972	C
31	Otter Slide	407	407	0	S	0	407	0
12C, 12A 2E UP, LOW	Peaceful Valley	6,010 3,976	3,173 3,976	2,837	S S	0	3,173 3,976	0
10A, 10B LOW	Pete Gay Pine Knot	2,455	2,455	0		0	2,455	(
N/A	Pipeline Traverse	5,419	5,419	0		0	5,419	0
1C (1NR-3F)	Pot Luck	723	723	0		0	723	
20	Powder Pass	3,580	3,580	0		0	3,580	0
1B	Quicksilver	2,036	2,036	0		0	2,036	(
C7	Ruby Run	2,563	2,563	0		0	2,563	0
11K	Sagamore	6,037	6,037	0	S,L1	0	6,037	O
6B-LOW (2K-6K)	Santanoni	180	133	47	S	0	133	C
1C (1A-1D), 1D	Showcase	5,950	5,928	22	S,L1	0	5,928	(
1K	Showoff	188	188	0	-	188	0	0
2B, 2I	Sleeping Bear	2,796	2,796	0		0	2,796	(
N/A	Starting Gate	359	359	0		0	0	359
1C (1C-1A), 1A	Sunway	5,047	5,047	0		0	4,142	905
2A	Tahawus	4,184	4,184	0		0	4,184	(
C1	Tannery	2,768	2,768	0		0	2,768	(
1C (FROM 1NR)	The Arena	991	991	0		0	991	· ·
7H	The Glen	433	433	0		0	433	0
N/A 2F (2J-2E)	The Gully	730 850	730 850	0		348	730 502	(
12B	The Cole Didge Trail	1,984	1,984	0		0	1,984	
N/A	The Oak Ridge Trail The Peace Pipe	918	918	0		0	918	
7N-L	The Rumor	1,260	1,260	0		0	1,260	
10E	Topridge	3,900	3,900	0		0	3,900	C
1K	Tower 6	118	118	0		118	0	0
3E	Twin Fawns	1,094	1,094	0		0	1,094	0
1F	Twister	6,603	6,603	0		0	6,603	0
N/A	Twister's Little Sister	121	121	0		121	0	0
10C-UP	Uncas	1,833	1,833	0		0	1,833	0
12c	Eagles Nest Bridge	620	620	0	-	620	0	C
6D	Upper Darby	808	808	0	-	281	527	(
1G	Upper Sleighride	1,727	1,727	0		0	1,727	(
6C	Upper Steilhang	1,739	1,739	0		0	1,739	(
2F (TO 2J)	Upper Wood In	973	973	0		210	763	0
13A	Village Slopes	1,260	0	1,260		0	0	(
3B	Ward Hill	874	874	0		0	874	(
1N-Q-1NR, 1N-R	Wildair	4,980	4,980	0		0	4,980	(
6J	Wood Lot North	924	924	0		0	924	(
6B-LOW(FROM 6K)	Wood Lot South	1,163	1,163	0		0	1,163	(
2J (FROM 6B)	Wood Out	2,340	2,340	0		1,769	571	(
M1	Woodchuck	1,163	1,163	0		1,163	0	
	Totals (LF)	157,922	144,814	13,108		6,919	135,656	
	Totals (MILAGE)	29.91	27.43	2.48	l	1.31	25.69	0.42

- Appurtenant Width Allowances:

 1. 5=Snowmaking (10', maintenance and safety)

 2. L1=Chairlift (60', Quad, Triple, or Gondola)

 3. L2=Chairlift (40', Double chair, Surface lift)

 Limitations:

 1. Up to 40 miles of trails 30'-200' wide

 2. No more than 8 miles of trails 120'-200' wide

 3. No trails over 200' wide unless area is counted as two trails side by side



Glade Inventory


February, 2018



		Gross Length	Length on "Intensive	Length on	Length within Previously Approved	Length within
Pod #	Glade Name	(LF)	Use" Lands	Town Lands	Trails ¹	Proposed Trails ¹
11E	Abenaki Glades	2,724	2,724	0		
11G, 11M	Barkeater Glades	3,645	3,645	0	3,645	
No#	Birch Bark Alley Glades	853	853	0		
No#	Boreas Glades	3,135	3,135	0		
No#	Cave Glades	1,017	1,017	0		
No#	Chatiemac Glades	635	635	0		
No#	Chatterbox Glades	3,388	3,388	0		
11J	Cirque Glades	5,607	5,607	0	4,085	1,522
No#	Darby Woods Glades	325	325	0		
No#	Darkside Glades	848	848	0		
7N-Q(a)	Double Barrel Glades	495	495	0	495	
No#	Forever Wild Glades	1,877	1,877	0		
No#	Half 'N' Half Glades	585	305	280		305
10F-LOW	High Pines Glades	2,345	2,345	0	2,345	
10B-UPPER	Kill Kare Glades	1,147	1,147	0		
No#	MacIntyre Glades	485	485	0		
No#	Mineshaft Glades	271	271	0		
No#	Otter Slide Glades	947	947	0		
No#	Pinebrook Glades	944	944	0		
No#	Rabbit Run	840	840	0		
12D UPPER	Ridge Runner Glades	740	540	200		
No#	Sagamore Glades	2,029	2,029	0		
No#	Ski Bowl Glades	4,000	0	4,000		
7N-P	Straight Brook Glades	1,725	1,725	0	630	
11B	Tahawus Glades	1,480	1,480	0	1,480	
No#	The Narrows Glades	1,209	1,209	0		
1N-O	Twister Glades	2,850	2,850	0	2,850	
	Totals (LF)	46,146	41,666	4,480	15,530	1,827
	Totals (Mileage)	8.74	7.89	0.85	2.94	0.35

¹If including the glades in a comparison against total allowable trail mileage, these columns must be subtracted from the Total Length of glades on IU Lands, since the lengths in these columns are already included under the "Approved, Not Yet Constructed", and the "Proposed" trail length categories.





40 Long Alley Saratoga Springs NY 12866 p: 518/587-8100 f: 518/587-0180 www.thelagroup.com

© the LA group 2017

Olympic Regional **Development Authority**

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law. 2634 Main Street Lake Placid, New York 12946




Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

1 inch = 1,500 feet

750

Feet

1





© the LA group 2018

Olympic Regional Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law. **Development Authority**

2634 Main Street Lake Placid, New York 12946




Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement


Trail and Glade Inventory 1 inch = 1,500 feet


750


Feet

2











New York State Department of Environmental Conservation

MEMORANDUM

TO: Olympic Files
FROM: Philip H. Gitlen

SUBJECT: Whiteface Mountain Ski Center - Expansion of Trails

PATE: February 17, 1977

Creation of the Whiteface Mt. Ski Center

On November 4, 1941 the People of the State of New York passed an Amendment to Article 14, Section 1 of the New York State Constitution, the "forever wild" clause authorizing the:

"constructing and maintaining [of] not more than twenty miles of ski trails thirty to eighty feet wide on the North, East and Northwest slopes of Whiteface Mt. in Essex County."

Chapter 691 of the Laws of 1944 created the Whiteface Mt. Authority from the Whiteface Mt. Highway Commission. The new Authority assumed the responsibility of the Memorial Highway and was further given the authority to "acquire, construct, reconstruct, equip, improve, extend, operate and maintain ski trail developments" at Whiteface Mt., Gore Mt. and Old Forge (Laws of 1944, ch. 691 §1). The term "ski trail development" was defined as meaning;

"ski trails, ski tows, open slopes made available for skiing, and all such appurtenances, facilities and related developments as in the judgment of the Authority may be necessary for the promotion, use and enjoyment of the ski trails." (Laws of 1944 ch. 691, §1; Public Authorities Law §101 [repealed 1974])

The use of the language underlined above, is of considerable interest because in 1947 an additional Amendment to the "forever wild" clause of the New York Constitution authorized the construction of ski trails at Belleayre and Gore Mountains together with "appurtenances thereto". The absence of the term "appurtenances" in the Amendment authorizing the development of the Whiteface Mt. Ski Center had caused some to argue that Whiteface Mt. was not to be developed as a commercial ski center, complete with lodges, lifts, parking facilities, etc. but was to solely consist of ski trails between thirty and eighty feet wide.

Apparently, however, the Legislature in 1944 was of a different view and authorized the Adirondack Mt. Authority not only to develop ski trails at Whiteface Mt. but to undertake "ski trail development" which was defined to include "ski tows, open slopes made available for skiing, and such appurtenances, facilities and related developments as in the judgment of the Authority may be necessary for the promotion, use and enjoyment of the ski trails."

The limitations, if any, to the development of the Whiteface Mt. Ski Center was further made the subject of an Attorney General's opinion in 1957. In that opinion, the current Attorney General opined that the Amendment to the Constitution authorizing the development of the Whiteface Mt. Ski Center "was intended and must be interpreted to authorize a ski trail development in the full extent as it is defined in Section 101, subd. 4, of the Public Authorities Law (see definition of "ski trail development" cited above).

Accordingly, not only has the Legislature authorized the development of Whiteface Mt. as a modern ski center including "open slopes", "ski tows" and related facilities, but the New York State Attorney General has agreed that the Legislature correctly interpreted the limitations contained in the New York State Constitution when it created the Whiteface Mt. Authority (see report of Attorney General 1957 pp.197 et seq.)

In 1960 the Whiteface Mt. Authority was renamed the "Adirondack Mt. Authority" (Laws of 1960; ch. 958). In 1974 the Adirondack Mt. Authority ceased to exist and the New York State Department of Environmental Conservation assumed responsibility for the continued development, maintenance and operation of the Whiteface Mt. Ski Center.

Existing Conditions at Whiteface Mt. Ski Center

25, 32, 40, 50 to 1

The only significant improvements which have occurred at the Whiteface Mt. Ski Center since the Department of Environmental Conservation assumed jurisdiction over the operation, maintenance and development of that Center, has been the addition of a small building at the Easy Acres area housing the Alpine Training Center and the construction this past Summer of a new "Quad" lift replacing the former chairlift No.1. All other aspects of the facility as it currently exists are as a result of it's development by the Adirondack Mt. Authority and its predecessor. Certain aspects of this development warrant further development here to provide a basis for the discussion of proposed improvements which follows.

Approximately twelve miles of ski trails were developed by the Adirondack Mt. Authority. These ski trails range in width from approximately thirty feet to a maximum where two trails join together of 400 ft. ("Deer" and "Lower Valley Run") and a maximum for a single trail or "slope" of 250 ft. ("Deer"). A review of other trails at the Whiteface Mt. Ski Center indicates that where two or more trails join together they were often developed so as to be a multiple of allowable 80 ft. width, e.g. where "Cloudspin" and "Downhill" join together they are of a combined width of approximately 200 ft., and where "McKenzie", "Wilderness" and "Approach" join together they are of a common width of approximately 300 feet.

There are two conclusions which can be drawn from this pattern of development. The first is that where two or more trails join together a multiple of the constitutionally imposed width limitation may be allowable. The second is that "slopes" may be provided pursuant to the legislation authorizing development of Whiteface Mt. and the Attorney General's opinion, both cited above. The latter conclusion, however, appears to be of doubtful constitutionality, particularly considering the fact that the 1944 legislation has since been repealed.

In addition, trails which have lifts associated with them are often considerably wider than the constitutionally stated maximum width of 80 feet. For example, "Appleknocker" is bisected by chairlift #5 and is as wide as 200 feet in certain places; Valley Run is bisected by chairlift #1 and is 125 feet wide in certain places. Cloudspin, which is bisected in places by chairlift #6, is 150 feet wide in certain places.

From this one can conclude that where a chairlift bisects a trail, an allowance for the width of the chairlift may be allowed in addition to the constitutional requirement for trail widths. This has the beneficial effect of limiting the amount of new clearing required for chairlifts and enhancing the visual appearance of the ski center. Staff have advised that the clearing for a chairlift would be at least thirty to fifty feet.

Whiteface Mt. Ski Center, of course, also contains the normal appurtenances to any modern ski center including a large base lodge, considerable parking facilities and snow-making facilities over a portion of the lower mountain. Each appurtenance has required clearing of forested areas.

Proposed Developments

In connection with the Department's implementation of it's long range plan for further development of the Whiteface Mt. Ski Center for the recreational skiier as well as to provide appropriate facilities for the Alpine events which are part of the 1980 Winter Olympic Games, the following improvements are planned:

Expansion of the existing base lodge;

 The installation of a significant additional amount of snow-making;

 Construction of a new warehouse and competitor's building;

The construction of a new giant slalom trail;

5. The relocation of former chairlift #1 to serve the giant slalom trails;

6. The replacement of a portion of existing chairlift #6 with a surface lift to provide better access to the summit of Whiteface Mt.; and

7. The limited widening of existing trails and the addition of certain safety "run-outs" on "Downhill" and "Cloudspin".

The expansion of the base lodge, installation of snow-making, relocation and modification to lifts, and construction of additional buildings all appear to be in conformance with the earlier legislative interpretation of the Amendment to the New York State Constitution authorizing the development of the ski center by the Whiteface Mt. Authority as further interpreted by the aforementioned opinion of the New York State Attorney General. The aspect of the Department's development plans which have received considerable attention here have revolved around the construction of the new giant slalom trail and the widening of existing trails due to the more explicit limitations contained in the aforementioned Constitutional Amendment with respect to the allowable mileage and width of ski trail.

With respect to the constitutional limitation which authorizes the development of "not more than twenty miles" of ski trails, the addition of the new giant slalom trail will result in a total of 16 miles of ski trails at the Whiteface Mt. Ski Center. Accordingly, the construction of this ski trail will not violate the express limitation on the allowable length of trails to be developed. This is so even if one considers areas where two trails join together as separate trails for the mileage computation.

The more difficult issue is the allowable width of trails at Whiteface Mt. Ski Center. As noted earlier, there already exist trails or perhaps more properly called "slopes" which greatly exceed the 80 ft. limitation contained in the New York State Constitution. In addition, existing "trails" are, in places, considerably wider than 80 feet. This may be a result of original construction of the trails or may be a result of the natural forces which are present whenever one clears an area on a mountain noted for it's high winds and excessive snow cover. More likely, the portions of the trails which are greater than the 80 ft. limitation are probably a combination of man-made and natural (e.g. windthrow) forces. Nevertheless, the New York State Constitution expressly limits the width of ski trails to a maximum of 80 feet.

With this background, this memorandum will examine the need and reasons for the proposed widening of existing ski trails as well as the parameters which ought be established for the construction of the new giant slalom trail.

There are several reasons for widening the existing ski trails at Whiteface Mt. These include: providing a measure of safety for the recreational skier on relatively steep and winding trails, compliance with the FIS rules which require a minimum trail width of thirty meters for FIS approval, adequate provision for access by modern snow grooming machinery without creating an unsafe condition for the recreational skiier, and provision of adequate means of access for use and maintenance of the snow making systems to be installed without decreasing the safety afforded the recreational skiier.

As is apparent from the prior development of Whiteface Mt., where lifts (an "appurtenance") bisect trails, an additional width allowance has been utilized to provide a safe skiing area. Additionally, where trails have joined together it has apparently been assumed that a multiple of the 80 ft. width limitation has been allowed.

Accordingly, several working rules may be derived from both the past history of Whiteface Mt. and the requirements attendant with the development of a modern ski center:

1. Where a lift bisects a trail, an allowance for the clearing required for the lift must be made. In such cases, a minimum of 30 additional feet of clearing is required for the lift line.

- 2. Where trails join together or at the junction of two trails a multiple of the 80 ft. width is allowable; and
- 3. Sufficient clearing adjacent to ski trails can be allowed for the purposes of installing and maintaining snow-making systems, an appurtenance to a modern ski center.

The Department staff has prepared a map of all the ski trails to be used during the 1980 Winter Olympics and has indicated thereon all of the areas which are currently less than 30 meters in width and the extent of clearing which would otherwise be required for FIS approval (areas which the FIS has requested be cleared to insure a safe finish area). The Department has considered these drawings in connection with it's proposed plans for expanding the lift and snow-making capacities at Whiteface Mt. and the legal justification for widening each area in order to meet FIS specifications, accommodate the new snow-making system, and provide a reasonably safe skiing environment considering the location of lifts, the topography and similar considerations. The following is a discussion keyed to the map prepared by the Department's staff of each proposed area of widening and/or clearing:

Cloudspin (Women's downhill)

Area 1. This 400 ft. section of trail is relatively steep and is currently as narrow as 50 ft. While the installation of snow-making piping can be accomplished within the trees on the edge of the trail, adequate room for maintenance and operation while maintaining a safe skiing area requires that certain widening of the trail occur. In addition, the use of grooming equipment on this area will require widening so that grooming can be conducted without obstructing the trail or creating a hazard for the recreational skiler. Accordingly, it is proposed that the trail be widened to approximately 90 (plus or minus) feet taking into account the 80 ft. limitation contained in the Constitution and an allowance for 10 feet of clearing for the provision of a suitable area for the maintenance and operation of snow-making equipment as well as to provide adequate room for grooming of the trails without creating an unsafe condition for the skiier. In this connection it should be noted that the grooming machinery to be used by the Department is approximately 15 feet wide and is capable of using implements for snow-grooming which may be as much as 20 feet wide. The area to be cleared contains birch, balsam and spruce averaging 3 inches in width.

Area 2. This 100 ft. section of trail is at the end of a steep curving run which is currently 70 feet in width. The Department proposes to widen this area to approximately 90 feet which is considerably less than the width of the trail just down hill from this area. This widening is necessitated by the installation of the snow-making equipment and the use of snow-grooming equipment as noted above. In addition, chairlift #6 bisects this trail in this area.

Area 3. This 200 ft. section of trail is between two sections which are considerably in excess of 80 feet wide. The trail here is currently approximately 50 feet wide and it is proposed to widen it to approximately 90 feet to accommodate the installation of the snow-making equipment, the maintenance and grooming vehicles as well as to accommodate the installation of a new overhead electric system. This trail section is also bisected by chairlift #6.

Area 4. This 100 ft. section is at the junction of a crossover from "Downhill" which is currently 70 feet wide. The Department proposes to widen this section of trail to approximately 90 feet, to allow for the installation of the snow-making piping and access thereto, and to accommodate maintenance vehicles. Chairlift #6 currently bisects this section of trail.

Areas 5, 6 and 7. These areas encompass approximately 2300 ft. of trail where the current width ranges from 50 to 70 feet. Although snow-making will be installed in these areas, the trail at these locations is relatively straight and not as steep as in the upper mountain area and accordingly, there is no compelling need to widen these sections beyond the 80 ft. limitation contained in the New York State Constitution.

Area 8. This is an extremely small area at the junction of three ski trails with a current width of approximately 180 feet. The proposed widening will not result in the three trails being wider than a combined total of 240 ft. and accordingly is apparently in conformance with the Constitution. In addition, although snow-making will be installed on this trail, the width provided by the three common trails does not necessitate any additional clearing.

Downhill (Men's downhill)

Area 9. This is a 300 ft. section of steep, twisting trail which is currently 50 feet wide in which the Department proposes to widen to approximately 90 feet. The need and justification for this widening is the same as with area #1 with the addition that a snow-making pumphouse (#4) is proposed for installation in this area.

Areas 10 and 11. These encompass approximately 800 feet of trail where the current width is approximately 70 feet. The Department proposes to widen these sections to approximately 90 feet for the same reasons as given with respect to area #1.

Area 12. This is a 400 ft. section of relatively steep, twisting trail which is currently approximately 40 feet wide. FIS has required that this particular section of trail be widened to provide safety for the competitive skiier. In addition, for the reasons given with respect to area #1, widening is needed for safety for the recreational skiier. This will require a certain amount of clearing as well as the construction of a minor structure to bridge a narrow gorge area to make a trail approximately 90 ft. wide.

Areas 13, 14 and 15. These areas comprise approximately 1,000 feet of trail which are currently 50 to 75 feet in width which are located in a relatively flat straight area. Accordingly, although the Department will be installing snow-making in these areas and will be utilizing snow grooming machinery in these areas, no widening in excess of the 80 ft. limitation contained in the Constitution is required.

Areas 16 and 16a. These are relatively small areas at the junction of "Cloudspin", "Downhill" and the giant slalom trail. The clearing required will not result in a maximum width in excess of the 240 feet, the allowable limit for three merged trails.

Wilderness (Slalom)

Area 18. This section of trail is currently approximately 60 feet wide and the Department proposes to widen it to 90 feet. This area will be the subject of the installation of underground snow-making pipes and accordingly, additional clearing is required to prevent tree roots from interfering with the snow-making pipes and to provide adequate room for maintenance and operation of the snow-making system.

Area 18a. This is actually not a ski trail, but a work road which is currently 20 to 30 feet wide and which will be widened to accommodate maintenance equipment.

Area 18b. This area is approximately 1,000 ft. long and is currently 60 feet wide. The Department proposes to widen this trail to 90 feet for the reasons given for area #18.

Giant Slalom

Area 18c. This area is at the junction of the existing giant slalom and the proposed giant slalom trails as well as the beginning of the slalom trail. In addition, chairlift #2 bisects the existing giant slalom trail. The Department proposes to widen this area to approximately 250 feet wide, taking into account the existence of the three trails and the lift.

Area 19. No cutting is apparently required in this area.

Area 20. This area will be widened from approximately 50 feet to approximately 90 feet to accommodate underground snow-making equipment.

Area 21. This area, over 1,000 feet in length is approximately 50 feet wide and will be widened to approximately 80 feet. Although underground snow-making will be installed in this section, it is relatively straight and not quite as steep as other areas and accordingly the installation of pipes and access for maintenance and operation can be accomplished within an 80 ft. trail width.

Finish Area

Area 17a. This is the confluence of four trails bisected by lift #1 and is currently 120 feet wide. The Department proposes to widen this area to 300 feet well within the allowable limitation for a multiple of four trails.

Area 17. This is below the finish area and can be considered an extension of the above mentioned four trails. Accordingly, the proposed widening to 250 feet from the current 150 feet is, again, well within the multiple allowed for four merged trails.

Area 17b. The Department staff does not see any particular reason for this clearing and accordingly it is not now being proposed.

PHG/jlb

Appendix 6 Vanderwhacker Mountain Wild Forest 2005 UMP Excerpts


APPENDIX J: Further Descriptions of Management Actions

Raymond Brook nordic ski trail (Town of Johnsburg)

In the middle of the twentieth century, a network of ski trails was operated on and around Gore Mountain and Pete Gay Mountain on state and private land. Some of these trails on private land were eventually closed, others became part of Little Gore (also known as the North Creek Ski Bowl), and still others on state land became a part of what is now Gore Mountain Ski Area. An unmarked ski trail that exists in the vicinity of Balm-of-Gilead Mountain in the Siamese Ponds Wilderness Area (SPWA) may also have been a part of this network. This trail connects the Old Farm Clearing trailhead in SPWA to Barton Mines Road and receives moderate winter use. The SPWA UMP proposes designation of this herdpath as a marked DEC trail.

A continuation of this trail, which runs through the Raymond Brook drainage, will be partially re-opened. The new complete trail will run from SPWA, across Barton Mines Road, and eventually connect with State Route 28N just north of the hamlet of North Creek. If an agreement can be reached with the neighboring private owner(s), a short trail will connect from Forest Preserve to existing ski trails on Little Gore (See map). The Town of Johnsburg has indicated that they have arranged for permission to cut and mark ski/hiking trails from the North Creek Ski Bowl across this private land to the state boundary. In this way, the new trail will connect the existing unmarked ski trail in Siamese Ponds Wilderness Area with the hamlet of North Creek. There will also be the opportunity to drive up Barton Mines Road and ski down.

The section from Barton Mines Road to the old trail in the vicinity of an old ski shed, will be comprised of new construction for a distance of approximately 1.5 miles. The middle section will follow the old trail and will require blowdown removal and installation of erosion control devices. The lower section will be a combination of new construction and upgrade of existing paths and skid roads on recently purchased property. A parking lot will be constructed adjacent to Barton Mines Road, and an existing clearing along Route 28N will be utilized for parking at the lower end of the trail.



Appendix 7 Stormwater Management Report



Stormwater Management Report

for:

Gore Mountain UMP at 793 Peaceful Valley Road North Creek, NY 12853 Warren County

Owner/Operator(s):

Olympic Regional Development Authority

2634 Main Street Lake Placid, NY 12946 Contact: Mike Pratt

SWM Report Contact(s):

The LA Group, PC 40 Long Alley Saratoga Springs, NY 12866 1-518-587-8100 Project No. 2016006

> **Preparation Date:** 11/7/2017

Table of Contents

1.0	INTRODUCTION	4
2.0	PROJECT DESCRIPTION	4
2.1	SITE LOCATION	4
2.2	PROJECT DESCRIPTION	
2.3	SOIL CONDITIONS/SOIL TESTING	
2.4	CURVE NUMBERS AND RAINFALL DATA	4
3.0	EXISTING CONDITIONS	5
4.0	PROPOSED CONDITIONS	5
5.0	NYSDEC DESIGN CRITERIA	6
5.1	SITE PLANNING TO PRESERVE NATURAL FEATURES	6
5.2	WATER QUALITY VOLUME (WQV)	8
5.3	RUNOFF REDUCTION VOLUME (RRV)	
5.4	CHANNEL PROTECTION VOLUME (CPV)	9
5.5	OVERBANK FLOOD (QP) AND EXTREME FLOOD (QF) ATTENUATION	9
6.0	PROPOSED STORMWATER FACILITIES	10
7.0	POST-CONSTRUCTION MAINTENANCE REQUIREMENTS	10
8.0	REFERENCES	10

Attachment

- A Soil Investigations
 Soil Survey
 Natural Resource Map
- **B** Existing Conditions Watershed Map and HydroCAD Calculations
- C Proposed Conditions Watershed Map and HydroCAD Calculations
- D Storm Data

1.0 INTRODUCTION

The following is a Stormwater Management Report (SWM Report) developed for the Operator, Olympic Regional Development Authority (ORDA), for Gore Mountain UMP, herein referred to as the "Project." It is prepared in accordance with the New York State Department of Environmental Conservation (NYSDEC) Stormwater Management Design Manual, dated January, 2015.

The Project has been designed in accordance with Chapter 4 of the NYSDEC Stormwater Management Design Manual (SWMDM), and NYSDEC's General Permit GP-0-15-002 for construction activities. Stormwater calculations were performed utilizing widely accepted engineering methodologies, including TR-55, and the stormwater modeling computer program HydroCAD (version 10.00) produced by HydroCAD Software Solutions, LLC.

2.0 PROJECT DESCRIPTION

2.1 Site Location

The Project is located off Gore Mountain Road in the Town of North Creek, Warren County, NY 12853. Access to the site is off of Peaceful Valley Road.

2.2 Project Description

The Project includes the construction of a new groomer garage and dedicated shuttle loop. The remainder of the proposed site improvements includes site grading, landscaping and stormwater controls. The project is considered a new development project per Chapter 4 of the SWMDM. The Project Site represents the area that will be disturbed as a result of the Project.

2.3 Soil Conditions/Soil Testing

According to the Natural Resources Conservation Service (NRCS) Web Soil Survey, the area surrounding the Project Site is comprised of Marlow very boulder fine sandy loam. The hydrological soil group classification for this soil type is 'C'.

2.4 Curve Numbers and Rainfall Data

The surface cover for the project area is meadow non-grazed, grass, woods and impervious buildings and parking lot. The curve numbers utilized in the modeling were assigned based on cover type and HSG soil classification.



The design storms used for the pre-development versus post-development comparison were the 1, 10, and 100-year, 24-hour duration, SCS Type II events. The rainfall amounts for these storms are 2.10, 3.50, and 5.50 inches, respectively.

3.0 EXISTING CONDITIONS

The Project area existing condition, for which this stormwater management plan is based, consists of meadows, woods, roofs, and grass. Under the watershed's Existing Condition, the watershed is broken into five (5) subcatchments. Runoff from the site flows to two separate analysis points (Analysis Points 1 & 2). Analysis Points 1 is located to the north east the project area and represents runoff entering North Creek. Analysis Points 2 is located to the south east of the project area and represents runoff entering Straight Brook. Analysis Points 1 & 2 were utilized in comparing all pre- versus post-runoff conditions. Refer to drawing "W-1 Existing Conditions Watershed Map," located in Attachment B for more information.

Table 3-1 below provides a summary of the existing conditions peak discharge rates for the Project's watershed.

Table 3-1 Existing Conditions Peak Discharge Rates				
Analysis Point	AP-1	AP-2		
Design Storm	(cfs)	(cfs)		
10-Year	190.47	40.46		
100-Year	455.12	122.47		

Refer to Attachment B for more information on the existing conditions watershed modeling.

4.0 PROPOSED CONDITIONS

Under the watershed's Proposed Condition, all stormwater from the Project will continue to discharge to the same point as in the Existing Condition (Analysis Points 1 & 2). The total watershed has generally remained unchanged, as is shown on the drawing "W-2 Proposed Conditions Watershed Map" contained in Attachment C. To meet NYSDEC requirements (see Section 5.0 NYSDEC Design Criteria of this report) a bioretention basin and wet swale have been incorporated into the stormwater management design to mitigate the quality and quantity of stormwater runoff discharged from the Project Site.

Table 4-1 below provides a summary of the existing conditions versus proposed conditions peak discharge rates for the Project's watershed.



Table 4-1 Existing Conditions Versus Proposed Conditions Peak Discharge Rates				
Analysis Point	AP-1		AP-2	
	Existing	Proposed	Existing	Proposed
Design Storm	(cfs)	(cfs)	(cfs)	(cfs)
10-Year	200.44	197.68	40.46	40.46
100-Year	468.63	468.61	122.47	122.47

Refer to Attachment C for more information on the proposed conditions watershed modeling.

5.0 NYSDEC DESIGN CRITERIA

The New York State Stormwater Management Design Manual, dated January 2015 (The Manual) has been utilized to develop the stormwater management plan. The Manual includes a five-step process that involves site planning and stormwater management practice selection. The five steps include;

- Site planning to preserve natural features and reduce impervious cover,
- Calculation of the Water Quality Volume (WQv) for the Site,
- Incorporation of green infrastructure techniques and standard SMPs with Runoff Reduction Volume (RRv) capacity,
- Use of standard SMPs where applicable, to treat the portion of WQv not addressed by green infrastructure techniques and standard SMPs with RRv capacity, and
- Design of volume and peak rate control (where required)

The approach of the stormwater management plan was to address the stormwater requirements separately. The five steps were reduced to Site Planning to Preserve Natural Features, Water Quality Volume, Runoff Reduction Volume, Channel Protection Volume, and Overbank Flood and Extreme Storm Attenuation, as discussed in the following sections.

Attachment D of this report contains detailed calculations for determining and summarizing the required and provided volumes for Water Quality and Runoff Reduction. In general, the required design criteria (WQv and RRv) were calculated for all areas where site disturbance or green infrastructure techniques are proposed.

5.1 Site Planning to Preserve Natural Features

Within Chapter 3 of The Manual, Table 3.1 Green Infrastructure Planning General Categories and Specific Practices includes a list of planning practices utilized in the planning and design of



a project. There are two categories, Preservation of Natural Resources and Reduction of Imperious Cover.

Preservation of Natural Resources includes:

- Preservation of Undisturbed Areas
- Preservation of Buffers
- Reduction of Clearing and Grading
- Locating Development in Less Sensitive Areas
- Open Space Design
- Soil Restoration

Reduction of Impervious Cover includes:

- Roadway Reduction
- Sidewalk Reduction
- Driveway Reduction
- Cul-de-sac Reduction
- Building Footprint Reduction
- Parking Reduction

A Natural Resource Map for Green Infrastructure Planning has been developed which indicates natural resource areas and critical environmental areas to be protected (where feasible). As required in Section 3.6 of The Manual, the map includes (where applicable):

- Jurisdictional Wetlands
 - o There are wetlands located near the project site. These wetlands will not be impacted as part of this project.
- Waterways
 - o No waterways are impacted by the Project.
- Wetland Adjacent Area
 - o There are wetlands located near the project site. The development does not impact NYSDEC wetland buffer areas.
- Floodplains
 - o The project is not within the flood plain.
- Forest, vegetative cover
 - o Project is designed to maintain as much of the woods as feasible.
- Topography/Steep slopes
 - o There are no steep slopes located throughout the project.
- Existing soils, including hydrologic soil groups and soil erodibility
 - o See Section 2.3 of this Report.
- Drainage Patterns
 - o See Section 3.0 of this Report.



- Bedrock/Significant geological features
 - o See Section 2.3 of this Report.

The Natural Resource Plan indicates the areas to be avoided and depicts the area most suitable for development.

5.2 Water Quality Volume (WQv)

The Water Quality Volume (WQv) requirement is designed to improve water quality sizing to capture and treat 90% of the average annual stormwater runoff volumes. The WQv is directly related to the amount of impervious cover created at a site. The following equation is used to determine the water quality storage volume.

$$WQv = \frac{(P)(Rv)(A)}{12}$$

Where:

WQv = Water quality volume (acre/feet)

P = 90% Rainfall Event (1.1" for North Creek)

Rv = 0.05 + 0.009(I) where I is percent impervious cover

A = Site area in acres

The required WQv will be provided by bioretention basins and a wet swale designed in accordance with the SWMDM. Refer to Table 5-1 for a summary of the required versus provided water quality volumes for the Project.

Table 5-1 Water Quality Volume (WQv) Summary				
SMP	Туре	Required	Provided	
		(ac-ft)	(ac-ft)	
SMP1	Wet Swale		0.194	
SMP2	Bioretention Basin		0.032	
SMP3	Bioretention Basin		0.105	
TOTAL		0.138	0.331	

Refer to Attachment D for detailed WQv calculations.

5.3 Runoff Reduction Volume (RRv)

Section 4.3 of the Manual states, "Runoff reduction shall be achieved by infiltration, groundwater recharge, reuse, recycle, evaporation/evapotranspiration of 100 percent of the post-



development water quality volumes to replicate pre-development hydrology by maintaining preconstruction infiltration, peak runoff flow, discharge volume, as well as minimizing concentrated flow by using runoff control techniques to provide treatment in a distributed manner before runoff reaches the collection system."

The project does not achieve 100% reduction of the on-site WQv; however, through the use of green infrastructure the minimum required RRv of 0.041 ac-ft is reduced.

Table 5-2				
Runoff Reduction Volume (RRv) Summary				
SMP	Provided			
	(unit)			
5.3.1 Conservation of Natural Areas	-			
5.3.2 Sheetflow to Riparian Buffers/Filter Strips	-			
5.3.3 Wet Open Swales	-			
5.3.4 Tree Planting/Tree Box	-			
5.3.5 Disconnection of Rooftop Runoff	-			
5.3.6 Stream Daylighting	-			
5.3.7 Rain Garden	-			
5.3.8 Green Roof	-			
5.3.9 Stormwater Planters	-			
5.3.10 Rain Tanks/Cisterns	-			
5.3.11 Porous Pavement	-			
Bioretention Basin (SMP2)	0.013			
Bioretention Basin (SMP3)	0.048			
TOTAL	0.061 (ac-ft)			

Refer to Attachment D for detailed RRv calculations.

5.4 Channel Protection Volume (CPv)

Channel Protection Volume (Cpv) is achieved by a combination of volume reduction through green infrastructure practices.

5.5 Overbank Flood (Qp) and Extreme Flood (Qf) Attenuation

The primary purpose of the Overbank Flood (Qp) control sizing criterion is to prevent an increase in the frequency and magnitude of out-of-bank flooding generated by urban



development. It requires storage and attenuation of the 10-year, 24-hour storm to ensure post-development peak discharge rates do not exceed the pre-development condition.

The intent of the Extreme Flood (Qf) criteria is to (a) prevent the increased risk of flood damage from large storm events, (b) maintain the boundaries of the pre-development 100-year floodplain, and (c) protect the physical integrity of stormwater management practices. It requires storage and attenuation of the 100-year, 24-hour storm to ensure post-development peak discharge rates do not exceed the pre-development condition.

During the 10-year and 100-year 24-hour storm the post-development peak discharge rates do not exceed the pre-development rates. See Table 4-1 of this Report for detailed comparison of pre- and post-development peak rates.

6.0 PROPOSED STORMWATER FACILITIES

The Project is proposing the installation of two bioretention basins and a wet swale to address stormwater requirements for the project. The stormwater facilities have been indicated on the plans and HydroCAD reports as SMP1 through SMP3. SMP1 is a wet swale located to the east of the new dedicated shuttle loop will treat runoff from the proposed shuttle loop as well as the existing roadway SMP2 is a bioretention basin located adjacent to the proposed groomer garage and will treat the roof runoff from the building. SMP3 is a bioretention basin located adjacent to the entrance of Lot E and will treat runoff from nearby impervious areas. The Stormwater facilities have been designed to provide the necessary pretreatment, treatment, and peak rate attenuation for stormwater runoff, for the project, as required by NYSDEC.

7.0 POST-CONSTRUCTION MAINTENANCE REQUIREMENTS

Gore Mountain will be responsible for the continuous upkeep and maintenance of all stormwater management facilities. Maintenance includes, but is not limited to, cleaning of sediment from drainage inlet sumps, removal of sediment from SMPs, cleaning conveyance piping and channels of obstructions, inspection and repair as required of any outlet control mechanisms, and repairing any other detriments in the design that is resulting in the facilities to not function as intended in the design.

8.0 REFERENCES

- 1. Urban Hydrology for Small Watersheds. Published by the U.S. Soil Conservation Service, Washington, D.C., June 1986.
- 2. HydroCAD 10.00 Computer Program, by HydroCAD Software Solutions, LLC.



3. NYSDEC Stormwater Management Design Manual. Published by the New York State Department of Environmental Conservation, Updated January 2015.

 $G:\label{lem:condition} G:\label{lem:condition} G:\l$



Attachment A

Soil Investigations Soil Survey Natural Resource Map



NRCS Natural

Natural Resources Conservation Service A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for Warren County, New York



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2 053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	
Soil Map	
Soil Map	
Legend	
Map Unit Legend	
Map Unit Descriptions	
Warren County, New York	13
BdC—Bice very bouldery fine sandy loam, sloping	13
HeE—Hermon very bouldery fine sandy loam, steep	14
HmE—Hermon-Lyman-Rock outcrop complex, steep	15
HpC—Hinckley-Plainfield complex, sloping	17
HpE—Hinckley-Plainfield complex, steep	19
LmE—Lyman-Rock outcrop complex, steep	21
MrC—Marlow very bouldery fine sandy loam, sloping	23
MrE—Marlow very bouldery fine sandy loam, steep	24
PIC—Plainfield loamy sand, 8 to 15 percent slopes	26
References	28

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.


Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



MAP LEGEND

Area of Interest (AOI)

Area of Interest (AOI)

Soils

Soil Map Unit Polygons

Soil Map Unit Lines

Soil Map Unit Points

Special Point Features

ဖ

Blowout

Borrow Pit

Clay Spot

Closed Depression

Gravel Pit

Gravelly Spot

Landfill Lava Flow

Marsh or swamp

Mine or Quarry

Miscellaneous Water Perennial Water

Rock Outcrop

Saline Spot

Sandy Spot

Severely Eroded Spot

Sinkhole

Slide or Slip

Sodic Spot

å

Spoil Area Stony Spot

Very Stony Spot

Ŷ

Wet Spot Other

Δ

Special Line Features

Water Features

Streams and Canals

Transportation

Rails

Interstate Highways

US Routes

Major Roads Local Roads

 \sim Background

Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15.800.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Warren County, New York Survey Area Data: Version 16, Sep 24, 2016

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 30, 2014—Mar 29, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
BdC	Bice very bouldery fine sandy loam, sloping	15.2	2.6%
HeE	Hermon very bouldery fine sandy loam, steep	48.4	8.1%
HmE	Hermon-Lyman-Rock outcrop complex, steep	47.0	7.9%
НрС	Hinckley-Plainfield complex, sloping	6.6	1.1%
НрЕ	Hinckley-Plainfield complex, steep	57.1	9.6%
LmE	Lyman-Rock outcrop complex, steep	31.5	5.3%
MrC	Marlow very bouldery fine sandy loam, sloping	184.0	31.0%
MrE	Marlow very bouldery fine sandy loam, steep	195.2	32.9%
PIC	Plainfield loamy sand, 8 to 15 percent slopes	9.2	1.6%
Totals for Area of Interest	,	594.2	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They

generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An association is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Warren County, New York

BdC—Bice very bouldery fine sandy loam, sloping

Map Unit Setting

National map unit symbol: 9xw2 Elevation: 800 to 1,800 feet

Mean annual precipitation: 40 to 50 inches Mean annual air temperature: 41 to 45 degrees F

Frost-free period: 100 to 130 days

Farmland classification: Not prime farmland

Map Unit Composition

Bice and similar soils: 70 percent Minor components: 30 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Bice

Setting

Landform: Ridges, hills, till plains

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till derived mainly from granite and gneiss with variable

components of sandstone and shale

Typical profile

Oe - 0 to 2 inches: moderately decomposed plant material

H2 - 2 to 5 inches: fine sandy loam H3 - 5 to 24 inches: fine sandy loam H4 - 24 to 60 inches: fine sandy loam

Properties and qualities

Slope: 8 to 15 percent

Percent of area covered with surface fragments: 1.6 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.20 to 1.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Moderate (about 7.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6s

Hydrologic Soil Group: B Hydric soil rating: No

Minor Components

Schroon

Percent of map unit: 5 percent

Hydric soil rating: No

Lyme

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

Stowe

Percent of map unit: 4 percent

Hydric soil rating: No

Woodstock

Percent of map unit: 4 percent

Hydric soil rating: No

Plainfield

Percent of map unit: 4 percent

Hydric soil rating: No

Hinckley

Percent of map unit: 4 percent

Hydric soil rating: No

Unnamed soils

Percent of map unit: 4 percent

Hydric soil rating: No

HeE—Hermon very bouldery fine sandy loam, steep

Map Unit Setting

National map unit symbol: 9xwq Elevation: 10 to 2,800 feet

Mean annual precipitation: 40 to 50 inches Mean annual air temperature: 41 to 45 degrees F

Frost-free period: 100 to 130 days

Farmland classification: Not prime farmland

Map Unit Composition

Hermon and similar soils: 70 percent Minor components: 30 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hermon

Setting

Landform: Valley sides, moraines

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Sandy and gravelly till derived mainly from crystalline rock

Typical profile

H1 - 0 to 5 inches: gravelly fine sandy loam H2 - 5 to 18 inches: gravelly fine sandy loam H3 - 18 to 25 inches: very gravelly sandy loam H4 - 25 to 65 inches: very gravelly loamy sand

Properties and qualities

Slope: 25 to 35 percent

Percent of area covered with surface fragments: 1.6 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): High to very high (1.98

to 19.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 3.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A Hydric soil rating: No

Minor Components

Marlow

Percent of map unit: 9 percent

Hydric soil rating: No

Peru

Percent of map unit: 9 percent

Hydric soil rating: No

Bice

Percent of map unit: 9 percent

Hydric soil rating: No

Unnamed soils

Percent of map unit: 3 percent Hydric soil rating: Unranked

HmE—Hermon-Lyman-Rock outcrop complex, steep

Map Unit Setting

National map unit symbol: 9xws Elevation: 10 to 2,800 feet

Mean annual precipitation: 37 to 50 inches Mean annual air temperature: 41 to 48 degrees F

Frost-free period: 100 to 160 days

Farmland classification: Not prime farmland

Map Unit Composition

Hermon and similar soils: 40 percent Lyman and similar soils: 20 percent

Rock outcrop: 20 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hermon

Setting

Landform: Valley sides, moraines

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Sandy and gravelly till derived mainly from crystalline rock

Typical profile

H1 - 0 to 5 inches: gravelly fine sandy loam H2 - 5 to 18 inches: gravelly fine sandy loam H3 - 18 to 25 inches: very gravelly sandy loam H4 - 25 to 65 inches: very gravelly loamy sand

Properties and qualities

Slope: 25 to 35 percent

Percent of area covered with surface fragments: 1.6 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): High to very high (1.98

to 19.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 3.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A Hydric soil rating: No

Description of Lyman

Setting

Landform: Hillsides or mountainsides

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till derived mainly from crystalline rock

Typical profile

Oe - 0 to 2 inches: moderately decomposed plant material

H2 - 2 to 4 inches: fine sandy loam H3 - 4 to 10 inches: fine sandy loam H4 - 10 to 19 inches: fine sandy loam

H5 - 19 to 23 inches: bedrock

Properties and qualities

Slope: 25 to 35 percent

Percent of area covered with surface fragments: 1.6 percent Depth to restrictive feature: 10 to 20 inches to lithic bedrock Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00

in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: D Hydric soil rating: No

Description of Rock Outcrop

Typical profile

R - 0 to 10 inches: bedrock

Properties and qualities

Depth to restrictive feature: 0 inches to lithic bedrock

Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00

in/hr)

Minor Components

Peru

Percent of map unit: 8 percent

Hydric soil rating: No

Marlow

Percent of map unit: 8 percent

Hydric soil rating: No

Unnamed soils

Percent of map unit: 4 percent Hydric soil rating: Unranked

HpC—Hinckley-Plainfield complex, sloping

Map Unit Setting

National map unit symbol: 9xwy

Elevation: 0 to 1,150 feet

Mean annual precipitation: 37 to 46 inches

Mean annual air temperature: 45 to 48 degrees F

Frost-free period: 110 to 160 days

Farmland classification: Not prime farmland

Map Unit Composition

Hinckley and similar soils: 45 percent Plainfield and similar soils: 35 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hinckley

Setting

Landform: Deltas, outwash plains, terraces Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Tread

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Sandy and gravelly glaciofluvial deposits derived principally from

granite, gneiss, and schist

Typical profile

Oi - 0 to 1 inches: slightly decomposed plant material

H2 - 1 to 5 inches: cobbly sandy loam

H3 - 5 to 28 inches: very gravelly loamy sand H4 - 28 to 64 inches: stratified very gravelly sand

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 3.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4s

Hydrologic Soil Group: A Hydric soil rating: No

Description of Plainfield

Setting

Landform: Deltas, outwash plains, terraces Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Tread

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Sandy glaciofluvial or deltaic deposits

Typical profile

Oi - 0 to 1 inches: slightly decomposed plant material

H1 - 1 to 11 inches: loamy sand

H2 - 11 to 26 inches: sand H3 - 26 to 60 inches: sand

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6s

Hydrologic Soil Group: A Hydric soil rating: No

Minor Components

Castile

Percent of map unit: 5 percent

Hydric soil rating: No

Pits, sand, gravel

Percent of map unit: 5 percent Hydric soil rating: Unranked

Unnamed soils

Percent of map unit: 5 percent

Hydric soil rating: Yes

Wareham

Percent of map unit: 3 percent

Hydric soil rating: No

Wareham

Percent of map unit: 2 percent Landform: Depressions Hydric soil rating: Yes

HpE—Hinckley-Plainfield complex, steep

Map Unit Setting

National map unit symbol: 9xwz

Elevation: 0 to 1,150 feet

Mean annual precipitation: 37 to 46 inches Mean annual air temperature: 45 to 48 degrees F

Frost-free period: 110 to 160 days

Farmland classification: Not prime farmland

Map Unit Composition

Hinckley and similar soils: 45 percent Plainfield and similar soils: 35 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hinckley

Setting

Landform: Deltas, outwash plains, terraces Landform position (two-dimensional): Backslope Landform position (three-dimensional): Riser

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Sandy and gravelly glaciofluvial deposits derived principally from

granite, gneiss, and schist

Typical profile

Oi - 0 to 1 inches: slightly decomposed plant material

H2 - 1 to 5 inches: cobbly sandy loam

H3 - 5 to 28 inches: very gravelly loamy sand H4 - 28 to 64 inches: stratified very gravelly sand

Properties and qualities

Slope: 25 to 35 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 3.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A Hydric soil rating: No

Description of Plainfield

Setting

Landform: Deltas, outwash plains, terraces Landform position (two-dimensional): Backslope Landform position (three-dimensional): Riser

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Sandy glaciofluvial or deltaic deposits

Typical profile

Oi - 0 to 1 inches: slightly decomposed plant material

H1 - 1 to 11 inches: loamy sand H2 - 11 to 26 inches: sand H3 - 26 to 60 inches: sand

Properties and qualities

Slope: 25 to 35 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A Hydric soil rating: No

Minor Components

Castile

Percent of map unit: 5 percent

Hydric soil rating: No

Unnamed soils

Percent of map unit: 5 percent

Hydric soil rating: No

Pits, sand, gravel

Percent of map unit: 5 percent

Hydric soil rating: No

Wareham

Percent of map unit: 3 percent

Hydric soil rating: No

Wareham

Percent of map unit: 2 percent

Landform: Depressions Hydric soil rating: Yes

LmE—Lyman-Rock outcrop complex, steep

Map Unit Setting

National map unit symbol: 9xx3

Mean annual precipitation: 37 to 50 inches Mean annual air temperature: 41 to 48 degrees F

Frost-free period: 100 to 160 days

Farmland classification: Not prime farmland

Map Unit Composition

Lyman and similar soils: 55 percent

Rock outcrop: 30 percent Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Lyman

Setting

Landform: Hillsides or mountainsides

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till derived mainly from crystalline rock

Typical profile

Oe - 0 to 2 inches: moderately decomposed plant material

H2 - 2 to 4 inches: fine sandy loam
H3 - 4 to 10 inches: fine sandy loam
H4 - 10 to 19 inches: fine sandy loam

H5 - 19 to 23 inches: bedrock

Properties and qualities

Slope: 25 to 35 percent

Percent of area covered with surface fragments: 1.6 percent Depth to restrictive feature: 10 to 20 inches to lithic bedrock Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00

in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: D Hydric soil rating: No

Description of Rock Outcrop

Typical profile

R - 0 to 10 inches: bedrock

Properties and qualities

Depth to restrictive feature: 0 inches to lithic bedrock

Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00 in/hr)

Minor Components

Peru

Percent of map unit: 4 percent

Hydric soil rating: No

Marlow

Percent of map unit: 4 percent

Hydric soil rating: No

Hermon

Percent of map unit: 4 percent

Hydric soil rating: No

Unnamed soils

Percent of map unit: 3 percent

Hydric soil rating: No

MrC—Marlow very bouldery fine sandy loam, sloping

Map Unit Setting

National map unit symbol: 9xx7

Mean annual precipitation: 40 to 50 inches Mean annual air temperature: 41 to 45 degrees F

Frost-free period: 100 to 130 days

Farmland classification: Not prime farmland

Map Unit Composition

Marlow and similar soils: 70 percent Minor components: 30 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Marlow

Setting

Landform: Hillsides or mountainsides

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy dense till derived mainly from crystalline rock

Typical profile

Oa - 0 to 2 inches: highly decomposed plant material

H2 - 2 to 8 inches: fine sandy loam

H3 - 8 to 14 inches: gravelly fine sandy loam H4 - 14 to 30 inches: gravelly fine sandy loam H5 - 30 to 60 inches: gravelly sandy loam

Properties and qualities

Slope: 8 to 15 percent

Percent of area covered with surface fragments: 1.6 percent Depth to restrictive feature: 18 to 36 inches to densic material

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: About 24 to 36 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6s

Hydrologic Soil Group: C Hydric soil rating: No

Minor Components

Hermon

Percent of map unit: 4 percent

Hydric soil rating: No

Lyman

Percent of map unit: 4 percent

Hydric soil rating: No

Woodstock

Percent of map unit: 4 percent

Hydric soil rating: No

Bice

Percent of map unit: 4 percent

Hydric soil rating: No

Peru

Percent of map unit: 4 percent

Hydric soil rating: No

Lyme

Percent of map unit: 4 percent Landform: Depressions

Hydric soil rating: Yes

Stowe

Percent of map unit: 4 percent

Hydric soil rating: No

Unnamed soils

Percent of map unit: 2 percent

Hydric soil rating: No

MrE—Marlow very bouldery fine sandy loam, steep

Map Unit Setting

National map unit symbol: 9xx8

Mean annual precipitation: 40 to 50 inches

Mean annual air temperature: 41 to 45 degrees F

Frost-free period: 100 to 130 days

Farmland classification: Not prime farmland

Map Unit Composition

Marlow and similar soils: 75 percent Minor components: 25 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Marlow

Setting

Landform: Hillsides or mountainsides

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy dense till derived mainly from crystalline rock

Typical profile

Oa - 0 to 2 inches: highly decomposed plant material

H2 - 2 to 8 inches: fine sandy loam

H3 - 8 to 14 inches: gravelly fine sandy loam H4 - 14 to 30 inches: gravelly fine sandy loam H5 - 30 to 60 inches: gravelly sandy loam

Properties and qualities

Slope: 25 to 35 percent

Percent of area covered with surface fragments: 1.6 percent Depth to restrictive feature: 18 to 36 inches to densic material

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: About 24 to 36 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: C Hydric soil rating: No

Minor Components

Unnamed soils

Percent of map unit: 4 percent

Hydric soil rating: No

Peru

Percent of map unit: 3 percent

Hydric soil rating: No

Hermon

Percent of map unit: 3 percent

Hydric soil rating: No

Lyman

Percent of map unit: 3 percent

Hydric soil rating: No

Woodstock

Percent of map unit: 3 percent

Hydric soil rating: No

Lyme

Percent of map unit: 3 percent Landform: Depressions Hydric soil rating: Yes

Bice

Percent of map unit: 3 percent

Hydric soil rating: No

Stowe

Percent of map unit: 3 percent

Hydric soil rating: No

PIC—Plainfield loamy sand, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 9xxq Elevation: 720 to 1,150 feet

Mean annual precipitation: 37 to 46 inches

Mean annual air temperature: 45 to 48 degrees F

Frost-free period: 110 to 160 days

Farmland classification: Not prime farmland

Map Unit Composition

Plainfield and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Plainfield

Setting

Landform: Deltas, outwash plains, terraces
Landform position (two-dimensional): Shoulder
Landform position (three-dimensional): Tread

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Sandy glaciofluvial or deltaic deposits

Typical profile

H1 - 0 to 10 inches: loamy sand H2 - 10 to 25 inches: sand H3 - 25 to 60 inches: sand

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Excessively drained

Capacity of the most limiting layer to transmit water (Ksat): High to very high (5.95

to 19.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 3.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6s

Hydrologic Soil Group: A Hydric soil rating: No

Minor Components

Elnora

Percent of map unit: 4 percent

Hydric soil rating: No

Hinckley

Percent of map unit: 4 percent

Hydric soil rating: No

Unnamed soils, similar to plainfield, reddish

Percent of map unit: 2 percent

Hydric soil rating: No

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084


United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

Attachment B

Existing Conditions Watershed Map and HydroCAD Calculations



SUBCATCHMENT BOUNDARY

SUBCATCHMENT ID

ANALYSIS POINT

STORMWATER FACILITY

People. Purpose. Place.

40 Long Alley p: 518-587-8100
Saratoga Springs f: 518-587-0180
NY 12866 www.thelagroup.com

The LA GROUP

Landscape Architecture & Engineering P.C.

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law.

© the LA Group 2017

Prepared for:

Olympic Regional Development Authority

2634 Main Street Lake Placid, New York 12946

Project Title:
Gore Mountain: 2017 Unit Management Plan Draft Amendment & Draft Generic Environmental Impact Statement

Project No.:			2015037
Design:			BCS
Drawn:	BCS	Ch'k'd:	DBH


Description:	Date:

Drawing Title

Existing Conditions Watershed Map

Drawing No.

W-1



Gore Pre Development
Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017

Page 2

Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
0.942	74	>75% Grass cover, Good, HSG C (3)
25.010	98	Paved parking, HSG C (1, 3, 4)
224.805	70	Woods, Good, HSG C (1, 2, 3, 4, 5)
250.757	73	TOTAL AREA

Gore Pre Development
Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
250.757	HSG C	1, 2, 3, 4, 5
0.000	HSG D	
0.000	Other	
250.757		TOTAL AREA

Gore Pre Development
Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017

Page 4

Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.942	0.000	0.000	0.942	>75% Grass cover, Good	3
0.000	0.000	25.010	0.000	0.000	25.010	Paved parking	1, 3, 4
0.000	0.000	224.805	0.000	0.000	224.805	Woods, Good	1, 2, 3, 4,
							5
0.000	0.000	250.757	0.000	0.000	250.757	TOTAL AREA	

Gore Pre Development

Prepared by The LA Group

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 1-YR Rainfall=2.10" Printed 11/7/2017

Primary=5.99 cfs 0.771 af

Page 5

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1: Subcat 1	Runoff Area=164.691 ac 8.95% Impervious Runoff Depth>0.31" Flow Length=2,229' Tc=29.6 min CN=73 Runoff=38.44 cfs 4.316 af
Subcatchment 2: Subcat 2	Runoff Area=35.807 ac 0.00% Impervious Runoff Depth>0.24" Flow Length=1,112' Tc=25.5 min CN=70 Runoff=5.99 cfs 0.705 af
Subcatchment 3: Subcat 3	Runoff Area=28.794 ac 30.03% Impervious Runoff Depth>0.52" Flow Length=3,110' Tc=24.7 min CN=79 Runoff=14.79 cfs 1.238 af
Subcatchment 4: Subcat 4	Runoff Area=17.152 ac 9.44% Impervious Runoff Depth>0.31" Flow Length=1,452' Tc=27.4 min CN=73 Runoff=4.24 cfs 0.450 af
Subcatchment 5: Subcat 5	Runoff Area=4.312 ac 0.00% Impervious Runoff Depth>0.24" Tc=6.0 min CN=70 Runoff=1.63 cfs 0.086 af
Pond 7P: Porous Parking Lots	Peak Elev=1,425.00' Storage=28 cf Inflow=1.63 cfs 0.086 af Outflow=1.62 cfs 0.086 af
Pond FB-1: Forebay 1	Peak Elev=1,428.19' Storage=4,471 cf Inflow=4.24 cfs 0.450 af Outflow=3.99 cfs 0.355 af
Pond SMP1: Pocket Pond 1	Peak Elev=1,428.02' Storage=12,634 cf Inflow=3.99 cfs 0.355 af Outflow=0.31 cfs 0.066 af
Link AP-1: AP-1	Inflow=52.02 cfs 5.554 af Primary=52.02 cfs 5.554 af
Link AP-2: AP-2	Inflow=5.99 cfs 0.771 af

Total Runoff Area = 250.757 ac Runoff Volume = 6.795 af Average Runoff Depth = 0.33" 90.03% Pervious = 225.747 ac 9.97% Impervious = 25.010 ac

Gore Pre Development

Prepared by The LA Group

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 10-YR Rainfall=3.50" Printed 11/7/2017

11/1/2017

Primary=40.46 cfs 3.793 af

Page 6

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1: Subcat 1	Runoff Area=164.691 ac 8.95% Impervious Runoff Depth>1.05" Flow Length=2,229' Tc=29.6 min CN=73 Runoff=159.47 cfs 14.475 af
Subcatchment 2: Subcat 2	Runoff Area=35.807 ac 0.00% Impervious Runoff Depth>0.90" Flow Length=1,112' Tc=25.5 min CN=70 Runoff=31.53 cfs 2.672 af
Subcatchment3: Subcat3	Runoff Area=28.794 ac 30.03% Impervious Runoff Depth>1.42" Flow Length=3,110' Tc=24.7 min CN=79 Runoff=43.50 cfs 3.416 af
Subcatchment 4: Subcat 4	Runoff Area=17.152 ac 9.44% Impervious Runoff Depth>1.06" Flow Length=1,452' Tc=27.4 min CN=73 Runoff=17.49 cfs 1.509 af
Subcatchment 5: Subcat 5	Runoff Area=4.312 ac 0.00% Impervious Runoff Depth>0.90" Tc=6.0 min CN=70 Runoff=7.41 cfs 0.325 af
Pond 7P: Porous Parking Lots	Peak Elev=1,425.00' Storage=128 cf Inflow=7.41 cfs 0.325 af Outflow=7.41 cfs 0.325 af
Pond FB-1: Forebay 1	Peak Elev=1,428.48' Storage=5,100 cf Inflow=17.49 cfs 1.509 af Outflow=17.43 cfs 1.413 af
Pond SMP1: Pocket Pond 1	Peak Elev=1,428.36' Storage=14,548 cf Inflow=17.43 cfs 1.413 af Outflow=16.44 cfs 1.121 af
Link AP-1: AP-1	Inflow=200.44 cfs 17.891 af Primary=200.44 cfs 17.891 af
Link AP-2: AP-2	Inflow=40.46 cfs 3.793 af

Total Runoff Area = 250.757 ac Runoff Volume = 22.397 af Average Runoff Depth = 1.07" 90.03% Pervious = 225.747 ac 9.97% Impervious = 25.010 ac

Gore Pre Development

Prepared by The LA Group

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 100-YR Rainfall=5.50"

Printed 11/7/2017

Page 1

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1: Subcat1	Runoff Area=164.691 ac 8.95% Impervious Runoff Depth>2.44" Flow Length=2,229' Tc=29.6 min CN=73 Runoff=382.14 cfs 33.502 af
Subcatchment 2: Subcat 2	Runoff Area=35.807 ac 0.00% Impervious Runoff Depth>2.19" Flow Length=1,112' Tc=25.5 min CN=70 Runoff=81.61 cfs 6.541 af
Subcatchment 3: Subcat 3	Runoff Area=28.794 ac 30.03% Impervious Runoff Depth>2.98" Flow Length=3,110' Tc=24.7 min CN=79 Runoff=91.09 cfs 7.157 af
Subcatchment 4: Subcat 4	Runoff Area=17.152 ac 9.44% Impervious Runoff Depth>2.44" Flow Length=1,452' Tc=27.4 min CN=73 Runoff=41.92 cfs 3.492 af
Subcatchment 5: Subcat 5	Runoff Area=4.312 ac 0.00% Impervious Runoff Depth>2.21" Tc=6.0 min CN=70 Runoff=18.13 cfs 0.794 af
Pond 7P: Porous Parking Lots	Peak Elev=1,425.00' Storage=313 cf Inflow=18.13 cfs 0.794 af Outflow=18.14 cfs 0.794 af
Pond FB-1: Forebay 1	Peak Elev=1,428.85' Storage=5,953 cf Inflow=41.92 cfs 3.492 af Outflow=41.80 cfs 3.395 af
Pond SMP1: Pocket Pond 1	Peak Elev=1,428.65' Storage=16,221 cf Inflow=41.80 cfs 3.395 af Outflow=41.66 cfs 3.100 af
Link AP-1: AP-1	Inflow=468.63 cfs 40.659 af Primary=468.63 cfs 40.659 af
Link AP-2: AP-2	Inflow=122.47 cfs 9.641 af Primary=122.47 cfs 9.641 af

Total Runoff Area = 250.757 ac Runoff Volume = 51.486 af Average Runoff Depth = 2.46" 90.03% Pervious = 225.747 ac 9.97% Impervious = 25.010 ac

Printed 11/7/2017

Page 2

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Summary for Subcatchment 1: Subcat 1

Runoff = 382.14 cfs @ 12.24 hrs, Volume= 33.502 af, Depth> 2.44"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

_	Area	(ac) C	N Desc	cription		
	14.745 98 Paved parking, HSG C			ed parking	, HSG C	
_	149.	946	70 Woo	ds, Good,	HSG C	
	164.	691	73 Weig	ghted Aver	age	
	149.946 91.05% Pervious Area			5% Pervio	us Area	
	14.745 8.95% Impervious Area			% Impervi	ous Area	
	_					
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	12.8	100	0.1000	0.13		Sheet Flow,
						Woods: Light underbrush n= 0.400 P2= 2.50"
	16.8	2,129	0.1790	2.12		Shallow Concentrated Flow,
		•				Woodland Kv= 5.0 fps
	29.6	2,229	Total			

Summary for Subcatchment 2: Subcat 2

Runoff = 81.61 cfs @ 12.20 hrs, Volume= 6.541 af, Depth> 2.19"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

	Area	(ac) C	N Desc	cription					
_	35.807 70 Woods, Good, HSG C								
35.807 100.00% Pervious Area									
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
-	16.8	100	0.0500	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.50"			
	8.7	1,012	0.1500	1.94		Shallow Concentrated Flow, Woodland Kv= 5.0 fps			
_	25.5	1,112	Total						

Summary for Subcatchment 3: Subcat 3

Runoff = 91.09 cfs @ 12.18 hrs, Volume= 7.157 af, Depth> 2.98"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

Prepared by The LA Group

Printed 11/7/2017

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Page 3

Area	(ac) C	N Des	cription		
0.	942	74 >75% Grass cover, Good,			, HSG C
8.	646	98 Pave	ed parking	HSG C	
19.	207	70 Woo	ds, Good,	HSG C	
28.	794	79 Weig	ghted Aver	age	
20.	149	69.9	7% Pervio	us Area	
8.	646	30.0	3% Imperv	vious Area	
Tc	Length	Slope	Velocity	Capacity	Description
<u>(min)</u>	(feet)	(ft/ft)	(ft/sec)	(cfs)	
11.2	100	0.1400	0.15		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 2.50"
2.3	315	0.2000	2.24		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
0.6	160	0.0500	4.54		Shallow Concentrated Flow,
					Paved Kv= 20.3 fps
10.6	2,535	0.0700	3.97		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 fps
24.7	3,110	Total			

Summary for Subcatchment 4: Subcat 4

Runoff = 41.92 cfs @ 12.22 hrs, Volume= 3.492 af, Depth> 2.44"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

	Area	(ac) C	N Desc	cription		
	1.619 98		98 Pave	ed parking	, HSG C	
15.533 70			70 Woo	ds, Good,	HSG C	
	17.152 73 Weighted Average				age	
	15.533 90.56% Pervious Area				us Area	
	1.619 9.44% Impervious Area				ous Area	
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	14.7	100	0.0700	0.11		Sheet Flow,
						Woods: Light underbrush n= 0.400 P2= 2.50"
	12.7	1,352	0.1257	1.77		Shallow Concentrated Flow,
						Woodland Kv= 5.0 fps
	27.4	1,452	Total			

Summary for Subcatchment 5: Subcat 5

Runoff = 18.13 cfs @ 11.98 hrs, Volume= 0.794 af, Depth> 2.21"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

Gore Pre Development

Type II 24-hr 100-YR Rainfall=5.50"

Prepared by The LA Group

Printed 11/7/2017

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Page 4

_	Area	(ac)	CN	Desc	cription		
	4.	.312	70	Woo	ds, Good,	HSG C	
	4.	.312		100.	00% Pervi	ous Area	
	То	Long	·h (Clone	Volocity	Consoity	Description
	Tc (min)	Lengt (fee		Slope (ft/ft)	(ft/sec)	Capacity (cfs)	Description
	6.0	,	•		, ,	, ,	Direct Entry,

Summary for Pond 7P: Porous Parking Lots

Inflow Area = 4.312 ac, 0.00% Impervious, Inflow Depth > 2.21" for 100-YR event

Inflow = 18.13 cfs @ 11.98 hrs, Volume= 0.794 af

Outflow = 18.14 cfs @ 11.98 hrs, Volume= 0.794 af, Atten= 0%, Lag= 0.4 min

Discarded = 18.14 cfs @ 11.98 hrs, Volume= 0.794 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 1,425.00' @ 11.98 hrs Surf.Area= 145,040 sf Storage= 313 cf

Plug-Flow detention time= 0.3 min calculated for 0.794 af (100% of inflow)

Center-of-Mass det. time= 0.2 min (794.9 - 794.7)

<u>Volume</u>	Inve	rt Avai	l.Storage	Storage Descriptio	n	
#1	1,425.0	0' 14	45,040 cf	Custom Stage Da	ta (Irregular)Liste	d below (Recalc)
Elevation (feet)	=	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
1,425.00)	145,040	2,721.0	0	0	145,040
1,426.00)	145,040	2,721.0	145,040	145,040	147,761
Device I	Routina	Inv	vert Outl	et Devices		

#1 Discarded 1,425.00' **25.000 in/hr Exfiltration over Surface area**

Discarded OutFlow Max=83.94 cfs @ 11.98 hrs HW=1,425.00' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 83.94 cfs)

Summary for Pond FB-1: Forebay 1

Inflow Area = 17.152 ac, 9.44% Impervious, Inflow Depth > 2.44" for 100-YR event

Inflow = 41.92 cfs @ 12.22 hrs, Volume= 3.492 af

Outflow = 41.80 cfs @ 12.23 hrs, Volume= 3.395 af, Atten= 0%, Lag= 0.6 min

Primary = 41.80 cfs @ 12.23 hrs, Volume= 3.395 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Starting Elev= 323.00' Surf.Area= 0 sf Storage= 0 cf

Peak Elev= 1,428.85' @ 12.23 hrs Surf.Area= 2,432 sf Storage= 5,953 cf

Plug-Flow detention time= 15.5 min calculated for 3.384 af (97% of inflow)

Center-of-Mass det. time= 5.4 min (811.2 - 805.8)

Gore Pre Development

Prepared by The LA Group

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017 Page 5

Volume	Inve	rt Avai	I.Storage	Storage Description	on		
#1	1,425.00)'	9,130 cf	Custom Stage Da	ata (Irregular)Liste	ed below (Recalc)	
Elevation (feet)	Ş	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
1,425.00		805	104.0	0	0	805	
1,426.00		1,147	123.0	971	971	1,166	
1,427.00		1,546	142.0	1,342	2,313	1,589	
1,428.00		2,002	161.0	1,769	4,082	2,071	
1,429.00		2,515	180.0	2,254	6,335	2,614	
1,430.00		3,085	200.0	2,795	9,130	3,248	
Device F	Routing	In	vert Outle	et Devices			
#1 F	Primary	1,428				ed Rectangular Weir	
				d (feet) 0.20 0.40			
			Coef	. (English) 2.49 2.	56 2.70 2.69 2.6	88 2.69 2.67 2.64	

Primary OutFlow Max=41.47 cfs @ 12.23 hrs HW=1,428.84' (Free Discharge) 1=Broad-Crested Rectangular Weir (Weir Controls 41.47 cfs @ 2.47 fps)

Summary for Pond SMP1: Pocket Pond 1

Inflow Are	a =	17.152 ac,	9.44% Impervious, Infl	ow Depth > 2.38" for 100-YR event
Inflow	=	41.80 cfs @	12.23 hrs, Volume=	3.395 af
Outflow	=	41.66 cfs @	12.25 hrs, Volume=	3.100 af, Atten= 0%, Lag= 1.1 min
Primary	=	41.66 cfs @	12.25 hrs, Volume=	3.100 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 1,428.65' @ 12.25 hrs Surf.Area= 5,994 sf Storage= 16,221 cf

Plug-Flow detention time= 39.8 min calculated for 3.100 af (91% of inflow)

Center-of-Mass det. time= 11.0 min (822.3 - 811.2)

Volume	Inver	t Avail.	Storage	Storage Description	n	
#1	1,425.00	' 2	5,197 cf	Custom Stage Da	ta (Irregular)Listed	d below (Recalc)
Elevatio	-	Surf.Area	Perim.	Inc.Store	Cum.Store	Wet.Area
(fee	,	(sq-ft)	(feet)	(cubic-feet)	(cubic-feet)	<u>(sq-ft)</u>
1,425.0	0	3,031	236.0	0	0	3,031
1,426.0	0	3,768	255.0	3,393	3,393	3,813
1,427.0	0	4,563	274.0	4,159	7,552	4,655
1,428.0		5,414	293.0	4,982	12,534	5,558
1,429.0		6,323	312.0	5,863	18,397	6,522
1,430.0		7,288	331.0	6,800	25,197	7,546
Device	Routing	Inve	ert Outle	et Devices		
#1	Device 2	1,428.0	00' 24.0	" x 24.0" Horiz. Ori	fice/Grate C= 0.6	000
		,		ed to weir flow at lov		
#2	Primary	1,425.0	00' 24.0 Inlet	" Round Culvert L / Outlet Invert= 1,42	L= 100.0' Ke= 0.5 25.00' / 1,424.00'	00 S= 0.0100 '/' Cc= 0.900 Flow Area= 3.14 sf

Gore Pre Development

Type II 24-hr 100-YR Rainfall=5.50"

Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017 Page 6

#3 Primary 1,428.00' 20.0' long x 10.0' breadth Broad-Crested Rectangular Weir

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64

Primary OutFlow Max=41.56 cfs @ 12.25 hrs HW=1,428.65' (Free Discharge)

2=Culvert (Passes 13.57 cfs of 24.60 cfs potential flow)

1=Orifice/Grate (Weir Controls 13.57 cfs @ 2.63 fps)

-3=Broad-Crested Rectangular Weir (Weir Controls 27.99 cfs @ 2.17 fps)

Summary for Link AP-1: AP-1

Inflow Area = 193.486 ac, 12.09% Impervious, Inflow Depth > 2.52" for 100-YR event

Inflow = 468.63 cfs @ 12.23 hrs, Volume= 40.659 af

Primary = 468.63 cfs @ 12.23 hrs, Volume= 40.659 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Link AP-2: AP-2

Inflow Area = 57.271 ac, 2.83% Impervious, Inflow Depth > 2.02" for 100-YR event


Inflow = 122.47 cfs @ 12.21 hrs, Volume= 9.641 af

Primary = 122.47 cfs @ 12.21 hrs, Volume= 9.641 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Attachment C

Proposed Conditions Watershed Map and HydroCAD Calculations



The LA GROUP

Landscape Architecture & Engineering P.C.

People. Purpose. Place.

40 Long Alley p: 518-587-8100
Saratoga Springs f: 518-587-0180
NY 12866 www.thelagroup.com

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law.

© the LA Group 2017

Prepared for:

Olympic Regional Development Authority

2634 Main Street Lake Placid, New York 12946

Project Title:
Gore Mountain: 2017 Unit Management Plan Draft Amendment & Draft Generic Environmental Impact Statement


Project No.:			2015037
Design:			BCS
Drawn:	BCS	Ch'k'd:	DBH
		Scale:	1"=200'

Drawing Title

Proposed Conditions Watershed map

Drawing No.

W-2



Gore Post Development
Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017 Page 2

Area Listing (all nodes)

	Area	CN	Description
	(acres)		(subcatchment-numbers)
	2.479	74	>75% Grass cover, Good, HSG C (1, 3, 7, 8)
	26.675	98	Paved parking, HSG C (1, 3, 4, 5, 7, 8)
2	21.578	70	Woods, Good, HSG C (1, 2, 3, 4, 5, 6, 7, 8)
2	250.732	73	TOTAL AREA

Gore Post Development
Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
250.732	HSG C	1, 2, 3, 4, 5, 6, 7, 8
0.000	HSG D	
0.000	Other	
250.732		TOTAL AREA

Gore Post Development
Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017

Page 4

Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	2.479	0.000	0.000	2.479	>75% Grass cover, Good	1, 3, 7, 8
0.000	0.000	26.675	0.000	0.000	26.675	Paved parking	1, 3, 4, 5,
							7, 8
0.000	0.000	221.578	0.000	0.000	221.578	Woods, Good	1, 2, 3, 4,
							5, 6, 7, 8
0.000	0.000	250.732	0.000	0.000	250.732	TOTAL AREA	

Page 5

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points Runoff by SCS TR-20 method, UH=SCS, Weighted-CN Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1: Subcat1	Runoff Area=163.668 ac 9.12% Impervious Runoff Depth>0.31" Flow Length=2,229' Tc=29.6 min CN=73 Runoff=38.20 cfs 4.289 af
Subcatchment 2: Subcat 2	Runoff Area=35.807 ac 0.00% Impervious Runoff Depth>0.24" Flow Length=1,112' Tc=25.5 min CN=70 Runoff=5.99 cfs 0.705 af
Subcatchment 3: Subcat 3	Runoff Area=19.014 ac 35.43% Impervious Runoff Depth>0.56" Flow Length=3,110' Tc=24.7 min CN=80 Runoff=10.68 cfs 0.881 af
Subcatchment 4: Subcat 4	Runoff Area=17.152 ac 9.44% Impervious Runoff Depth>0.31" Flow Length=1,452' Tc=27.4 min CN=73 Runoff=4.24 cfs 0.450 af
Subcatchment 5: Subcat 5	Runoff Area=1.075 ac 28.40% Impervious Runoff Depth>0.48" Flow Length=324' Tc=18.5 min CN=78 Runoff=0.60 cfs 0.043 af
Subcatchment 6: Subcat 6	Runoff Area=4.312 ac 0.00% Impervious Runoff Depth>0.24" Tc=6.0 min CN=70 Runoff=1.63 cfs 0.086 af
Subcatchment7: Subcat 7	Runoff Area=214,383 sf 42.27% Impervious Runoff Depth>0.65" Flow Length=1,411' Tc=12.2 min CN=82 Runoff=4.85 cfs 0.265 af
Subcatchment 8: Subcat 8	Runoff Area=4.782 ac 21.00% Impervious Runoff Depth>0.41" Flow Length=1,380' Tc=20.9 min CN=76 Runoff=2.04 cfs 0.163 af
Reach SMP-1: Vegetated Swale n=0.150	Avg. Flow Depth=0.33' Max Vel=1.01 fps Inflow=4.85 cfs 0.265 af L=1,317.0' S=0.0580 '/' Capacity=77.31 cfs Outflow=2.40 cfs 0.252 af
Pond 7P: Porous Parking Lots	Peak Elev=1,425.00' Storage=28 cf Inflow=1.63 cfs 0.086 af Outflow=1.62 cfs 0.086 af
Pond FB-1: Forebay 1	Peak Elev=1,428.19' Storage=4,471 cf Inflow=4.24 cfs 0.450 af Outflow=3.99 cfs 0.355 af
Pond PP-1: Pocket Pond 1	Peak Elev=1,428.02' Storage=12,634 cf Inflow=3.99 cfs 0.355 af Outflow=0.31 cfs 0.066 af
Pond SMP2: Bioretention Basin	Peak Elev=1,570.19' Storage=550 cf Inflow=0.60 cfs 0.043 af Outflow=0.14 cfs 0.043 af
Pond SMP3: Bioretention Basin	Peak Elev=1,464.64' Storage=1,548 cf Inflow=2.04 cfs 0.163 af Outflow=1.46 cfs 0.143 af
Link AP-1: AP-1	Inflow=49.66 cfs 5.607 af Primary=49.66 cfs 5.607 af
Link AP-2: AP-2	Inflow=5.99 cfs 0.771 af Primary=5.99 cfs 0.771 af

Type II 24-hr 1-YR Rainfall=2.10" Printed 11/7/2017

Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Page 6

Total Runoff Area = 250.732 ac Runoff Volume = 6.882 af Average Runoff Depth = 0.33" 89.36% Pervious = 224.057 ac 10.64% Impervious = 26.675 ac

Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017

Page 7

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1: Subcat1	Runoff Area=163.668 ac 9.12% Impervious Runoff Depth>1.05" Flow Length=2,229' Tc=29.6 min CN=73 Runoff=158.48 cfs 14.385 af
Subcatchment 2: Subcat 2	Runoff Area=35.807 ac 0.00% Impervious Runoff Depth>0.90" Flow Length=1,112' Tc=25.5 min CN=70 Runoff=31.53 cfs 2.672 af
Subcatchment 3: Subcat 3	Runoff Area=19.014 ac 35.43% Impervious Runoff Depth>1.49" Flow Length=3,110' Tc=24.7 min CN=80 Runoff=30.14 cfs 2.363 af
Subcatchment 4: Subcat 4	Runoff Area=17.152 ac 9.44% Impervious Runoff Depth>1.06" Flow Length=1,452' Tc=27.4 min CN=73 Runoff=17.49 cfs 1.509 af
Subcatchment 5: Subcat 5	Runoff Area=1.075 ac 28.40% Impervious Runoff Depth>1.36" Flow Length=324' Tc=18.5 min CN=78 Runoff=1.84 cfs 0.122 af
Subcatchment 6: Subcat 6	Runoff Area=4.312 ac 0.00% Impervious Runoff Depth>0.90" Tc=6.0 min CN=70 Runoff=7.41 cfs 0.325 af
Subcatchment7: Subcat7	Runoff Area=214,383 sf 42.27% Impervious Runoff Depth>1.64" Flow Length=1,411' Tc=12.2 min CN=82 Runoff=12.38 cfs 0.672 af
Subcatchment 8: Subcat 8	Runoff Area=4.782 ac 21.00% Impervious Runoff Depth>1.23" Flow Length=1,380' Tc=20.9 min CN=76 Runoff=6.88 cfs 0.492 af
Reach SMP-1: Vegetated Swale n=0.150	Avg. Flow Depth=0.63' Max Vel=1.46 fps Inflow=12.38 cfs 0.672 af L=1,317.0' S=0.0580 '/' Capacity=77.31 cfs Outflow=7.88 cfs 0.653 af
Pond 7P: Porous Parking Lots	Peak Elev=1,425.00' Storage=128 cf Inflow=7.41 cfs 0.325 af Outflow=7.41 cfs 0.325 af
Pond FB-1: Forebay 1	Peak Elev=1,428.48' Storage=5,100 cf Inflow=17.49 cfs 1.509 af Outflow=17.43 cfs 1.413 af
Pond PP-1: Pocket Pond 1	Peak Elev=1,428.36' Storage=14,548 cf Inflow=17.43 cfs 1.413 af Outflow=16.44 cfs 1.121 af
Pond SMP2: Bioretention Basin	Peak Elev=1,570.58' Storage=1,858 cf Inflow=1.84 cfs 0.122 af Outflow=0.77 cfs 0.122 af
Pond SMP3: Bioretention Basin	Peak Elev=1,464.90' Storage=2,260 cf Inflow=6.88 cfs 0.492 af Outflow=6.66 cfs 0.464 af
Link AP-1: AP-1	Inflow=197.68 cfs 17.986 af Primary=197.68 cfs 17.986 af
Link AP-2: AP-2	Inflow=40.46 cfs 3.793 af Primary=40.46 cfs 3.793 af

Type II 24-hr 10-YR Rainfall=3.50" Printed 11/7/2017

Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Page 8

Total Runoff Area = 250.732 ac Runoff Volume = 22.539 af Average Runoff Depth = 1.08" 89.36% Pervious = 224.057 ac 10.64% Impervious = 26.675 ac

Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 100-YR Rainfall=5.50" Printed 11/7/2017

Page 1

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points Runoff by SCS TR-20 method, UH=SCS, Weighted-CN Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1: Subcat 1	Runoff Area=163.668 ac 9.12% Impervious Runoff Depth>2.44" Flow Length=2,229' Tc=29.6 min CN=73 Runoff=379.77 cfs 33.294 af
Subcatchment 2: Subcat 2	Runoff Area=35.807 ac 0.00% Impervious Runoff Depth>2.19" Flow Length=1,112' Tc=25.5 min CN=70 Runoff=81.61 cfs 6.541 af
Subcatchment 3: Subcat 3	Runoff Area=19.014 ac 35.43% Impervious Runoff Depth>3.08" Flow Length=3,110' Tc=24.7 min CN=80 Runoff=61.92 cfs 4.875 af
Subcatchment 4: Subcat 4	Runoff Area=17.152 ac 9.44% Impervious Runoff Depth>2.44" Flow Length=1,452' Tc=27.4 min CN=73 Runoff=41.92 cfs 3.492 af
Subcatchment 5: Subcat 5	Runoff Area=1.075 ac 28.40% Impervious Runoff Depth>2.90" Flow Length=324' Tc=18.5 min CN=78 Runoff=3.90 cfs 0.260 af
Subcatchment 6: Subcat 6	Runoff Area=4.312 ac 0.00% Impervious Runoff Depth>2.21" Tc=6.0 min CN=70 Runoff=18.13 cfs 0.794 af
Subcatchment 7: Subcat 7	Runoff Area=214,383 sf 42.27% Impervious Runoff Depth>3.28" Flow Length=1,411' Tc=12.2 min CN=82 Runoff=24.19 cfs 1.345 af
Subcatchment 8: Subcat 8	Runoff Area=4.782 ac 21.00% Impervious Runoff Depth>2.71" Flow Length=1,380' Tc=20.9 min CN=76 Runoff=15.24 cfs 1.081 af
Reach SMP-1: Vegetated Swale n=0.150	Avg. Flow Depth=0.95' Max Vel=1.83 fps Inflow=24.19 cfs 1.345 af L=1,317.0' S=0.0580 '/' Capacity=77.31 cfs Outflow=17.10 cfs 1.318 af
Pond 7P: Porous Parking Lots	Peak Elev=1,425.00' Storage=313 cf Inflow=18.13 cfs 0.794 af Outflow=18.14 cfs 0.794 af
Pond FB-1: Forebay 1	Peak Elev=1,428.85' Storage=5,953 cf Inflow=41.92 cfs 3.492 af Outflow=41.80 cfs 3.395 af
Pond PP-1: Pocket Pond 1	Peak Elev=1,428.65' Storage=16,221 cf Inflow=41.80 cfs 3.395 af Outflow=41.66 cfs 3.100 af
Pond SMP2: Bioretention Basin	Peak Elev=1,570.75' Storage=2,505 cf Inflow=3.90 cfs 0.260 af Outflow=3.34 cfs 0.245 af
Pond SMP3: Bioretention Basin	Peak Elev=1,465.21' Storage=2,543 cf Inflow=15.24 cfs 1.081 af Outflow=16.10 cfs 1.073 af
Link AP-1: AP-1	Inflow=468.61 cfs 40.805 af Primary=468.61 cfs 40.805 af
Link AP-2: AP-2	Inflow=122.47 cfs 9.641 af Primary=122.47 cfs 9.641 af

Type II 24-hr 100-YR Rainfall=5.50" Printed 11/7/2017

Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Page 2

Total Runoff Area = 250.732 ac Runoff Volume = 51.682 af Average Runoff Depth = 2.47" 89.36% Pervious = 224.057 ac 10.64% Impervious = 26.675 ac

Page 3

Summary for Subcatchment 1: Subcat 1

Runoff = 379.77 cfs @ 12.24 hrs, Volume= 33.294 af, Depth> 2.44"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

	Area	(ac) (CN Des	cription		
	0.	109	74 >75	% Grass co	over, Good	, HSG C
	14.	928	98 Pav	ed parking	, HSG C	
148.631 70 Woods, Good, HSG C						
	163.	668	73 Wei	ghted Aver	age	
	148.	740		88% Pervio		
	14.	928	9.12	% Impervi	ous Area	
	_		01			B 1.0
	Tc	Length		Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	12.8	100	0.1000	0.13		Sheet Flow,
						Woods: Light underbrush n= 0.400 P2= 2.50"
	16.8	2,129	0.1790	2.12		Shallow Concentrated Flow,
_						Woodland Kv= 5.0 fps
	29.6	2,229	Total			

Summary for Subcatchment 2: Subcat 2

Runoff = 81.61 cfs @ 12.20 hrs, Volume= 6.541 af, Depth> 2.19"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

Are	ea (a	c) C	N Desc	cription		
	35.80	7)7	O Woo	ds, Good,	HSG C	
	35.80)7	100.	00% Pervi	ous Area	
T (mir		ength.	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.	8	100	0.0500	0.10	, , ,	Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.50"
8.	7	1,012	0.1500	1.94		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
25.	5	1,112	Total			

Summary for Subcatchment 3: Subcat 3

Runoff = 61.92 cfs @ 12.18 hrs, Volume= 4.875 af, Depth> 3.08"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

Type II 24-hr 100-YR Rainfall=5.50"

Prepared by The LA Group

Printed 11/7/2017

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Page 4

	Area	(ac) C	N Desc	cription						
	1.	256 7	74 >75°	>75% Grass cover, Good, HSG C						
	6.	737	8 Pave	ed parking						
_	11.	022 7	70 Woo	Woods, Good, HSG C						
	19.	014 8	30 Weig	ghted Aver	age					
	12.	277	64.5	7% Pervio	us Area					
	6.	737	35.4	3% Imperv	ious Area					
	_		01			D. C. C.				
	Tc	Length	Slope	Velocity	Capacity	Description				
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)					
	11.2	100	0.1400	0.15		Sheet Flow,				
						Woods: Light underbrush n= 0.400 P2= 2.50"				
	2.3	315	0.2000	2.24		Shallow Concentrated Flow,				
						Woodland Kv= 5.0 fps				
	0.6	160	0.0500	4.54		Shallow Concentrated Flow,				
	40.0	0 =0=				Paved Kv= 20.3 fps				
	10.6	2,535	0.0700	3.97		Shallow Concentrated Flow,				
_						Grassed Waterway Kv= 15.0 fps				
	24.7	3,110	Total							

Summary for Subcatchment 4: Subcat 4

Runoff = 41.92 cfs @ 12.22 hrs, Volume= 3.492 af, Depth> 2.44"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

_	Area	(ac) (N Des	cription		
1.619 98 Paved parking, HSG C						
15.533 70 Woods, Good, HSG C					HSG C	
17.152 73 Weighted Average					age	
	15.	533	90.5	6% Pervio	us Area	
	1.	619	9.44	% Impervi	ous Area	
	Тс	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	14.7	100	0.0700	0.11		Sheet Flow,
						Woods: Light underbrush n= 0.400 P2= 2.50"
	12.7	1,352	0.1257	1.77		Shallow Concentrated Flow,
		•				Woodland Kv= 5.0 fps
	27.4	1,452	Total			

Summary for Subcatchment 5: Subcat 5

Runoff = 3.90 cfs @ 12.11 hrs, Volume= 0.260 af, Depth> 2.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

Prepared by The LA Group

Printed 11/7/2017

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Page 5

_	Area	(ac) C	N Desc	cription		
	0.	305		ed parking		
0.770 70 Woods, Good, HSG C						
	1.	075 7	78 Weig	ghted Aver	age	
	0.	770	71.6	0% Pervio	us Area	
	0.	305	28.4	0% Imperv	ious Area	
	·					
	Tc	Length	Slope	Velocity	Capacity	Description
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	16.8	100	0.0500	0.10		Sheet Flow,
						Woods: Light underbrush n= 0.400 P2= 2.50"
	1.7	224	0.1000	2.21		Shallow Concentrated Flow,
						Short Grass Pasture Kv= 7.0 fps
_	18.5	324	Total			·

Summary for Subcatchment 6: Subcat 6

Runoff = 18.13 cfs @ 11.98 hrs, Volume= 0.794 af, Depth> 2.21"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

Area	(ac) (CN Des	cription		
4.	312	70 Wo	ods, Good,	HSG C	
4.	312	100	.00% Pervi	ious Area	
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Summary for Subcatchment 7: Subcat 7

Runoff = 24.19 cfs @ 12.04 hrs, Volume= 1.345 af, Depth> 3.28"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

 Area (sf)	CN	Description			
30,438	74	>75% Grass cover, Good, HSG C			
90,629	98	Paved parking, HSG C			
 93,317	70	Woods, Good, HSG C			
214,383	82	Weighted Average			
123,755		57.73% Pervious Area			
90,629		42.27% Impervious Area			

Prepared by The LA Group

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Page 6

 Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.4	100	0.0800	0.26		Sheet Flow,
					Grass: Short n= 0.150 P2= 2.50"
2.1	404	0.0470	3.25		Shallow Concentrated Flow,
0.7	100	0.0470	4.40		Grassed Waterway Kv= 15.0 fps
0.7	190	0.0470	4.40		Shallow Concentrated Flow, Paved Kv= 20.3 fps
3.0	717	0.0700	3.97		Shallow Concentrated Flow,
0.0		0.07.00	0.01		Grassed Waterway Kv= 15.0 fps
12.2	1,411	Total			

Summary for Subcatchment 8: Subcat 8

Runoff = 15.24 cfs @ 12.14 hrs, Volume= 1.081 af, Depth> 2.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-YR Rainfall=5.50"

Area	(ac) C	N Desc	cription		
0.	416 7	74 >75°	% Grass co	over, Good,	, HSG C
1.	004	8 Pave	ed parking,	, HSG C	
3.	362 7	'0 Woo	ds, Good,	HSG C	
4.	782 7	'6 Weig	ghted Aver	age	
3.	778	79.0	0% Pervio	us Area	
1.	004	21.0	0% Imperv	vious Area	
Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
12.3	100	0.1100	0.14		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 2.50"
7.0	749	0.1290	1.80		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
1.6	531	0.0790	5.71		Shallow Concentrated Flow,
					Paved Kv= 20.3 fps
20.9	1,380	Total			

Summary for Reach SMP-1: Vegetated Swale

Inflow Area = 4.922 ac, 42.27% Impervious, Inflow Depth > 3.28" for 100-YR event

Inflow = 24.19 cfs @ 12.04 hrs, Volume= 1.345 af

Outflow = 17.10 cfs @ 12.33 hrs, Volume= 1.318 af, Atten= 29%, Lag= 17.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.83 fps, Min. Travel Time= 12.0 min Avg. Velocity = 0.61 fps, Avg. Travel Time= 36.2 min

Peak Storage= 12,285 cf @ 12.13 hrs Average Depth at Peak Storage= 0.95'

Bank-Full Depth= 2.00' Flow Area= 28.0 sf, Capacity= 77.31 cfs

Type II 24-hr 100-YR Rainfall=5.50"

Prepared by The LA Group
HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017

Page 7

6.00' x 2.00' deep channel, n= 0.150

Side Slope Z-value= 4.0 '/' Top Width= 22.00'

Length= 1,317.0' Slope= 0.0580 '/'

Inlet Invert= 1,465.00', Outlet Invert= 1,388.61'



Summary for Pond 7P: Porous Parking Lots

Inflow Area = 4.312 ac, 0.00% Impervious, Inflow Depth > 2.21" for 100-YR event

Inflow = 18.13 cfs @ 11.98 hrs, Volume= 0.794 af

Outflow = 18.14 cfs @ 11.98 hrs, Volume= 0.794 af, Atten= 0%, Lag= 0.4 min

Discarded = 18.14 cfs @ 11.98 hrs, Volume= 0.794 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Peak Elev= 1,425.00' @ 11.98 hrs Surf.Area= 145,040 sf Storage= 313 cf

Plug-Flow detention time= 0.3 min calculated for 0.794 af (100% of inflow)

Center-of-Mass det. time= 0.2 min (794.9 - 794.7)

below (Recalc	a (Irregular)Listed	Custom Stage Data	15,040 cf	425.00' 14	#1
Wet.Area (sq-ft)	Cum.Store (cubic-feet)	Inc.Store (cubic-feet)	Perim. (feet)	Surf.Area (sq-ft)	Elevation (feet)
145,040	0	0	2,721.0	145,040	1,425.00
147,761	145,040	145,040	2,721.0	145,040	1,426.00

Device Routing Invert Outlet Devices

#1 Discarded 1.425.00' **25.000** in/hr Exfiltration over Surface area

Discarded OutFlow Max=83.94 cfs @ 11.98 hrs HW=1,425.00' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 83.94 cfs)

Summary for Pond FB-1: Forebay 1

Inflow Area = 17.152 ac, 9.44% Impervious, Inflow Depth > 2.44" for 100-YR event

Inflow = 41.92 cfs @ 12.22 hrs, Volume= 3.492 af

Outflow = 41.80 cfs @ 12.23 hrs, Volume= 3.395 af, Atten= 0%, Lag= 0.6 min

Primary = 41.80 cfs @ 12.23 hrs, Volume= 3.395 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Starting Elev= 323.00' Surf.Area= 0 sf Storage= 0 cf

Peak Elev= 1,428.85' @ 12.23 hrs Surf.Area= 2,432 sf Storage= 5,953 cf

Plug-Flow detention time= 15.5 min calculated for 3.384 af (97% of inflow)

Prepared by The LA Group

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017 Page 8

Center-of-Mass det. time= 5.4 min (811.2 - 805.8)

Volume	Inv	ert Avai	I.Storage	Storage Description	on		
#1	1,425.0	00'	9,130 cf	Custom Stage D	ata (Irregular) Liste	ed below (Recalc)	
Elevation (feet)		Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
1,425.00		805	104.0	0	0	805	
1,426.00		1,147	123.0	971	971	1,166	
1,427.00		1,546	142.0	1,342	2,313	1,589	
1,428.00		2,002	161.0	1,769	4,082	2,071	
1,429.00		2,515	180.0	2,254	6,335	2,614	
1,430.00		3,085	200.0	2,795	9,130	3,248	
Device F	Routing	In	vert Outle	et Devices			
#1 F	Primary	1,428	.00' 20.0	' long x 10.0' brea	adth Broad-Creste	ed Rectangular Weir	
			Head	d (feet) 0.20 0.40	0.60 0.80 1.00 1	.20 1.40 1.60	
			Coef	f. (English) 2.49 2	.56 2.70 2.69 2.6	88 2.69 2.67 2.64	

Primary OutFlow Max=41.47 cfs @ 12.23 hrs HW=1,428.84' (Free Discharge) 1=Broad-Crested Rectangular Weir (Weir Controls 41.47 cfs @ 2.47 fps)

Summary for Pond PP-1: Pocket Pond 1

Inflow Area = 17.152 ac, 9.44% Impervious, Inflow Depth > 2.38" for 100-YR event

Inflow = 41.80 cfs @ 12.23 hrs, Volume= 3.395 af

Outflow = 41.66 cfs @ 12.25 hrs, Volume= 3.100 af, Atten= 0%, Lag= 1.1 min

Primary = 41.66 cfs @ 12.25 hrs, Volume= 3.100 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 1,428.65' @ 12.25 hrs Surf.Area= 5,994 sf Storage= 16,221 cf

Plug-Flow detention time= 39.8 min calculated for 3.100 af (91% of inflow)

Center-of-Mass det. time= 11.0 min (822.3 - 811.2)

Volume	Inver	t Avail.	Storage	Storage Description	on		
#1	1,425.00)' 25	5,197 cf	Custom Stage Da	ata (Irregular) Lis	ted below (Recalc)	
Elevation (feet)		Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
1,425.00)	3,031	236.0	0	0	3,031	
1,426.00)	3,768	255.0	3,393	3,393	3,813	
1,427.00)	4,563	274.0	4,159	7,552	4,655	
1,428.00)	5,414	293.0	4,982	12,534	5,558	
1,429.00)	6,323	312.0	5,863	18,397	6,522	
1,430.00)	7,288	331.0	6,800	25,197	7,546	
Device I	Routing	Inve	ert Outle	et Devices			
#1 l	Device 2	1,428.0	00' 24.0	" x 24.0" Horiz. Or	rifice/Grate C=	0.600	
			Limit	ed to weir flow at le	ow heads		
#2 l	Primary	1,425.0	00' 24.0	" Round Culvert	L= 100.0' Ke= 0).500	

Prepared by The LA Group HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC Printed 11/7/2017

Page 9

Inlet / Outlet Invert= 1,425.00' / 1,424.00' S= 0.0100 '/' Cc= 0.900

n= 0.013 Corrugated PE, smooth interior, Flow Area= 3.14 sf

#3 Primary 1,428.00' 20.0' long x 10.0' breadth Broad-Crested Rectangular Weir

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64

Primary OutFlow Max=41.56 cfs @ 12.25 hrs HW=1,428.65' (Free Discharge)

2=Culvert (Passes 13.57 cfs of 24.60 cfs potential flow)

1=Orifice/Grate (Weir Controls 13.57 cfs @ 2.63 fps)

-3=Broad-Crested Rectangular Weir (Weir Controls 27.99 cfs @ 2.17 fps)

Summary for Pond SMP2: Bioretention Basin

Inflow Area = 1.075 ac, 28.40% Impervious, Inflow Depth > 2.90" for 100-YR event

Inflow 3.90 cfs @ 12.11 hrs, Volume= 0.260 af

3.34 cfs @ 12.19 hrs, Volume= Outflow 0.245 af, Atten= 15%, Lag= 5.1 min

3.34 cfs @ 12.19 hrs, Volume= Primary 0.245 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 1,570.75' @ 12.19 hrs Surf.Area= 4,026 sf Storage= 2,505 cf

Plug-Flow detention time= 60.5 min calculated for 0.245 af (94% of inflow)

Center-of-Mass det. time= 39.9 min (829.6 - 789.7)

Volume	Inve	rt Avail	.Storage	Storage Descriptio	n		
#1	1,570.00	0'	4,518 cf	Custom Stage Da	ita (Irregular)Liste	ed below (Recalc)	
Elevation (fee 1,570.0 1,571.2	ot) 00	Surf.Area (sq-ft) 2,691 4,953	Perim. (feet) 275.0 308.0	Inc.Store (cubic-feet) 0 4,518	Cum.Store (cubic-feet) 0 4,518	Wet.Area (sq-ft) 2,691 4,261	
Device	Routing	Inv	ert Outle	et Devices			
#1	Device 3	1,570.	00' 2.00	0 in/hr Exfiltration	over Surface are	a	
#2	Primary	1,570.	50' 10.0 '	' long x 10.0' brea	dth Broad-Creste	ed Rectangular Weir	
#3	Primary	1,566.	Coef 75' 6.0" Inlet	Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64 6.0" Round Culvert L= 30.0' Ke= 0.500 Inlet / Outlet Invert= 1,566.75' / 1,565.00' S= 0.0583 '/' Cc= 0.900 n= 0.012, Flow Area= 0.20 sf			

Primary OutFlow Max=3.31 cfs @ 12.19 hrs HW=1,570.75' (Free Discharge)

-2=Broad-Crested Rectangular Weir (Weir Controls 3.13 cfs @ 1.25 fps)

3=Culvert (Passes 0.19 cfs of 1.83 cfs potential flow)

1=Exfiltration (Exfiltration Controls 0.19 cfs)

HydroCAD® 10.00-19 s/n 00439 © 2016 HydroCAD Software Solutions LLC

Printed 11/7/2017 Page 10

Summary for Pond SMP3: Bioretention Basin

Inflow Area = 4.782 ac, 21.00% Impervious, Inflow Depth > 2.71" for 100-YR event

Inflow = 15.24 cfs @ 12.14 hrs, Volume= 1.081 af

Outflow = 16.10 cfs @ 12.14 hrs, Volume= 1.073 af, Atten= 0%, Lag= 0.0 min

Primary = 16.10 cfs @ 12.14 hrs, Volume= 1.073 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 1,465.21' @ 12.14 hrs Surf.Area= 2,928 sf Storage= 2,543 cf

Plug-Flow detention time= 7.6 min calculated for 1.070 af (99% of inflow)

Center-of-Mass det. time= 4.7 min (800.1 - 795.4)

Volume	Inve	rt Avail	.Storage	Storage Description	on			
#1	1,464.00	O'	2,543 cf	Custom Stage Da	ata (Irregular)Liste	ed below (Recalc)		
Elevation (fee 1,464.0 1,465.0	(t) (O	Surf.Area (sq-ft) 2,177 2,928	Perim. (feet) 175.0 200.0	Inc.Store (cubic-feet) 0 2,543	Cum.Store (cubic-feet) 0 2,543	Wet.Area (sq-ft) 2,177 2,946		
Device	Routing	Inv	ert Outle	et Devices				
#1	Device 3	1,464.	00' 2.00	0 in/hr Exfiltration	over Surface are	a		
#2	Primary	1,464.	50' 10.0 '	long x 10.0' brea	dth Broad-Creste	d Rectangular Wei	ſ	
#3	Primary	1,460.	Coef 75' 6.0" Inlet	Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64 6.0" Round Culvert L= 35.0' Ke= 0.500 nlet / Outlet Invert= 1,460.75' / 1,460.00' S= 0.0214 '/' Cc= 0.900 n= 0.012, Flow Area= 0.20 sf				

Primary OutFlow Max=15.97 cfs @ 12.14 hrs HW=1,465.20' (Free Discharge)

2=Broad-Crested Rectangular Weir (Weir Controls 15.84 cfs @ 2.26 fps)

-3=Culvert (Passes 0.14 cfs of 1.74 cfs potential flow)

1=Exfiltration (Exfiltration Controls 0.14 cfs)

Summary for Link AP-1: AP-1

Inflow Area = 193.461 ac, 12.95% Impervious, Inflow Depth > 2.53" for 100-YR event

Inflow = 468.61 cfs @ 12.24 hrs, Volume= 40.805 af

Primary = 468.61 cfs @ 12.24 hrs, Volume= 40.805 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Summary for Link AP-2: AP-2

Inflow Area = 57.271 ac, 2.83% Impervious, Inflow Depth > 2.02" for 100-YR event

Inflow = 122.47 cfs @ 12.21 hrs, Volume= 9.641 af

Primary = 122.47 cfs @ 12.21 hrs, Volume= 9.641 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Attachment D

Storm Data

Gore Mountain

Minimum Runoff Reduction Volume

11/7/2017

 $\mathbf{RRv} = [(\mathbf{P})(\mathbf{Rv}^*)(\mathbf{Ai})]/12$

Where:

Ai = (S)(Aic)

Rv = 0.05 + 0.009(I) where I is 100% impervious

Ai = impervious cover targeted for runoff reduction

Aic = Total area of new impervious cover

P = 90% rainfall (see Figure 4.1 in NYS Stormwater Management Design Manual)

S = Hydrologic Soil Group (HSG) Specific Reduction Factor (S)

A=0.55, B=0.40, C=0.30, D=0.20

S (HSG C)	0.30
Aic	1.58 acres
Rv	0.95
90% Rainfall	1.10
Ai	0.474

RRv =**0.041** acre feet = 1,799 ft³

Stormwater Practice Sizing

Job Name and #

Gore Mountain

Water Quality Volume Calculation

11/7/2017

 $\mathbf{WQv} = [(\mathbf{P})(\mathbf{Rv})(\mathbf{A})]/12$

Where:

Rv = 0.05 + 0.009(I)

I = impervious cover in percent

P = 90% rainfall (see Figure 4.1 in NYS Stormwater Management Design Manual)

A = Area in acres

New Impervious

% Impervious	100.00%
Rv	0.95
90% Rainfall	1.10
Area in Square Feet	68868

 $WQv Required = 5997 ft^3$

0.138 ac-ft

SMP-1: Wet Swale

% Impervious	42.27%
Rv	0.43
90% Rainfall	1.10
Area in Square Feet	214402

 $WQv Required = 8459 ft^3$

0.194 ac-ft

SMP-2: Bioretention Basin

% Impervious	21.48%
Rv	0.24
90% Rainfall	1.10
Area in Square Feet	62204

WQv Required = 1387 ft³

0.032 ac-ft

SMP-3: Bioretention Basin

% Impervious	21.00%
Rv	0.24
90% Rainfall	1.10
Area in Square Feet	208304

 $WQv Required = 4564 ft^3$

0.105 ac-ft

BIORETENTION WORKSHEET

(See Section 6.4.4 of the NYSDEC Stormwater Management Design Manual 2015)

1.	Underlying soil permeability	=	0.50 in/h	٦r
	(if no underdrains proposed, must infiltrate within 48 hours,			
	HSG A and B Soils)			

2. Calculate WQv:

DA (maximum 5 acres)	=	62,210 ft ²
Percent Impervious Area, I	=	21.48 %
Rv = .05 + .009 (1) (Minimum 0.2)	=	0.243
P (90% Rainfall)	=	1.10 in.
WQv = P Rv A/12	=	1,388 ft ³
75% of WQv		1,040.7

3. Bioretention Details:

Material		Planting So	il Mix
Filter bed depth (d _f) (2.5 - 4.0 ft)	=	2.50	ft
Coefficient of permeability of filter media (k)	=	1.00	ft/day
Avg. height of water above filter media (h _f) (max. 0.5 ft	=	0.50	ft
Design filter bed drain time (t _f)	=	2	days

4. Calculate required bioretention surface area (A_f):

Surface area
$$(A_f) = \frac{WQv \times d_f}{k (h_f + d_f) (t_f)}$$

		Required Surface Area (A _f)	=	578 ft ²
5.	Bioretention surface area pro	ovided	=	600 ft ² (design)
6.	Water Quality Volume provide	ed	=	1440 ft3 (design)
7.	Is Bioretention Basin Lined o	r in HSG C/D Soils		Yes
8.	Runoff Reduction Volume pro	ovided	=	576 ft3 (design)

BIORETENTION WORKSHEET-SMP-3

(See Section 6.4.4 of the NYSDEC Stormwater Management Design Manual 2015)

1. Underlying soil permeability = 0.50 in/hr (if no underdrains proposed, must infiltrate within 48 hours, HSG A and B Soils)

2. Calculate WQv:

DA (maximum 5 acres)	=	208,303 ft ²
Percent Impervious Area, I	-	21.00 %
Rv = .05 + .009 (I) (Minimum 0.2)	=	0.239
P (90% Rainfall)	-	1.10 in.
WQv = P Rv A/12	=	4,564 ft ³
75% of WQv		3,422.7

3. Bioretention Details:

Material		Planting So	oil Mix
Filter bed depth (d _f) (2.5 - 4.0 ft)	=	2.50	ft
Coefficient of permeability of filter media (k)	=	1.00	ft/day
Avg. height of water above filter media (h _f) (max. 0.5 ft	=	0.50	ft
Design filter bed drain time (t _f)	=	2	days

4. Calculate required bioretention surface area (A_f):

Surface area
$$(A_f) = \frac{WQv \times d_f}{k (h_f + d_f) (t_f)}$$

		Required Surface Area (A _f)	=	1,901 ft ²
5.	Bioretention surface area pro	ovided	=	2177 ft ² (design)
6.	Water Quality Volume provide	ed	=	5225 ft3 (design)
7.	Is Bioretention Basin Lined o	r in HSG C/D Soils		Yes
8.	Runoff Reduction Volume pro	ovided	=	2090 ft3 (design)

Appendix 8 Tree Counts

					Total	Mountain Ash	Aspen	Striped Maple	Balsam Fir	Hemlock	Red Oak	Basswood	Red Maple	Red Spruce	Ironwood	Black cherry	White ash	White birch	Yellow birch	Beech	Sugar Maple				
							The state of the s			7.70%							- Tilliander							Community	
					136.9	0	0	68.5	39.4	0	0	0	0	0	0	0	0	29	0	0	0	3-4" dbh	Pioneer HW	Α	
					178	0	0	11.2	22	0.6	0	0	0	1.9	0	0	0	130.2	1.7	0.5	9.9	>4" dbh			
					134.7						30.9		14.6							8.2	81	3-4" dbh	Mixed HW	В	
					237.8				6.8		11.8		27.7	10.4		6.5		24.4	4.9	20.2	125.1	>4" dbh			
	7.47.50				68.2										7					39.2	22	3-4" dbh	North HW	С	
					193.1					0.1	9.9	0.6	4.4	0.4	4.3	0.4	8.9	6	16.8	22.2	119.1	>4" dbh			
					176.9				27.6				6.1		6.1		12.1		12.1	18.2	94.7	3-4" dbh	Mixed HW	D	
					211.3		19.7	- Control of the Cont	4.9	5.4		9.2	20.9			2.7	7.4	24.5	27.4	25.8	63.4	>4" dbh			
			11100		286.7						10.5								10.5	189.2	76.5	3-4" dbh	Mixed HW	ш	
		n. d e e e			357.8		3.4	6.6		T Solidania	14.7		28.4					33.5	11	197.2	63	>4" dbh	TELEVISION OF THE PERSON OF TH		

db db 3.9 3.9 3.9	Not Used >4" dbh 3-4" dbh >4" dbh 129.7 40.4 38.7 1.9 13.9
	Not Used 3-4" dbh
J SF & PH h 3-4" dbh 109.8	

	700	7 >					
		3		Z	İ	0	
7		SF & PH		North HW		Not used	
3-4" dbh >4" dbh 3-4" dbh	dbh >4" dbh	า 3-4" dbh	>4" dbh		>4" dbh		>4" dbh
Sugar Maple			39.8	68	280.1		
				144.7	72.1		
White hirch 100 2 53		217	70				
		F+,	ò	88	ر د		
Black cherry				G			100
Ironwood							
Red Spruce 12.8 14.9			38.4		9.5		
Basswood							
			147				
Balsam Fir 263.8 337.4		159.5	101.8				
Striped Maple		57.5	44.2				
			18.3				
Mountain Ash 12.8 5.7	0000						
398.6 411	0 0	434	320.5	280.7	364.8	0	0

Total	Mountain Ash	Aspen	Striped Maple	Balsam Fir	Hemlock	Red Oak	Basswood	Red Maple	Red Spruce	Ironwood	Black cherry	White ash	White birch	Yellow birch	Beech	Sugar Maple				
																			Community	
38.3										7.7					15.3	15.3	3-4" dbh	North HW	Р	
177			2.5			0.9	5.9	0.4		6.8		4	0.6	10.6	39.7	105.6	>4" dbh			
115.1			28.8	43.1									28.8	14.4			3-4" dbh	Pioneer HW	Q	
262.2	9.2		17.4	38.9				24.1	32.9				108.4	31.3			>4" dbh			
86.4			28.8												28.8	28.8	3-4" dbh	North HW	R	
234.4									1.8					16.2	25.1	191.3	>4" dbh	`		

Table 20	17 Manageme	nt Actions T	ree Cutting	2017 Management Actions Tree Cutting by Community Type and Location	and Location	
GORE IUA						
	Community	В		Trail 11-0	Trail 11-0	Trail 11-0
		Mixed HW		4.2 acres	4.2 acres	4.2 Acres
		3-4" dbh	>4" dbh	3-4" dbh	>4" dbh	Total
Sugar Maple		81	125.1	340.2	525.42	865.62
Beech		8.2	20.2	34.44	84.84	119.28
Yellow birch			4.9	0	20.58	20.58
White birch			24.4	0	102.48	102.48
White ash				0	0	0
Black cherry			6.5	0	27.3	27.3
Ironwood				0	0	0
Red Spruce			10.4	0	43.68	43.68
Red Maple		14.6	27.7	61.32	116.34	177.66
Basswood				0	0	0
Red Oak		30.9	11.8	129.78	49.56	179.34
Hemlock				0	0	0
Balsam Fir			6.8	0	28.56	28.56
Striped Maple				0	0	0
Aspen				0	0	0
Mountain Ash				0	0	0
				565.74	998.76	
					SUBTO	TAL 1564.5

GORE IUA Community E Trails 110,11A, 1N-P Chalce		4447.05	SUBTOTAL					
IUA Community E Trails 110,11A, 1N-P Trails 110,11A, 1N-P Community E Trails 110,11A, 1N-P Community E Community C	,		2468.82	1978.23				
IUA Community E Trails 110,11A, 1N-P G.9 acres Maple 76.5 63 527.85 43.47		0	0	0			12.00	Mountain Ash
IUA		23.46	23.46	0	3.4			Aspen
IUA		45.54	45.54	0	6.6			Striped Maple
IUA Community E Trails 110,11A, 1N-P Trails 110,11A, 1N-P Community E Trails 110,11A, 1N-P Trails 110,11A, 1N-P Community E Community Community E Community Community Community E Community Commun		0	0	0			To the second se	Balsam Fir
IUA Community E Trails 110,11A, 1N-P Trails 110,11A, 1N-P Trails 110,11A, 1N-P Trails 110,11A, 1N-P		0	0	0				Hemlock
IUA Community E Trails 110,11A, 1N-P Trails 110,11A, 1N		173.88	101.43	72.45	14.7	10.5		Red Oak
IUA Community E Trails 110,11A, 1N-P Trails 110,11A, 1N		0	0	0				Basswood
IUA Community E Trails 110,11A, 1N-P Trails 110,1A, 1N-P Trails 110,1A, 1N-P Trails 110,1A, 1N-P T		195.96	195.96	0	28.4			Red Maple
IUA Community E Trails 110,11A, 1N-P Trails 110,11A, 1N		0	0	0				Red Spruce
IUA Community E Trails 110,11A, 1N-P Trails 110,11A, 1N		0	0	0				Ironwood
IUA Community E Trails 110,11A, 1N-P Trails 110,11A, 1N		0	0	0			- 100 ()	Black cherry
IUA E Trails 110,11A, 1N-P Trails		0	0	0				White ash
IUA E Trails 110,11A, 1N-P Trails		231.15	231.15	0	33.5			White birch
IUA E Trails 110,11A, 1N-P 4.9 acres	Ti di	148.35	75.9	72.45	11	10.5		Yellow birch
Community E Trails 110,11A, 1N-P 4.9 acres 4.9 acr		2666.16	1360.68	1305.48	197.2	189.2		Beech
Community E Trails 110,11A, 1N-P Trails 110,11A, 1N-P		962.55	434.7	527.85	63	76.5		Sugar Maple
Community E Trails 110,11A, 1N-P Trails 110,11A, 1N-P Mixed HW 6.9 acres 6.9 acres		Total	>4" dbh	3-4" dbh	>4" dbh	3-4" dbh		
Community E Trails 110,11A, 1N-P Trails 110,11A, 1N-P	The state of the s	6.9 Acres	6.9 acres	6.9 acres		Mixed HW		
GORE IUA		Trails 110,11A, 1N-P	Trails 110,11A, 1N-P	Trails 110,11A, 1N-P		m	Community	
				The state of the s				GORE IUA

REIUA Community Q Twister Widen Total 4 Men Men<	AL 415.03	SUBTOTAL				-	
IUA Community Q Twister Widen 4.1 acres 1.1 acres 1.1 acres 4.1 acres 4.2 dbh 4.4 dbh 3.4 "dbh 4.4" dbh 4.4" dbh 7.4" dbh 4.4" dbh 7.0 dbh		288.42	126.61	000			
IUA Community Q Twister Widen Total Maple 11.4 31.3 34.74 31.68 11.1 acres 11.1 acres 10 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	10.12	10.12	0	9.2			Mountain Ash
Community Q Twister Widen Tuister Widen Twister Widen Tuister Widen Total 14.4 31.3 31.5 31.68 119.24 34.43 34.43 34.43 34.43 34.43 34.43 36.19 36.19 36.19 36.19 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 36.51 <td< td=""><td>0</td><td>0</td><td>0</td><td></td><td></td><td></td><td>Aspen</td></td<>	0	0	0				Aspen
Community Q Twister Widen Tuister Widen	50.82	19.14	31.68	17.4	28.8		Striped Maple
A Community Q Twister Widen Tuister Widen Twister Widen Tuister Widen Twister Widen Tuister Widen Twister Widen Tuister Widen Twister Widen Twister Widen Tuister Widen Tuister Widen Tuister Widen Tuister Widen Tuister Widen Tuister Widen Total Total aple 14.4 31.3 15.84 31.68 119.24 19.24 19.24 19.24 19.24 19.24 19.24 19.24 19.24 19.24 19.24 19.24 19.24 19.24	90.2	42.79	47.41	38.9	43.1		Balsam Fir
Community Q Twister Widen 1.1 acres 7 otal	0	0	0				Hemlock
Community Q Twister Widen 1.1 acres 7 octal 0 0 0 0 Total 7 octal 1.1 acres 1.1 acres 1.1 acres 1.1 acres 1.1 acres 24" dbh 4" dbh 4" dbh 7 octal 7 octal 7 octal 0	0	0	0				Red Oak
Community Q Twister Widen Tuister Widen Twister Widen Tuister Widen Twister Widen Tuister Widen Total ch 14.4 31.3 15.84 31.68 119.24 0	0	0	0				Basswood
Community Q Twister Widen Tuister Widen Total Total<	26.51	26.51	0	24.1		The state of the s	Red Maple
Community Q Twister Widen Tuister Widen Total	36.19	36.19	0	32.9			Red Spruce
Community Q Twister Widen 1.1 acres 10 0 0 Total Total Total 1.1 acres 10 0 0 Total Total 1.1 acres 1.1 acres 10 0 0 0 0 0 Total 1.1 acres 10 0 0 <th< td=""><td>0</td><td>0</td><td>0</td><td></td><td></td><td></td><td>Ironwood</td></th<>	0	0	0				Ironwood
Community Q Twister Widen 1.1 acres 1.1 acres 1.1 acres 1.1 acres 1.1 acres 1.1 acres Total	0	0	0				Black cherry
Community Q Twister Widen Total 1.1 acres 1.1 acres 1.1 acres 1.1 acres 1.1 acres Total Total </td <td>0</td> <td>0</td> <td>0</td> <td></td> <td></td> <td></td> <td>White ash</td>	0	0	0				White ash
Community Q Twister Widen Twister Widen Pioneer HW 1.1 acres 1.1 acres 3-4" dbh >4" dbh >4" dbh 0 0 0 14.4 31.3 15.84 34.43	150.92	119.24	31.68	108.4	28.8		White birch
Community Q Twister Widen Twister Widen Pioneer HW 1.1 acres 1.1 acres 3-4" dbh >4" dbh 3-4" dbh 0 0 0	50.27	34.43	15.84	31.3	14.4		Yellow birch
Community Q Twister Widen Twister Widen Pioneer HW 1.1 acres 1.1 acres 3-4" dbh >4" dbh 3-4" dbh 0 >4" dbh	0	0	0	1 1 1 1			Beech
Community Q Twister Widen Twister Widen Pioneer HW 1.1 acres 1.1 acres 3-4" dbh >4" dbh >-4" dbh >-4" dbh	0	0	0			77.00	Sugar Maple
Community Q Twister Widen Twister Widen Pioneer HW 1.1 acres 1.1 acres	Total	>4" dbh	3-4" dbh	>4" dbh	3-4" dbh		
Community Q Twister Widen Twister Widen	1.1 acres	1.1 acres	1.1 acres	8	Pioneer H		
DRE IUA	Twister Widen	Twister Widen	Twister Widen		۵	Community	
	The state of the s	70.00					GORE IUA

GORE IUA	-					
	Community	P		Various (net)*	Various (net)	Various (net)
		North HW		15.4 acres	15.4 acres	15.4 acres
		3-4" dbh	>4" dbh	3-4" dbh	>4" dbh	Total
Sugar Maple		15.3	105.6	235.62	1626.24	1861.86
Beech		15.3	39.7	235.62	611.38	847
Yellow birch			10.6	0	163.24	163.24
White birch			0.6	0	9.24	9.24
White ash			4	0	61.6	61.6
Black cherry				0	0	0
Ironwood		7.7	6.8	118.58	104.72	223.3
Red Spruce				0	0	0
Red Maple			0.4	0	6.16	6.16
Basswood			5.9	0	90.86	90.86
Red Oak			0.9	0	13.86	13.86
Hemlock				0	0	0
Balsam Fir				0	0	0
Striped Maple			2.5	0	38.5	38.5
Aspen				0	0	0
Mountain Ash				0	0	0
				589.82	2725.8	
					SUBTOTAL	3315.62
*Community N =	= Various locations totaling 22.7	ions totalin	g 22.7 acres	- 7.3	acres of abandoned cutting from 1995 Maintenance Area and Lifts 9A and 9B	Naintenance Area and Lif
	The state of the s					

0						
0	3649.56	2924.34				
	0	0				Mountain Ash
34.68	34.68	0	3.4			Aspen
67.32	67.32	0	6.6			Striped Maple
0	0	0				Balsam Fir
0	0	0	**************************************		The state of the s	Hemlock
257.04	149.94	107.1	14.7	10.5		Red Oak
0	0	0			- Annual Control of the Control of t	Basswood
289.68	289.68	0	28.4			Red Maple
0	0	0				Red Spruce
0	0	0			77,000	Ironwood
0	0	0				Black cherry
0	0	0				White ash
341.7	341.7	0	33.5			White birch
219.3	112.2	107.1	11	10.5		Yellow birch
3941.28	2011.44	1929.84	197.2	189.2		Beech
1422.9	642.6	780.3	63	76.5		Sugar Maple
Total	>4" dbh T	3-4" dbh	>4" dbh	3-4" dbh		
10.2 acres	10.2 acres 1	10.2 acres		Mixed HW	7.7	
Lift and Trails 12	Lift and Trails 12	Lift and Trails 12		т	Community	T - Address
					dition	Land Swap Addition

Appendix 9 Gore Mountain Sustainability Analysis





This report is a summation of various aspects of Gore Mountain's environmental performance. The information will be regularly updated and utilized as we develop annual reports and master plans for the facility.

Gore Mountain recognizes the impact that climate change has on our environment, and potentially on the ski experience we provide. We are an industry leader in environmental stewardship; our consistent commitment to sustainability can be noted not only throughout our responsible development practices, but also through the industry's recognition of Gore with several prestigious awards in this area. We voluntarily reviewed our entire operation in this report to demonstrate how we have improved, and where we can continue to improve.

As the largest ski area in New York State, we can play an active role in helping to change the culture toward a more sustainable future. We have improved our efficiencies and transferred our electric loads from traditional supply to solar power. We will continue modernizing our snowmaking system and greening our on-road and grooming fleets. We are working towards a hydroelectric generation system, composting our food waste, and expanding our educational programs.

Gore Mountain works closely with the Department of Environmental Conservation (DEC) to maintain the health of the environment at our facilities. The DEC has issued environmental permits to Gore Mountain for Bulk Petroleum Fuel Storage, Wastewater Treatment Facility Operations, Water Withdrawal, Dam Safety, Stormwater Management, and Air Emissions. We have expanded our educational programs and are developing plans for both a hydroelectric generation system and food waste composting.



03 | ELECTRICITY & FUEL

Diesel, Gas, & Propane Electricity Emissions Solar Hydroelectric

№ 09 | WATER

Potable Water
North Creek Reservoir
Hudson River
Wastewater
Stormwater
Water Conservation

12 | WASTE MANAGEMENT & RECYCLING

Waste Repurposing Single-Stream Recycling Precious Metal Recycling Hazardous Waste Food Waste

15 | HERITAGE & EDUCATION

Visual Resource Management Environmental Awareness Timeline of Progress









Diesel

Diesel is a major energy source for our operation. We use diesel for powering maintenance equipment, snowmaking compressors, and grooming equipment. Diesel operates the ski lifts during power outages and also fuels trucks and buses.

Over the past eight fiscal years, our usage of off-road diesel has decreased significantly and a future trend forecasts that this shift will continue (See Figure 1.1).

Our on-road diesel usage has had a slight average increase over the past eight fiscal years (See Figure 1.2). We correlate this to the amount of vehicles and equipment in our control, including the shuttle bus fleet. This increase was necessary to accommodate our growing number of guests, trails, and other expansion projects. We are actively investigating modernization of existing fleets with new technologies such as electric grooming machines and hybrid buses. Revised shuttle routes will help to conserve energy during busy days, and we are researching alternative fuels for the vehicles we presently own.






Figure 1.1: Off-road diesel usage over the past 8 fiscal years




Figure 1.2: On-road diesel usage over the past 8 fiscal years




Figure 1.3: Gasoline usage over the past 9 fiscal years




Figure 1.4: Propane usage over the past 8 fiscal years

Gasoline

Gore Mountain uses gasoline to operate snowmobiles for ski patrol and snowmaking operations. Gasoline is also used to attend trade shows, meetings, and conferences in our vehicles. Our use has been fluctuating over time, but overall there is a slight downward trend. (See Figure 1.3).

Propane

Our propane usage had a dramatic increase after the 2007/2008 fiscal year due to the addition of the Northwoods Lodge, conversion of the Base Lodge's heat from fuel oil, and the addition of two more commercial kitchens. Propane is used to heat almost all of Gore Mountain's buildings, with the exception of the Saddle Lodge which uses a wood stove and electric heat. The usage trend for propane is relatively flat and primarily dependent on the weather. (See Figure 1.4) A green heat initiative is targeted for future improvement in propane use reduction.





Electricity

While electricity powers the lifts, the largest use of it is for snowmaking compressors and pumps. We have substantially reduced the amount of kilowatt hours (kWh) used during the last four fiscal years and we plan to maintain this trend by continuing to replace traditional snowmaking with modernized, high-efficiency guns. We are also modernizing our compressors with improved, more efficient drives and changing most lighting to motion sensing and high-efficiency bulbs or LEDs. (See Figure 1.5)




Figure 1.5: Kilowatt Hours used over the past 4 fiscal years

Emissions

Every year we measure the carbon and nitrate emissions directly expelled from Gore Mountain's use of electricity. The lifts, lodges, snowmaking operations, and larger buildings are measured. There is an upward trend over the past six fiscal years for both of the emissions sources (See Figures 1.6 and 1.7). We are actively lessening this impact through a conversion to solar power.




Figure 1.6: Carbon and Nitrous emissions from all measured sources over the past 6 fiscal years








Solar

Gore Mountain signed two 25-year solar power purchase agreements in June 2015. 14,589 panels have since been installed spanning 20 acres, with their energy production scheduled to go online in summer 2016. The electricity generated, a combined 5.325MWdc, will credit Gore's meter at a rate higher than power that is traditionally sourced, and will offset approximately 85% of the mountain's energy use. The agreements are projected to save Gore approximately \$10M over the life of the contract, while providing a cleaner, more sustainable source of energy to Gore Mountain's electric distribution zone.





Hydroelectric


Gore Mountain has conceptually designed and is seeking capital funds for a hydroelectric plant on site using the existing Hudson River snowmaking water transmission system. It is estimated that the plant will generate 1,380,000 million kWh annually by passively utilizing natural water resources.

Gore Mountain has an advanced, sophisticated system of water storage, transportation, and control that is currently used only 3 months of the year. Capitalizing upon this infrastructure throughout the year could provide economic opportunities and bolster the mountain's sustainability.

Installation of a hydroelectric turbine and generator could almost completely offset the cost and emissions of electricity required to run the Hudson River pumps, all from naturally collected rainwater that otherwise pours over a dam and is not presently generating energy.

This system would provide yearly benefits up to \$118,700 for the foreseeable future, and would pay for itself within 8 years. Additional tax credits of \$15,200 could also be available.

If non-renewable energy costs continue to rise, this system will return even higher percentages of the initial investment.







Potable Water


Gore Mountain's treated water is provided by its own non-transient, non-community potable water system. There are two developed wells, one in the Base Area that produces 70 gallons per minute, and another at the Saddle Area that produces 5 gallons per minute. Both systems utilize holding tanks with chlorination pumps that are activated by flow. The chlorine residuals are monitored and recorded daily. Analytical reports are filed monthly with the NYS Department of Health. The Ski Bowl Lodge's potable water is serviced by the North Creek Water District.

North Creek Reservoir

The North Creek reservoir is a 25-million gallon upper elevation water source used for snowmaking since 1975. The reservoir was originally built as a Work Progress Administration project for the North Creek Water District. The reservoir is above Roaring Brook, an intermittent brook that flows into North Creek and then the Hudson River.

Hudson River

Gore Mountain withdraws water for snowmaking from the Hudson River. The pump house is located at the North Creek Train Depot. The established limit of 5,000 gallons per minute (GPM) is 1% of the record low flow at this location. The intake structure is designed to appear as a box culvert with a stream flowing into the river and has baffles and chambers designed to mitigate carryover effects from pumping and draining. Each year, almost 300 million gallons of water are used in snowmaking.





Wastewater

The mountain's annual wastewater treatment permit is a State Pollutant Discharge Elimination System permit, which is designed to "eliminate the pollution of New York waters and to maintain the highest quality of water possible consistent with; public health, public enjoyment of the resource, protection and propagation of fish and wildlife and the industrial development within the state," according to the DEC's website.

Gore Mountain's operators monitor the wastewater produced. The normal testing parameters are volume, temperature, turbidity, dissolved oxygen, pH, biochemical oxygen demand, ammonia, suspended solids, settled solids and alkalinity. These tests are done on a daily basis and recorded for monthly submission to DEC. The waste sludge is trucked out periodically to a commercial wastewater facility. The plant has the capacity to process 70,000 gallons of wastewater per day but even at its peak, the mountain does not operate at 50% of design capacity.

Stormwater

Gore Mountain actively practices stormwater management techniques through proper implementation of Stormwater Pollution Prevention Plans developed individually for each construction project. During heavy construction, the project site and the water downstream are closely monitored to protect water quality. Gore Mountain also incorporates proper stormwater management devices into any new construction project to control runoff after construction projects are completed.

Water Conservation

Gore Mountain uses low flow water fixtures in the lodges. These fixtures use a high-pressure technique that produces an equal flow to that of older, less efficient models, but they use less water.

With tactical earthwork of smoothing and filling irregularities on terrain, Gore has had great success decreasing the amount of manmade snow required to open several trails. Earthen features built into runs such as our boardercross have also allowed some mountain areas to open more quickly, with less energy needed to do so.







WASTE MANAGEMENT & RECYCLING

Waste Repurposing

Gore Mountain has repurposed many items to keep material out of the waste cycle. The most high profile examples of repurposed, relocated items are the Topridge Triple, the Hudson Chair, the Village Chair, and the Bear Cub surface lift. Many of our buildings have been modernized and some have even been moved to continue utilizing these resources. Large repurposing projects include the Northwoods Lodge, which was converted from the loading barn of the historic 1967 gondola. Relocated buildings include the Mountain Adventure Buildings, both Ski Bowl yurts, and the operator buildings for the base of the gondola and Topridge lifts. Repurposed material has been used to construct the framework for the Fairview observation deck, safety bollards, corral posts, parking lot directional equipment, the Corduroy Café, and other specialty items.

Single-Stream Recycling

For the last four years, Gore Mountain has utilized a facility-wide single-stream recycling system. Single-stream recycling is a process in which materials are all mingled together with no sorting required by individuals.



Precious Metal Recycling

Our recycling has remained fairly constant. In fiscal year 2014/2015, we recycled an inordinately large amount of material due to a lift replacement that generated several tons of scrap metal.




Figure 1.10: Amount of material recycled over the past 4 fiscal years

Hazardous Waste

Gore Mountain generates some hazardous waste that must be disposed of properly and separately from the regular waste. Most of this waste is mercury from expired light bulbs. These light bulbs are temporarily stored in a sealed container by Gore Maintenance, then properly disposed of at a certified off-site facility.

Food Waste

Gore Mountain staff is researching compost systems in order to generate fertile soil from food waste. One option is an on-site composting pile or a composting tumbler. The compost would be initially generated from the kitchens' food waste, then secondarily from customer waste. The fertile soil produced would be used in gardens around the mountain and could also be spread on trails.

Gore Mountain and the Olympic Regional Development Authority have a corporate partnership with Centerplate to be their concession operator. Centerplate has transferred all of its cups and paper products used at the mountain to compostable and recyclable products. The amount of locally sourced foods and healthier options within Centerplate's offerings to Gore's guests is on the rise.



HERITAGE & EDUCATION

Visual Resource Management

A "gore" is a surveyor's term for an area of unsurveyed land. Gore Mountain was left off the area's earliest maps, likely due to the mysterious way the summit blends into the peaks surrounding it upon approach, as well as the natural ruggedness of the landscape. We have held true to this natural blend we have with our surroundings in our development of the ski resort as well. Examples of our award-winning performance in mitigating visual impact include:

- •The layout and appearance of the Northwoods Gondola, designed with low towers, a low-profile lift line that follows the natural contour of the land, and color scheme carefully selected to blend into its surroundings.
- •The appearance of the Hudson River Pump House and transformer at the Upper Hudson River Railroad station, painted Johnsburg Brown and designed to merge flawlessly into the depot facade.



•The appearance of the Hudson River Intake Structure, designed on the water's edge to appear as a box culvert from which a tributary would flow.


- •Gore's new lift and trail network at the North Creek Ski Bowl, designed using a layout virtually identical to its historic layout.
- •Constructing new buildings only in color schemes and architectural styles that match the natural environment, while renovating existing shells when possible to preserve open space and reuse materials.
- •The "Topridge Area," a pod of skiing that cannot be seen from any developed location.
- •Gore Mountain's new Nordic trail network, using existing terrain profiles and infrastructure to integrate new recreational opportunities with resources already available.

Environmental Awareness

Gore Mountain transforms every gondola ride into an educational opportunity with its unique Northwoods Knowledge program. Each cabin features a unique story about the area's ecology or heritage. Topics that guests can read about on their gondola rides include wildlife adaptations, the Great Camps of the Adirondacks, how mountains are formed, and the science of snow. Interpretive signage is also placed around the mountain and lodges for people to identify area peaks, learn about the environment, and discover the history of Gore.

Gore has hosted environmental field trips for area schools and is developing environmental activities to incorporate into summer programming.





Timeline of Progress

- 1934 The first snow train, carrying 378 winter enthusiasts, arrives in North Creek at 10:30am from Schenectady on March 4. Round trip \$1.50. The Ski Patrol was organized, led by Lois Perret. It was one of the first of its kind and served as a model for patrols all over the world.
- 1946 A 3000' t-bar is installed at the North Creek Ski Bowl, servicing 830 vertical feet.
- 1964 The primary Gore Mountain facility is opened by New York State on January 25. It features a j-bar, a t-bar, and for the more advanced, a double chair, the longest lift in the East.
- 1967 The first gondola in New York State is installed at Gore Mountain. It remains New York's only gondola until 1999.
- 1976 Gore Mountain installs its first snowmaking system on four trails: Sleeping Bear, Sunway, Showcase, and Cloud.
- 1984 Gore Mountain installs the "Adirondack Express." This high-speed triple is the only lift of its kind in the Eastern US.
- 1995 "The Rumor" opens on February 9. This trail has 70% pitch and is one of the steepest trails in the East, designed for experts only.
- 1996 Gore Mountain taps the mighty Hudson River for a snowmaking water source and quadruples snowmaking capabilities.
- 1999 The Northwoods Gondola replaces the 1967 "Old Red Gondola." The high-speed eight-passenger lift is named SKI Magazine's "Best New Lift" and transports guests to the newly developed summit of Bear Mountain.
- 2002 The Topridge Area is introduced with a lift and four new trails. Conveniently linking guests from the Straight Brook Valley to Bear Mountain's summit, Topridge transforms the Gore Mountain experience.
- 2003 Gore Mountain begins winter management of the town-owned North Creek Ski Bowl.
- 2006 "Ruby Run," a new easier-rated trail off the Northwoods Gondola is added, offering beginners 1700' vertical feet and 2.2 miles of continuous skiing and riding.
- **2007** Gore Mountain opens the new Northwoods Lodge. "Village Chair," the first-ever aerial chairlift at the North Creek Ski Bowl, is installed for day/night skiing and snowboarding.
- 2008 New terrain serviced by a high-speed quad opens on Burnt Ridge Mountain, increasing Gore's vertical to 2300'.
- 2011 Gore Mountain opens the "Hudson Chair," completing its interconnect with the Historic North Creek Ski Bowl on Little Gore Mountain, and further developing its fourth peak of terrain.
- 2014 The 1984 Adirondack Express is replaced with an all-new luxurious and high-speed detachable quad, AEII.
- **2016** Gore Mountain's 14,589 solar panels go live on the grid and offset 85% of the mountain's energy use.



Awards and Recognitions

In May 2016, Gore Mountain received the ski industry's most esteemed recognition for sustainable performancethe Golden Eagle for Overall Environmental Excellence, presented by SKI Magazine and the National Ski Areas Association (NSAA). Gore was chosen for consistent leadership on environmental stewardship enhancing the guest experience in creative ways that help both the planet and its business, with an emphasis upon initiatives accomplished during the last twelve months. Gore Mountain serves as an industry model for development, demonstrating that a growing resort (its acreage and uphill capacity have increased 131 percent and 142 percent respectively over the last 20 years) can at the same time be sustainable. Gore's commitment to solar energy, its steady investment in snowmaking efficiencies, strategic trail work to offset energy use, newly introduced service of locally sourced foods, replacement of traditional lighting with LED, and its environmental education initiatives all contributed to this esteemed award.

NSAA has also chosen Gore for past awards in the specific topics of Visual Resource Management, Environmental Education, and Environmental Group Relations. In addition, the mountain was a finalist for an award in Waste Reduction & Recycling.

Other honors include National Grid's 2014 nomination of Gore Mountain for a national energy conservation award, based on its efficiency upgrades. Demonstrating long-standing leadership in stewardship, Gore was one

of thirty presenters to the Environmental Concerns Task Force at the White House Conference on Travel and Tourism in 1995, and was one of twenty-four parties invited to participate the EPA's Sustainable Industry Mountain Resort Development Stakeholder Meeting in 1999.











Appendix 10 DGEIS Public Hearing Transcript

*** Proof of Publication ***

1.001 011 451
WARREN COUNTY AFFIDAVIT
STATE OF NEW YORK:
County of Warren, ss:
Donna Morehousebeing duly sworn,
says that (s)he is an authorized designee for Lee Enterprises, publishers of THE POST-STAR, a daily newspaper published in Glens Falls, Warren County, State of New York, and that the printer notice attached hereto was cut from the said POST-STAR, and that the said notice was published therein, namely
NS OTYMPIC Regional Development
JAn May 8 1 2018
THE LA GROUP LEGALS
40 LONG ALLEY
SARATOGA SPRINGS, NY 12866
ORDER NUMBER 38724
rigned this day of DANUANU, 2018
June Mark 2018
tworn to before me this, 20 \(\int \)

Notice of SEQRA Public Hearing

The NYS Olympic Regional
Development Authority will hold a Development Authority will note a public hearing on Wednesday January 24, 2018 at 7:00 PM in the Gore Mountain Base Lodge to receive public comment on the 2017 Amendment to the 2002 Gore Mountain Unit Management Plan /Draft Generic Environmental Impact Statement (UMP/DGEIS). Copies of the UMP/DGEIS are available for review at Gore Mountain, NYSDEC offices in Warrensburg and in Albany (Lands and Forests), at ORDA's Lake Placid office and at Johnsburg Town Hall in North Creek. The UMP/DGEIS is also available online at http://www.dec.ny.gov/lands/41866.html. New actions proposed at Gore Mountain in the 2017 UMP Amendment include the following; construct a new ski trail connecting Burnt Ridge and the Base Lodge, widen Echo and Twister trails, Widen Sunway and other green trails served by Lift 3, add a new triple or quad chair from Northwoods Lodge to Lower Sunway, construct dedicated shuttle lanes, expand the NYSEF building, reconfigure maintenance to place a groomer garage and fueling station adjacent to the Sunway Trail, enlarge the snowmaking reservoir, construct a single-track bike trail loop for the Town trail at the top of Little Gore, and develop a hiking center based out of the Northwoods Lodge. public hearing on Wednesday January 24, 2018 at 7:00 PM in the Gore center based out of the Northwoods Lodge.

Lodge.
The purpose and need for the UMP
Amendment is the on-going improvement and modernization of
facilities at Gore Mountain that will
add to the public accessibility,
increase user safety and enhance
recreational pursuits while simultarecreation computing with the Auditaneously complying with the Adiron-dack Park State Land Master Plan and Article XIV of the NYS Constitution.

and Article AIV of the NIS Constitution.

Oral and written public comments will be accepted at the January 24, 2018 public hearing. Written public comments may also be submitted before or after the public hearing until the public comment period closes on February 9, 2018. Written public comments can be submitted via mail to: Olympic Regional Development Authority, 2634 Main Street, Lake Placid, NY, 12946, attn: Department of Environment, Planning & Construction or electronically to: Gore_2017_UMP_comments@orda.org

PUBLISHED ON: 01/08/2018

BRIAN J. CORCORAN

Notary Public - State of New York No. 01CO6133976 Qualified in Saratoga County My Commission Expires September 19, 2021

TOTAL AD COST:

57.98

FILED ON:

1/3/2018

1	
2	
3	
4	
5	SEQRA PUBLIC HEARING
6	NYS Olympic Regional Development Authority
7	
8	
9	
10	
11	January 24, 2018
12	7:00 p.m.
13	Gore Mountain Base Lodge North Creek, New York
14	
15	
16	
17	
18	Contact: Kevin Franke
19	The LA Group 40 Long Alley
20	Saratoga Springs, New York 12866 518-587-8100
21	kfranke@thelagroup.com
22	
23	

1 2 PROCEEDINGS: 3 MR. PRATT: Thanks for attending 4 tonight's presentation. I'm Mike 5 I'm the president of the Pratt. 6 Olympic Regional Development Authority 7 and former manager of Gore. This is a powerful presentation 8 9 tonight. Our plans here for updating 10 our Unit Management Plan are not traditional. They also include plans 11 to develop lands of the Town of 12 13 Johnsburg at the North Creek Ski 14 Bowl. So, simultaneously, we're 15 going through the SEQRA process, 16 trying to make amendments to our Unit 17 Management Plan, as well as complete our Section 814 Adirondack Park 18 19 Agency application so that we gain 20 permits for both projects 21 simultaneously. 2.2. So we've been working very hard 23 on these projects. Everybody at Gore

has been contributing. People at the Olympic Authority have been contributing, and we've been supported by our friends at the LA Group. So right now I certainly would like to thank all the staff people that have been helping us out, and I'll recognize Kevin Franke from the LA Group who will kind of explain the reasons for this public hearing tonight and the SEQRA process.

What we're going to have is, after Kevin speaks, Gore's general manager, Bone Bayse, will give a presentation of the plans and we'll certainly give everyone an opportunity to make comments.

As part of the SEQRA process, this public hearing is designed for us to accept your comments, not necessarily designed to be a question and answer session, but if there's simple answers we can provide, we're

1 happy to do that. And certainly 2 after the presentation, we'll be 3 around for a little bit if anyone 4 wants one-on-one questions. 5 All right. Kevin Franke. 6 MR. FRANKE: Thanks, Mike. Just 7 a few procedural issues to get out of the way before Bone gives the 8 9 presentation on the content of the 10 UMP. 11 Tonight's public hearing is 12 being held in accordance with the 13 State Environmental Quality Review 14 Act and Article 8 of the Conservation The document that's been issued 15 Law. 16 today is a Draft Unit Management 17 Plan, Draft Environmental Impact 18 Statement. Comments that we receive 19 tonight and comments that we'll 20 receive throughout the comment period 21 will all be addressed in the Final 2.2. UMP, Final Environmental Impact 23 Statement.

Most of you saw on the way in, there is a sign-up sheet for those who wish to speak. Emily has that. We'll be calling up speakers from that list. We do have a stenographer here tonight to get an accurate record of the hearing, so we'd ask that when you first start your comments that you restate your name so Kelly, our stenographer, can get that down for the record.

In addition to the comments that we receive tonight, the public comment period will remain open until February 9th. Written comments can be submitted by e-mail or by regular mail. There are addresses, both written and e-mail, where those comments can be submitted on sheets here on the front table. I believe Emily also has a copy, as well, and that information will also be up on the screen at the end of Bone's

2.2.

1 presentation.

Copies of UMP. Where can I get a copy? There are hard copies in a number of locations. Bone has a copy here at Gore Mountain. There's one down in Town Hall. There's one at the DEC offices, both in Warrensburg and in Albany. And for those who are closer to Lake Placid, there's one at the ORDA offices in Lake Placid.

The notice of this public
hearing was published in the
Environmental Notice Bulletin on
January 10th, 2018. There was a
legal notice announcing this public
hearing that was published in the
Post-Star on January 8th, 2018.

As part of this procedural matter, I'd just like to read into the record the public notice, and then we'll turn it over to Bone for his presentation.

Notice of SEQRA Public Hearing.

2.2.

1	New York State Olympic Regional
2	Development Authority will hold a
3	public hearing on Wednesday, January
4	24, 2018 at 7:00 PM in the Gore
5	Mountain Base Lodge to receive public
6	comment on the 2017 Amendment to the
7	2002 Gore Mountain Unit Management
8	Plan/Draft Generic Environmental
9	Impact Statement (UMP/DGEIS). Copies
10	of the UMP/DGEIS are available for
11	review at Gore Mountain, NYSDEC
12	offices in Warrensburg and in Albany
13	(Lands and Forests), at ORDA's Lake
14	Placid office and at Johnsburg Town
15	Hall in North Creek. The UMP/DGEIS
16	is also available online at
17	http:www/dec/ny/
18	gov/lands/41866.html.
19	New actions proposed at Gore
20	Mountain in the 2017 UMP Amendment
21	include the following: Construct a
22	new ski trail connecting Burnt Ridge
23	and the Base Lodge, widen Echo and

Twister trails, Widen Sunway and the other green trails served by Lift 3, add a new triple or quad chair from Northwoods Lodge to Lower Sunway, construct dedicated shuttle lanes, expand the NYSEF building, reconfigure maintenance to place a groomer garage and fueling station adjacent to the Sunway Trail, enlarge the snowmaking reservoir, construct a single-track bike trail loop for the Town trail at the top of Little Gore, and develop a hiking center based out of the Northwoods Lodge.

The purpose and need for the UMP Amendment is the on-going improvement and modernization of facilities at Gore Mountain that will add to the public accessibility, increase user safety and enhance recreational pursuits while simultaneously complying with the Adirondack Park State Land Master Plan and Article

2.2.

1	XIV of the NYS Constitution.
2	Oral and written public comments
3	will be accepted at the January 24,
4	2018 public hearing. Written public
5	comments may also be submitted before
6	or after the public hearing until the
7	public comment period closes on
8	February 9, 2018. Written public
9	comments can be submitted via mail
10	to: Olympic Regional Development
11	Authority, 2634 Main Street, Lake
12	Placid, NY, 12946, Attn: Department
13	of Environmental Planning and
14	Construction, or electronically to
15	Gore.2017_UMP_comments@orda.org.
16	Again, thanks for coming out
17	tonight. We appreciate your interest
18	and your comments. Bone.
19	MR. BAYSE: Thank you, Kevin.
20	Thank you, Mike.
21	Hello everybody and thanks for
22	coming out this evening for tonight's
23	presentation. I'm going to walk you

through these slides, and, as both

Mike and Kevin had mentioned, at the
end, you'll have plenty of
opportunity to make comments.

So the Master Plan goals for Gore are listed here and what we're trying to do is make our venues more desirable for recreational quests, athlete training and hosting premiere events, modernize the aging facilities and infrastructure, continue energy efficiency improvements, improve operational efficiency, increase competitiveness in our marketplace, explore potential for and increase development of year-round and summer attractions, improve quality and diversity of recreational facilities and attract more visitors, including the younger and the next generation. And so, working off of that master plan is what brings us into those 2017

20 more vi 21 and the 22 working 23 what br

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

amendments to our 2002 plan.

The proposed action overview -this is an overview and we'll keep getting into more details as we go construction, trail widening, lift improvements, enlarge our snowmaking reservoir, construct an independent shuttle lane -- and that's a modification of an already approved 1995 UMP, and build a new grooming garage and fueling station, which is also a modification of an approved 1995 UMP, an expansion on the NYSEF building -- that's our race facility

This also includes a request for a land reclassification that involves the Gore Mountain intensive use area, the Vanderwhacker Mountain Wild Forest, and the Siamese Ponds Wilderness. We're also looking to expand summer recreation operations

at the North Creek Ski Bowl and that would include a zip coaster, ropes courses, mini golf, hiking and mountain biking at that location.

This map right here shows you an overview of the entire facility, just to give you an idea of where we're looking to make these improvements, and then we'll get into some closer slides. But down here you see where our new proposed shuttle lane is, and that's along the access road, and then in through our parking lots into the base area.

Lift and trail improvements at our beginner area, which is the Sunway Lift area and the Poma Lift area if you're familiar with skiing here. An intermediate trail — a new intermediate trail on the Burnt Ridge area of the mountain, an expansion of our snowmaking reservoir, a potential land reclassification — and I

1 mentioned that a couple moments ago. 2 And that would be, this piece of land 3 here would become wilderness. This 4 here would become part of the 5 intensive use of the ski area. And 6 then this area here, which are the 7 lands of the Town of Johnsburg, the Ski Bowl. 8 9 Okay. First closeup slide. 10 This is the beginner area where we're 11 looking to do some improvements. 12 Again, if you're familiar with the 13 ski area now Lift 3 or our Sunway 14 Lift terminates right here. We're 15 looking to replace and extend that Sunway Lift to go across the Sunway 16 17 Trial into that area. We believe 18 this will give us a better experience 19 for our customers, a better unloading 20 area. It gives them an 21 opportunity -- I don't know if you're 2.2. familiar with beginner skiers, but 23 they can sometimes have a tough time

getting their act together. When they get off the lift, they're kind of wobbly. This will allow them to have a better staging area.

The green shaded areas are where we're proposing to widen the trails in this area, again, to make a better experience for our beginner skiers.

Down here is the Poma Lift, and there's where it currently ends.

We're proposing to put a new lift there that would go all the way to the bottom of that lower Sunway area, and that would give a really nice experience, again, for our beginner and advanced beginner skiers.

Over onto the Burnt Ridge area.

This is the top of the Burnt Ridge

Lift for reference. And these shaded

areas are previously approved trails,

just so you can see what's out there.

But what we are proposing is to add a

new trail right here. This will give

2.2.

another much needed access to the base area. And when it goes towards — especially when you're talking about the inner connect from Gore over to the main base area here, the middle part of this proposed trail has already been approved — previously approved where that's shaded. And just this top section and the bottom section are new actions that we're looking to take to get that trail.

This slide brings us over to the base area and that's kind of where we —— well, it's definitely where we are right now. And this shows us the proposed shuttle bus lane. And what that shuttle bus lane would do, that would be separate from the general traffic flow. We found that our busy days here continue to get busier and a problem we have is that our shuttle busses get caught in that traffic,

people coming up the road and going through the parking lot. So with a dedicated shuttle lane, we feel that we can keep the traffic flow going much smoother and make a much more positive experience for our customers.

Also, over here you can see where our new grooming garage is identified, where we would like to put that. In the previous UMP approval, it was to replace the existing grooming garage, so the only change is moving to a different location. And what this will do for us is put the grooming tractors closer to snow. And that will help quite a bit on maintenance, when those machines don't have to come down a gravel dirt road to get into the garage. They'll be able to come right off of the snow into the garage and back out onto the snow.

and back out onto

Court Reporting Services of Kelly Wegg Joseph
(518) 506-8017 kwjsteno@gmail.com

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

2.2.

And then the NYSEF building expansion. This is where the NYSEF building is and that's where that would be expanded.

This slide shows the request for land reclassification from the Gore Mountain Intensive Use Area to Siamese Ponds Wilderness Area. And we're requesting that this area here be reclassified. And this is currently part of the Vanderwhacker Mountain Wild Forest and we would like to have that reclassified as intensive use area, which is the ski area classification.

This slide here shows us our Ski Bowl improvements that we would like to make. This top area, we're just looking at that piece of land that we would like to be reclassified. If we were granted that reclassification, we're proposing to realign the Hudson Chair and have it terminate up here.

1	Currently it terminates down here.
2	That lift would come up here and we
3	would replace that lift with a
4	detachable chair. The shaded areas
5	show previously approved ski trails.
6	The lighter green areas show proposed
7	ski trails that would tie into those
8	previously approved.
9	Up here is our reservoir and the
10	light blue areas show where we are
11	proposing to enlarge the reservoir.
12	Summer and winter operation
13	improvements at the Ski Bowl include
14	a zip coaster, and that's on the next
15	slide. This gives you the overview.
16	Let's just jump to that. There.
17	It's a little bit closer for everyone
18	to see. This zip coaster is in
19	purple. We're proposing to put that
20	in there, along with a high ropes
21	course.
22	We're proposing to extend the
23	Village Chair. Currently the Village

Chair ends right there. We're looking to extend that up into this area, which puts it up high on the Moxham Trail. We're looking to extend the lights up there. This will give a much better nighttime skiing experience and it will also give people ski lift access to the ropes courses.

Down here we're looking to put summer and winter tubing and a permanent mini golf course. mentioned in the previous slide about realigning the Hudson Chair. That shows that there again. If that land reclassification was not granted to us, then we would keep the existing alignment of that lift, but still planning on changing the lift from a fixed grip to a detachable chair. The detachable chairs are easier for summer traffic for people to load and offload, as well as mountain bikes.

They're easier to load and offload on 1 2 those. And that would make it a much 3 nicer customer experience in the 4 summer. And if you haven't been to 5 the top of this area, the views of 6 downtown North Creek are spectacular. 7 We're also planning to continue actions approved in previous UMPs. 8 9 We're going to continue trail 10 development and trail widening, lift 11 improvements, lodge improvements and 12 expansions, parking improvements, 13 snowmaking modernization and energy 14 efficiency improvements, infrastructure modernization and 15 16 energy efficiency improvements. 17 We're going to continue to 18 improve and develop compatible 19 recreation amenities and public 20 access, and we'll also continue to 21 develop and improve a strong 2.2. connection between Gore, the Ski Bowl

and the Village of North Creek.

1	So that is the presentation in a
2	nutshell. I've shown you all the
3	_
	slides and told you what we're
4	planning on doing. This slide here
5	gives you some more information.
6	Kevin had mentioned where you can get
7	copies of the UMP. It's also
8	available online. This gives you
9	some addresses here if you want to
10	send in written public comment.
11	And so at this time we're did
12	Kevin go? There he is. At this
13	time, we would start with the public
14	comment.
15	MR. FRANKE: And I would just
16	remind people, if you are going to
17	speak, please state your name for the
18	record so the stenographer can get
19	that down.
20	FROM THE FLOOR: Can we ask
21	questions first?
22	MR. BAYSE: Let's go through the
23	public comment.

1 FROM THE FLOOR: Hi everyone. 2 I'm Rick Morris. I know most of you. 3 I've skied at Gore for about 40 years. 4 I love Gore. It's my home mountain. 5 I love some of the work that's been 6 done here in the past. Great job for 7 Mike and great job for Bone for keeping it up, and everyone else here. 8 9 And I also like the existing 10 hiking trails and backcountry ski 11 trails and snowshoe trails in the 12 area, and I've worked hard to help 13 build some of these trails. 14 worked hard to help maintain them, as 15 have a lot of other people here. 16 I would like for Gore to be able to 17 expand as it feels necessary, as well 18 as to protect the existing trail 19 system, which we have for the public 20 to use. 21 The Rabbit Pond Ski Trail gets a 2.2. lot of use spring, summer, fall and 23 It's an existing trail for winter.

quite a while now. And I just think there should be some way to both expand Gore and to protect the existing trail and to protect Rabbit Pond. And that's what I would like to see.

And what I have, I have a map here of the proposed expansion of Gore into the Rabbit Pond area and I have a map of the existing trails in the Rabbit Pond area, which I was able to get from North Creek for visitors to North Creek to use. what I haven't seen, and maybe this is my fault, in the UMP, I haven't seen a map showing both right on the same map and showing how the proposed new development would impact the existing trails. And it seems like, if you're going to put new trails in and have them coexist with existing trails, it would be important to be able to see where they both lie.

23

1

2

1 So that's my comments. Great 2 job to people at Gore. You've done a 3 fantastic job in the past. And I 4 would like to see new development 5 here at Gore, but just to also 6 protect what we already have. Thank 7 you. FROM THE FLOOR: Hi. I'm Dick 8 9 Carlson. Most people know me. 10 worked here at Gore for seven years, I 11 would like to say back in the day, on 12 the ski patrol. I worked at Garnet 13 Hill for 25 years and am associated 14 lately with the same group that Rick 15 works with, which is the Siamese Ponds 16 Trail Improvement Society, Upper 17 Hudson Trails Alliance. I work with Adirondack Trecks and so forth. 18 19 We're concerned with 20 trails-based recreation in the North 21 Creek area. And, you know, I would 2.2. like to preface my comments by 23 saying, if this is the least of our

problems, compared to some of the federal climate change, EPA, National Park Service and a host of other ones, I think we're indeed fortunate. This is not a huge deal in that respect.

That said, the Village of North Creek has very few hiking opportunities. And I have to discount hiking on ski trails and hiking on wide areas. There's really three main trails. The Schaeffer Trail, the Rabbit Pond Trail and the Raymond Brook Trail. And to, you know, utilize one little bit of added vertical for those trails that come down from the Rabbit Pond area, I think is misquided, especially if it will eliminate the Rabbit Pond Trail from hiking, snowshoeing and skiing in season. It's really a delightful trail. And it's an intimate hiking trail, like a regular trail you would

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

2.2.

see in the woods where the trees are quite close to you on both sides. So it's an important consideration, as well.

And the Hamlets to Hut

Initiative is using the Raymond Brook

Trail, which is right adjacent to the

Rabbit Pond Trail, for their premiere

trip, which is supposed to begin this

spring.

And, also, the North Country

National Scenic Trail is also -- I

think the signs are up already. The

Raymond Brook Trail is part of that.

And, again, the Rabbit Pond Trail

teases into all this and to have that

not be available anymore would be,

again, I think misguided.

The question I had, and I know that Crikelair property is some of the Alpine Trails that are proposed that are already approved. And I'm wondering, is this development on

1 Crikelair's property? Is it Town of 2 Johnsburg? Is it going to be ORDA 3 property? How is that all going to 4 work? 5 And I guess that's about all I 6 have, other than the questions. 7 Thanks. Thank you, 8 FROM THE FLOOR: 9 everyone. I'm Jill Broderick. I'm 10 one of twelve members of the ORDA 11 board of directors and I would like to 12 thank everybody for their help putting 13 I know -- I've this plan together. 14 been told it takes a lot of time and 15 it looked like there's 300-some pages 16 that I perused today. 17 So I don't have many notes, but 18 I am very happy with probably 19 80 percent of the plan. And like 20 Rick just said, and Dick just said, I 21 do have my reservations about the 2.2. Rabbit Pond reclassification of that 23 land, only because it's sensitive.

1	lot of people enjoy it just the way			
2	it is and I don't think it's I'm			
3	not sure if it's feasible, so I			
4	haven't seen the numbers and I don't			
5	really understand the realignment of			
6	the lift. Let me see. I have notes.			
7	If I may suggest adding to the			
8	master plan goals, I would include to			
9	improve and enhance the economy for			
10	the host benefit community of the			
11	Town of Johnsburg, and to improve the			
12	health and wellness for the residents			
13	by making recreational activities			
14	affordable and accessible.			
15	That's all I have. Again, thank			
16	you very much.			
17	FROM THE FLOOR: I'm Scott			
18	Robertson. I've lived here for 35			
19	years, taught, skied same with			
20	everybody else here, probably. And			
21	sorry. Okay.			
22	All the comments before, I echo			
23	one hundred percent. I really hope			

you guys can move the trail either back to where you originally had it or put in a trail -- I don't really like this idea too much, but if we have to compromise, maybe put in another trail to move around so we don't lose Rabbit Pond.

I've been going to the Huts and Hamlets meetings and doing a lot of these things and there's really exciting stuff going on in the backcountry. And, to be honest with you, that's what I live for and I have a lot of friends and that's what they live for, too.

I'd hate to lose this trail. I
think it would be a big mistake.
What I did, I spent a lot of time
using typographical maps and tried to
overlay your maps on there to see
exactly where the trails went, and it
looked to me like we're going to be
losing part of the trail. Maybe I'm

1 wrong about that, but if we do the 2 proposal, that's what it looks like 3 to me. And I think that would be a 4 huge mistake, so -- that's it. 5 MR. FRANKE: Anyone else? 6 FROM THE FLOOR: This is quick. 7 I'm Julie West. I live in North I've been here for a long 8 River. 9 time. Skied all over. 10 I have an idea. The summer 11 recreation idea at Little Gore I 12 think is really exciting. And right 13 at Little Gore we have these awesome 14 hiking trails and biking trails, so 15 if you take the portions -- the 16 Rabbit Pond area that the everyone is 17 concerned about and make it a winter 18 area, it kind of takes the glimmer 19 out of the summer recreational 20 opportunities that maybe some of the 21 family could be doing while the 2.2. others are on the zip lines.

thought.

1 My other concern is skier 2 numbers here at Little Gore. Do we 3 need more terrain at Little Gore? 4 just haven't seen the mountain even 5 open that much because of climate 6 change or whatever. We just don't 7 have the terrain or snow for it. 8 So that's what I wanted to say.

So that's what I wanted to say. Thanks.

FROM THE FLOOR: Okay. I'm Kelly Nessle. I really -- this is the first time I've paid any attention to this, so my question -- and it's really more of a question than a statement. We have -- the Town of Johnsburg has received money from the State of New York for a design of trails that leaves from Ski Bowl Park and goes up through to North River and then goes to other parts of the town. And that work is probably going to be starting sometime this year. And what I worry about is a collision between the

22 someti 23 about

9

10

11

12

13

14

15

16

17

18

19

20

interests of Gore Mountain and their 1 summer activities and the interests of 2 3 the Town of Johnsburg with their 4 hiking trails and their biking trails. 5 And I don't want the public that's 6 been coming already from Schenectady 7 and Vermont and everything else coming up here to bike, all of the sudden 8 9 they can't go on trails that we're 10 making because they are going to be 11 charged. And I don't know if that's 12 in the plans or not, but that would be 13 my concern. 14 MR. FRANKE: Does anyone else 15 have a comment? 16 FROM THE FLOOR: Brandon Himmoff. 17 First of all, I think it's a great 18 plan, and there's a tremendous asset 19 here of, you know, a great mountain 20 and there's a lot of revenue that, you 21 know, that the state and the community 2.2. will get out of it if the mountain 23 grows.

I think that there are a couple issues that I think the mountain is beginning to realize. I thought some of the commentary on like the pump capacity and stuff that I saw on the news was really very interesting.

But it seems to me that, like one of the key issues of the mountain is the connectivity of this side of the mountain here and getting to Burnt Ridge, and then using Burnt Ridge maybe as the key to getting down the mountain to the Ski Bowl.

The new route really helps a lot, I think, to connect Burnt Ridge back to the main part of the mountain — or historically the larger part of the mountain. And I wonder if maybe we can address solutions to get to the other side, because I don't think you really increase the skier numbers if the mountain is sort of disjointed. And

I think that there's a sort of design issue.

I mean, the mountain sort of is as it is. We just need to make trails to connect A to B. And it seems that, unless you kind of create some kind of tunnel going under the races going on at Echo all the time and Twister, which I guess those are certified as race courses and so there's not a whole lot you can do about that, but you still have to get people from one side to the other. I wonder if you could address how the plan can sort of make that happen.

And also related to all these expansions, I think the food strategy at the mountain needs to get addressed, because I think in order to address — I think locals are really interested in, we'll bring a picnic. We know how it is on the mountain. That's not so big an

issue. But I think to really attract tourists, you need a little more variety and high-class cuisine, and it's hard to do that under the current state contracts. And I just wonder if that could be addressed somehow.

I think that, you know, this idea of sort of improving local recreational health goes well beyond Johnsburg. Certainly, it's over in my area and really beyond that. It's great to get all these kids out here — and I'm really speaking on behalf of my seven—year—old and nine—year—old who love spending every Saturday and Sunday here whenever there's snow on the ground.

So I think the plan is terrific and really critical. And I also just wonder about the time frame of all these plans. There's about 20 years worth of projects probably in that

2.2.

Unit Management Plan and I was
wondering if someone can sort of
vaguely give their impressions of
which things are more of an urgent
priority and which things are longer
term priorities.

I think that's all. Thank you. FROM THE FLOOR: Okay. My name is Bob Nessle. To give you a little perspective, it was exactly 54 years ago in this very room when Gore Mountain Ski Center opened up. It was a terribly miserable day. Cold, windy, wet, icy. There was no snow but there was a lot of ice all over the mountain. Is this still working? And the next day I was hired on as a professional ski patroller and I've been here ever since.

Now, just right off the bat, one question about this skiing. I like the idea of the escape route off the top of Burnt Ridge. But how are you

21

2.2.

1	going to get over that the rock wall
2	that separates Sagamore and Echo?
3	You're going to blast a tunnel
4	through there? How are you going to
5	get out?
6	MR. BAYSE: I'll tell you all
7	about it after your comments.
8	FROM THE FLOOR: (Mr. Nessle)
9	The other thing is, the Ski Bowl Park,
10	there's no doubt about it that summer
11	activities expanded summer
12	activities are going to be fantastic
13	for the community, for the
14	recreational or the recreation menu
15	for the southern southeastern part
16	of Adirondack Park.
17	However, estimates have been
18	pushing 40,000 participants, and
19	whether that's just going to be
20	summer or summer and winter but
21	the word around the skiing industry
22	is that the summer activities at ski
23	resorts is sometimes greater in

fact, in many areas is greater than the wintertime.

Now, over at Ski Bowl Park, supposing you're going to manage 30,000 customers from June, when school is out, until say September, and then into the fall period a little bit. Now, how are the infrastructure problems going to be 30,000 people are going to solved? require a very complex and well -and an excellently designed sewer Now, there are three town system. wells within 200 feet of the base area of the Village slopes and the leg up -- the loading area for the Hudson Trail Lift and the new lift and the whole works. So depositing sewage in the aquifer is probably not going to work. I hope -- I certainly hope that it doesn't work. So that's part of the problem.

Also, where are all those people

going to park and what are they going to do when they come back off the zip line or the zip coaster or on the mountain coaster. And are they going to go to Joe Minder? Are they going to take a break in the pavilion?

But, once again, you're dealing with 30,000 people over the period of three or four months. That's another problem.

So there's still some work to be done, as I can see it, because, once again, we have to remember that Ski Bowl Park is not ORDA Ski Bowl Park. It's Town of Johnsburg Ski Bowl Park. Its basic design and its life since the 1920s has been to provide a place for Town of Johnsburg residents to recreate. And I think there's got to be some way to figure out a peaceful coexistence and take care of the sewage.

Thank you.

FROM THE FLOOR: Katy

Nightengale. I've been working with Gore for a while now updating the town contract, so I've got a lot of background on a lot of this stuff.

And I'm for a lot of everything they want to make at the main mountain and at the Ski Bowl, but I have concerns about the land swap.

I have skied those trails and they are really awesome. And there are already planned trails in existence to come down from the top of the Hudson Chair. I see economic development from both Gore and what they're doing for us at the main mountain and at the Ski Bowl, but I also see what's becoming this huge backcountry draw to ski backcountry. And I hate to lose those backcountry trails to be not accessible anymore for somebody who wants to ski up to ski down, so — that's it.

1 FROM THE FLOOR: Peter Bauer. Protect the Adirondacks. So thanks 2 for the opportunity. We've been going 3 4 through the draft. And just three 5 comments. 6 We, too, have a lot of concerns 7 about the land swap and the Rabbit Pond tract. We're not sure that's 8 9 the best way to go and we think 10 there's some major issues that need 11 to be looked at that we'll put in our 12 comments. 13 It has to do with backcountry 14 skiing and it has to do with -- we 15 think there's some legal issues 16 there, too, with the land that was 17 designated at the time of the constitutional amendment that wasn't 18 19 part of it. We're not sure it can be 20 added in. So we think there's some 21 issues to look at with the Rabbit 2.2. Pond tract. 23 We think the scheduling is

important. A lot of the unit
management plans for forest preserve
tracts that enumerate a bunch of
different activities schedule them in
five-year plans. ORDA hasn't always
done that with detail. DEC's always
done that with its unit management
plans and that would be very helpful.

I think there's an awful lot of good things in this plan to expand to mountain, a lot of upgrades of basic facilities and basic trails that are very important. And, certainly, there's a lot to support in that.

But we're concerned about Rabbit Pond.

We also would like to see better detail about the amount of acreage here at Gore, and also at White Face, but here at Gore, that has been used pursuant to the constitutional amendment that was approved, because we think you're getting very close to

1 your clearing limits. We would like 2 to see a real good accounting of the 3 methodology that ORDA is using about 4 the cleared areas, the cleared 5 acreage of trails, the width of trails and that sort of thing. 6 7 We've been looking at it independently and we think that 8 9 you're getting very close to your 10 limits. So I think that's something 11 you need to be very mindful about, so 12 we would like to see a really good 13 accounting of that. That's not 14 really a unit management plan issue, 15 but we think it's an important issue 16 going ahead because it affects your 17 trail upgrades and your trails. 18 Thank you. 19 MR. BAYSE: Excellent. So if 20 there aren't any other comments, we'll 21 be here for a while if anyone wants to 2.2. talk personally. 23 I will make a comment about the

1 Rabbit Pond, because I know that 2 seemed to be a resounding concern with folks. Any of the changes that 3 4 we have in there, the trails do not 5 encroach on the Rabbit Pond ski or 6 hiking trail. And it may be hard to 7 see a little bit on that map, but we feel pretty strongly that this area 8 9 needs to work in harmony with 10 backcountry access, ski lift access, 11 hiking, mountain biking. It's the 12 only way we can be successful in this 13 community, is to have as much of that 14 stuff offered as possible. So we're 15 not trying to close that out. 16 But, with that comment, thanks a 17 lot, everybody, for coming and we'll 18 be kicking around and hope to meet up 19 with you. 20 MR. FRANKE: Just for the record, the public hearing is closed for 21 2.2. tonight, but, just to remind people, 23 the public comment period for written

1	comments is going to stay open until
2	February 9th.
3	Thanks again for coming out and
4	we look forward to getting more
5	comments.
6	(Whereupon, the public hearing was concluded at
7	7:53 p.m.)
8	
9	
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	
21	
22	
23	

CERTIFICATION

I, Kelly Wegg Joseph, Shorthand Reporter and Notary Public in and for the State of New York, do hereby certify that the foregoing record taken by me at the place and date noted in the heading hereof is a true and accurate transcript of same to the best of my ability and belief.

1.0

Ketty Weyg Voseph

Dated: February 10, 2018

1	address [3] 33/19 34/14 34/20	Article 8 [1] 4/14
1	addressed [3] 4/21 34/19 35/6	as [22] 2/17 2/17 3/18 5/21 6/18
10 [1] 46/11	addresses [2] 5/17 21/9	10/1 11/4 17/13 19/23 19/23 22/14
10th [1] 6/14 12866 [1] 1/20	Adirondack [4] 2/18 8/22 24/18 37/16	22/17 22/17 22/18 26/3 33/12 34/4 34/10 36/17 39/12 44/13 44/14
12946 [1] 9/12	Adirondacks [1] 41/2	ask [2] 5/7 21/20
1920s [1] 39/17	adjacent [2] 8/9 26/7	asset [1] 32/18
1995 [2] 11/11 11/14	advanced [1] 14/16	associated [1] 24/13
2	affects [1] 43/16 affordable [1] 28/14	at [52] athlete [1] 10/9
20 [1] 35/22	after [4] 3/13 4/2 9/6 37/7	attending [1] 2/3
200 feet [1] 38/14	again [11] 9/16 13/12 14/7 14/15	attention [1] 31/12
2002 [2] 7/7 11/1 2017 [3] 7/6 7/20 10/23	19/15 26/15 26/18 28/15 39/7 39/13 45/3	Attn [1] 9/12 attract [2] 10/19 35/1
2017 [3] 7/0 7/20 10/23 2018 [7] 1/11 6/14 6/17 7/4 9/4 9/8	Agency [1] 2/19	attract [2] 10/19 33/1 attractions [1] 10/17
46/11	aging [1] 10/10	Authority [5] 1/6 2/6 3/2 7/2 9/11
24 [3] 1/11 7/4 9/3	ago [2] 13/1 36/11	available [4] 7/10 7/16 21/8 26/17
25 [1] 24/13 2634 Main [1] 9/11	ahead [1] 43/16 Albany [2] 6/8 7/12	awesome [2] 30/13 40/11 awful [1] 42/9
3	alignment [1] 19/18	В
	all [21] 3/6 4/5 4/21 14/12 21/2	
30,000 [3] 38/5 38/10 39/8 300-some [1] 27/15	26/16 27/3 27/5 28/15 28/22 30/9 32/8 32/17 34/8 34/16 35/13 35/21	back [5] 16/23 24/11 29/2 33/16 39/2 backcountry [7] 22/10 29/12 40/19
35 [1] 28/18	36/7 36/15 37/6 38/23	40/19 40/20 41/13 44/10
4	Alley [1] 1/19	background [1] 40/5
40 [2] 1/19 22/3	Alliance [1] 24/17	base [8] 1/13 7/5 7/23 12/14 15/2
40 [2] 1/19 22/3 40,000 [1] 37/18	allow [1] 14/3 along [2] 12/12 18/20	15/5 15/14 38/14 based [2] 8/13 24/20
41866.html [1] 7/18	Alpine [1] 26/21	basic [3] 39/16 42/11 42/12
5	already [7] 11/10 15/7 24/6 26/13	bat [1] 36/20
518-587-8100 [1] 1/20	26/22 32/6 40/12 also [23] 2/11 5/21 5/22 7/16 9/5	Bauer [1] 41/1 Bayse [1] 3/14
54 [1] 36/10	11/13 11/17 11/22 16/8 19/7 20/7	be [47]
7	20/20 21/7 22/9 24/5 26/11 26/12	because [9] 27/23 31/5 32/10 33/21
7:00 [2] 1/12 7/4	34/16 35/20 38/23 40/18 42/17 42/19 always [2] 42/5 42/6	34/19 39/12 42/22 43/16 44/1 become [2] 13/3 13/4
7:53 [1] 45/7	am [2] 24/13 27/18	becoming [1] 40/18
8	amendment [5] 7/6 7/20 8/16 41/18	been [20] 2/22 3/1 3/2 3/3 3/7 4/15
80 percent [1] 27/19	42/22 amendments [2] 2/16 11/1	15/7 20/4 22/5 27/14 29/8 30/8 32/6 36/19 37/17 39/17 40/2 41/3 42/20
8100 [1] 1/20	amenities [1] 20/19	43/7
814 [1] 2/18 8th [1] 6/17	amount [1] 42/18	before [3] 4/8 9/5 28/22
	announcing [1] 6/15 another [3] 15/1 29/6 39/9	begin [1] 26/9 beginner [6] 12/16 13/10 13/22 14/8
9	answer [1] 3/22	14/15 14/16
9th [2] 5/15 45/2	answers [1] 3/23	beginning [1] 33/3
A	any [3] 31/12 43/20 44/3 anymore [2] 26/17 40/21	behalf [1] 35/15 being [1] 4/12
ability [1] 46/7	anyone [4] 4/3 30/5 32/14 43/21	belief [1] 46/8
able [4] 16/21 22/16 23/12 23/23 about [21] 15/4 19/13 22/3 27/5	application [1] 2/19	believe [2] 5/20 13/17
27/21 30/1 30/17 31/23 34/12 35/21	appreciate [1] 9/17 approval [1] 16/12	benefit [1] 28/10 best [2] 41/9 46/7
35/22 36/21 37/7 37/10 40/9 41/7	approved [10] 11/10 11/13 14/20	better [6] 13/18 13/19 14/4 14/7
42/15 42/18 43/3 43/11 43/23	15/7 15/8 18/5 18/8 20/8 26/22 42/22	19/6 42/17
accept [1] 3/20 accepted [1] 9/3	aquifer [1] 38/19 are [40] 2/10 5/17 6/3 6/8 7/10 10/6	between [2] 20/22 31/23 beyond [2] 35/10 35/12
access [6] 12/12 15/1 19/8 20/20	13/6 14/5 14/20 14/22 15/10 15/16	big [2] 29/17 34/23
44/10 44/10	18/10 19/21 20/6 21/16 26/1 26/13	bike [2] 8/11 32/8
accessibility [1] 8/19 accessible [2] 28/14 40/21	26/21 26/22 30/22 32/10 33/1 34/9	bikes [1] 19/23
accordance [1] 4/12	34/20 36/4 36/5 36/23 37/4 37/12 38/8 38/10 38/13 38/23 39/1 39/4	biking [4] 12/4 30/14 32/4 44/11 bit [6] 4/3 16/18 18/17 25/15 38/8
accounting [2] 43/2 43/13	39/5 40/11 40/12 42/12	44/7
accurate [2] 5/6 46/7 acreage [2] 42/18 43/5	area [38] 11/19 12/14 12/16 12/17	blast [1] 37/3
acreage [2] 42/16 43/3	12/18 12/21 13/5 13/6 13/10 13/13 13/17 13/20 14/4 14/7 14/13 14/17	blue [1] 18/10 board [1] 27/11
act [2] 4/14 14/1		Bob [1] 36/9
action [1] 11/2	17/15 17/18 19/3 20/5 22/12 23/9	Bone [6] 3/14 4/8 6/4 6/21 9/18 22/7
actions [3] 7/19 15/11 20/8 activities [6] 28/13 32/2 37/11 37/12	23/11 24/21 25/17 30/16 30/18 35/12 38/15 38/16 44/8	Bone's [1] 5/23 both [9] 2/20 5/17 6/7 10/1 23/2
37/22 42/4	38/15 38/16 44/8 areas [8] 14/5 14/20 18/4 18/6 18/10	23/16 23/23 26/2 40/15
add [3] 8/3 8/18 14/22	25/11 38/1 43/4	bottom [2] 14/13 15/10
added [2] 25/15 41/20 adding [1] 28/7	aren't [1] 43/20	Bowl [15] 2/14 12/1 13/8 17/17
addition [1] 5/12	around [4] 4/3 29/6 37/21 44/18 Article [2] 4/14 8/23	18/13 20/22 31/18 33/13 37/9 38/3 39/14 39/14 39/15 40/8 40/17
	., 1. 0, 20	
L		

В	41/12 43/20 45/1 45/5 community [4] 28/10 32/21 37/13	DGEIS [3] 7/9 7/10 7/15 Dick [2] 24/8 27/20
Brandon [1] 32/16	44/13	did [2] 21/11 29/18
break [1] 39/6	compared [1] 25/1	different [2] 16/14 42/4
bring [1] 34/21 brings [2] 10/23 15/13	compatible [1] 20/18 competitiveness [1] 10/14	directors [1] 27/11 dirt [1] 16/20
Broderick [1] 27/9	complete [1] 2/17	discount [1] 25/10
Brook [3] 25/14 26/6 26/14 build [2] 11/11 22/13	complex [1] 38/11 complying [1] 8/22	disjointed [1] 33/23 diversity [1] 10/18
building [4] 8/6 11/15 17/1 17/3	compromise [1] 29/5	do [16] 4/1 5/5 10/7 13/11 15/18
Bulletin [1] 6/13	concern [3] 31/1 32/13 44/2	16/15 27/21 30/1 31/2 34/11 35/4
bunch [1] 42/3 Burnt [8] 7/22 12/20 14/17 14/18	concerned [3] 24/19 30/17 42/15 concerns [2] 40/8 41/6	39/2 41/13 41/14 44/4 46/4 document [1] 4/15
33/10 33/11 33/15 36/23	concluded [1] 45/6	Does [1] 32/14
bus [2] 15/17 15/18	connect [3] 15/4 33/15 34/5	doesn't [1] 38/21
busier [1] 15/21 busses [1] 15/23	connecting [1] 7/22 connection [1] 20/22	doing [4] 21/4 29/9 30/21 40/16 don't [11] 13/21 16/19 27/17 28/2
busy [1] 15/20	connectivity [1] 33/9	28/4 29/3 29/7 31/6 32/5 32/11 33/21
but [26] 3/22 12/10 13/22 14/22 19/18 23/13 24/5 27/17 29/4 30/1	Conservation [1] 4/14 consideration [1] 26/3	done [5] 22/6 24/2 39/12 42/6 42/7 doubt [1] 37/10
32/12 33/7 34/12 35/1 36/15 36/23	Constitution [1] 9/1	down [12] 5/11 6/6 12/10 14/9 16/20
37/20 39/7 40/8 40/17 42/15 42/20	constitutional [2] 41/18 42/21	18/1 19/10 21/19 25/17 33/12 40/13
43/15 44/7 44/16 44/22	construct [4] 7/21 8/5 8/10 11/8 construction [2] 9/14 11/6	40/23 downtown [1] 20/6
С	Contact [1] 1/18	draft [4] 4/16 4/17 7/8 41/4
calling [1] 5/4 can [21] 3/23 5/10 5/15 5/19 6/2 9/9	content [1] 4/9	draw [1] 40/19
13/23 14/21 16/4 16/8 21/6 21/18	continue [6] 10/12 15/21 20/7 20/9 20/17 20/20	E
21/20 29/1 33/19 34/11 34/15 36/2	contract [1] 40/4	e-mail [2] 5/16 5/18
39/12 41/19 44/12 can't [1] 32/9	contracts [1] 35/5 contributing [2] 3/1 3/3	easier [2] 19/21 20/1 echo [4] 7/23 28/22 34/8 37/2
capacity [1] 33/5	copies [4] 6/2 6/3 7/9 21/7	economic [1] 40/14
care [1] 39/21	copy [3] 5/21 6/3 6/4	economy [1] 28/9
Carlson [1] 24/9 caught [1] 15/23	could [3] 30/21 34/14 35/6 Country [1] 26/11	efficiency [4] 10/12 10/14 20/14 20/16
center [2] 8/13 36/12	couple [2] 13/1 33/1	either [1] 29/1
certainly [6] 3/5 3/16 4/1 35/11	course [2] 18/21 19/12	electronically [1] 9/14
38/20 42/13 certified [1] 34/10	courses [3] 12/3 19/9 34/10 create [1] 34/6	eliminate [1] 25/19 else [5] 22/8 28/20 30/5 32/7 32/14
certify [1] 46/5	Creek [10] 1/13 2/13 7/15 12/1 20/6	Emily [2] 5/3 5/21
chair [8] 8/3 17/23 18/4 18/23 19/1 19/14 19/20 40/14	20/23 23/12 23/13 24/21 25/8	encroach [1] 44/5 end [2] 5/23 10/3
chairs [1] 19/21	Crikelair [1] 26/20 Crikelair's [1] 27/1	ends [2] 14/10 19/1
change [3] 16/14 25/2 31/6	critical [1] 35/20	energy [3] 10/12 20/13 20/16
changes [1] 44/3	cuisine [1] 35/3 current [1] 35/5	enhance [2] 8/20 28/9 enjoy [1] 28/1
charged [1] 32/11	currently [4] 14/10 17/11 18/1 18/23	enlarge [3] 8/9 11/7 18/11
class [1] 35/3 classification [1] 17/15	customer [1] 20/3	entire [1] 12/6
cleared [2] 43/4 43/4	customers [3] 13/19 16/7 38/5	enumerate [1] 42/3 Environmental [6] 4/13 4/17 4/22
clearing [1] 43/1	D	6/13 7/8 9/13
climate [2] 25/2 31/5 close [4] 26/2 42/23 43/9 44/15	date [1] 46/6 Dated [1] 46/11	EPA [1] 25/2 escape [1] 36/22
closed [1] 44/21	day [3] 24/11 36/13 36/17	especially [2] 15/3 25/18
closer [4] 6/9 12/9 16/17 18/17	days [1] 15/21	estimates [1] 37/17
closes [1] 9/7 closeup [1] 13/9	deal [1] 25/5 dealing [1] 39/7	even [1] 31/4 evening [1] 9/22
coaster [5] 12/2 18/14 18/18 39/3	dec [2] 6/7 7/17	events [1] 10/10
39/4 coexist [1] 23/21	DEC's [1] 42/6 dedicated [2] 8/5 16/3	ever [1] 36/19 every [1] 35/16
coexistence [1] 39/21	definitely [1] 15/15	everybody [5] 2/23 9/21 27/12 28/20
Cold [1] 36/13	delightful [1] 25/21	44/17
collision [1] 31/23 come [6] 16/19 16/21 18/2 25/16	Department [1] 9/12 depositing [1] 38/18	everyone [6] 3/16 18/17 22/1 22/8 27/9 30/16
39/2 40/13	design [3] 31/17 34/1 39/16	everything [2] 32/7 40/6
coming [7] 9/16 9/22 16/1 32/6 32/7 44/17 45/3	designated [1] 41/17 designed [3] 3/19 3/21 38/12	exactly [2] 29/21 36/10 Excellent [1] 43/19
comment [11] 4/20 5/14 7/6 9/7	desirable [1] 10/8	excellently [1] 38/12
21/10 21/14 21/23 32/15 43/23 44/16	detachable [3] 18/4 19/20 19/21	exciting [2] 29/11 30/12
44/23 commentary [1] 33/4	detail [2] 42/6 42/18 details [1] 11/4	existence [1] 40/13 existing [9] 16/13 19/17 22/9 22/18
comments [23] 3/17 3/20 4/18 4/19	develop [4] 2/12 8/13 20/18 20/21	22/23 23/4 23/10 23/19 23/21
5/9 5/12 5/15 5/19 9/2 9/5 9/9 9/15 9/18 10/4 24/1 24/22 28/22 37/7 41/5	development [10] 1/6 2/6 7/2 9/10 10/16 20/10 23/18 24/4 26/23 40/15	expand [5] 8/6 11/23 22/17 23/3 42/10
5, 10 10/7 27/1 27/22 20/22 3/// 41/3	10,10 20,10 23,10 24,4 20,23 40,13	72/10

-	goals [2] 10/5 28/8	high [3] 18/20 19/3 35/3
E	goes [4] 15/2 31/18 31/19 35/10	high-class [1] 35/3
expanded [2] 17/4 37/11		hiking [12] 8/13 12/3 22/10 25/8
expansion [4] 11/14 12/21 17/2 23/8 expansions [2] 20/12 34/17	16/4 20/9 20/17 21/16 23/20 27/2 27/3 29/8 29/11 29/22 31/21 32/10	25/10 25/11 25/20 25/22 30/14 32/4 44/6 44/11
experience [6] 13/18 14/8 14/15	34/7 34/8 37/1 37/3 37/4 37/12 37/19	
16/6 19/7 20/3	38/4 38/9 38/10 38/20 39/1 39/1 39/4	Himmoff [1] 32/16
explain [1] 3/9	39/5 41/3 43/16 45/1	hired [1] 36/17
explore [1] 10/15 extend [4] 13/15 18/22 19/2 19/5	golf [2] 12/3 19/12 good [3] 42/10 43/2 43/12	his [1] 6/22 historically [1] 33/17
F	Gore [33] 1/13 2/7 2/23 6/5 7/4 7/7	hold [1] 7/2
	7/11 7/19 8/12 8/18 10/6 11/19 15/5	home [1] 22/4
Face [1] 42/19 facilities [4] 8/17 10/11 10/19 42/12	17/6 20/22 22/3 22/4 22/16 23/3 23/9 24/2 24/5 24/10 30/11 30/13 31/2	honest [1] 29/12 hope [4] 28/23 38/20 38/21 44/18
facility [2] 11/15 12/6	31/3 32/1 36/11 40/3 40/15 42/19	host [2] 25/3 28/10
fact [1] 38/1	42/20	hosting [1] 10/9
fall [2] 22/22 38/7	Gore's [1] 3/13	how [7] 23/17 27/3 34/14 34/22
familiar [3] 12/18 13/12 13/22 family [1] 30/21	Gore.2017 [1] 9/15 got [2] 39/19 40/4	36/23 37/4 38/8 However [1] 37/17
fantastic [2] 24/3 37/12	gov [1] 7/18	http:www [1] 7/17
fault [1] 23/15	gov/lands/41866.html [1] 7/18	http:www/dec/ny [1] 7/17
feasible [1] 28/3	granted [2] 17/21 19/16	Hudson [5] 17/22 19/14 24/17 38/17
February [4] 5/15 9/8 45/2 46/11 federal [1] 25/2	gravel [1] 16/20 great [6] 22/6 22/7 24/1 32/17 32/19	40/14 huge [3] 25/5 30/4 40/18
feel [2] 16/3 44/8	35/13	hundred [1] 28/23
feels [1] 22/17	greater [2] 37/23 38/1	Hut [1] 26/5
feet [1] 38/14 few [2] 4/7 25/8	green [3] 8/2 14/5 18/6	Huts [1] 29/8
figure [1] 39/20	grip [1] 19/20 groomer [1] 8/8	I
Final [2] 4/21 4/22	grooming [4] 11/11 16/9 16/13 16/16	I'd [2] 6/19 29/16
first [5] 5/8 13/9 21/21 31/11 32/17	ground [1] 35/18	I'll [2] 3/8 37/6
five [1] 42/5 five-year [1] 42/5	group [4] 1/19 3/5 3/9 24/14 grows [1] 32/23	I'm [15] 2/4 2/5 9/23 22/2 24/8 26/22 27/9 27/9 28/2 28/17 29/23
fixed [1] 19/20	guess [2] 27/5 34/9	30/7 31/10 35/14 40/6
flow [2] 15/20 16/4	guests [1] 10/8	I've [12] 21/2 22/3 22/12 22/13
folks [1] 44/3 following [1] 7/21	guys [1] 29/1	27/13 28/18 29/8 30/8 31/12 36/18 40/2 40/4
food [1] 34/17	Н	ice [1] 36/15
foregoing [1] 46/5	had [4] 10/2 21/6 26/19 29/2	icy [1] 36/14
forest [3] 11/21 17/12 42/2 Forests [1] 7/13	Hall [2] 6/6 7/15 Hamlets [2] 26/5 29/9	idea [6] 12/7 29/4 30/10 30/11 35/9 36/22
former [1] 2/7	happen [1] 34/15	identified [1] 16/10
forth [1] 24/18	happy [2] 4/1 27/18	if [27] 3/22 4/3 12/18 13/12 13/21
fortunate [1] 25/4	hard [6] 2/22 6/3 22/12 22/14 35/4	17/20 19/15 20/4 21/9 21/16 23/20 24/23 25/18 28/3 28/7 29/4 30/1
forward [1] 45/4 found [1] 15/20	44/6 harmony [1] 44/9	30/15 32/11 32/22 33/19 33/22 34/14
four [1] 39/9	has [11] 3/1 5/3 5/21 6/4 15/7 25/8	35/6 36/2 43/19 43/21
frame [1] 35/21	31/15 39/17 41/13 41/14 42/20	impact [4] 4/17 4/22 7/9 23/18
Franke [3] 1/18 3/8 4/5 friends [2] 3/4 29/14	hasn't [1] 42/5 hate [2] 29/16 40/20	important [5] 23/22 26/3 42/1 42/13 43/15
front [1] 5/20	have [40] 3/2 3/7 3/12 5/5 10/3	impressions [1] 36/3
fueling [2] 8/8 11/12	13/23 14/4 15/22 16/19 17/13 17/23	improve [6] 10/13 10/18 20/18 20/21
G	22/15 22/19 23/7 23/7 23/10 23/21 24/6 25/9 26/16 27/6 27/17 27/21	28/9 28/11 improvement [2] 8/16 24/16
gain [1] 2/19	28/6 28/15 29/5 29/14 30/10 30/13	improvements [12] 10/13 11/7 12/8
garage [6] 8/8 11/12 16/9 16/13	31/7 31/15 32/15 34/12 37/17 39/13	12/15 13/11 17/17 18/13 20/11 20/11
16/21 16/22 Garnet [1] 24/12	40/8 40/10 41/6 44/4 44/13 haven't [5] 20/4 23/14 23/15 28/4	20/12 20/14 20/16 improving [1] 35/9
general [2] 3/13 15/19	31/4	in [64]
generation [1] 10/21	he [1] 21/12	include [6] 2/11 7/21 11/5 12/2
Generic [1] 7/8 get [20] 4/7 5/6 5/10 6/2 12/9 14/2	heading [1] 46/6 health [2] 28/12 35/10	18/13 28/8 includes [1] 11/17
15/12 15/21 15/23 16/20 21/6 21/18	hearing [13] 1/5 3/10 3/19 4/11 5/7	including [1] 10/20
23/12 32/22 33/20 34/12 34/18 35/13	6/12 6/16 6/23 7/3 9/4 9/6 44/21 45/6	increase [4] 8/19 10/14 10/16 33/22
37/1 37/5 gets [1] 22/21	held [1] 4/12 Hello [1] 9/21	indeed [1] 25/4 independent [1] 11/8
getting [7] 11/4 14/1 33/10 33/12	help [4] 16/17 22/12 22/14 27/12	independent [1] 11/8 independently [1] 43/8
42/23 43/9 45/4	helpful [1] 42/8	industry [1] 37/21
give [10] 3/14 3/16 12/7 13/18 14/14		information [2] 5/22 21/5
14/23 19/6 19/8 36/3 36/9 gives [5] 4/8 13/20 18/15 21/5 21/8	helps [1] 33/14 here [47]	infrastructure [3] 10/11 20/15 38/9 Initiative [1] 26/6
glimmer [1] 30/18	hereby [1] 46/5	inner [1] 15/4
	hereof [1] 46/6	intensive [4] 11/19 13/5 17/7 17/14
32/9 39/5 41/9	Hi [2] 22/1 24/8	interest [1] 9/17

I	Let [1] 28/6	may [3] 9/5 28/7 44/6
interested [1] 34/21	Let's [2] 18/16 21/22 lie [1] 23/23	maybe [6] 23/14 29/5 29/23 30/20 33/12 33/19
interesting [1] 33/6	life [1] 39/16	me [6] 24/9 28/6 29/22 30/3 33/7
interests [2] 32/1 32/2	lift [22] 8/2 11/6 12/15 12/17 12/17	46/5
intermediate [2] 12/19 12/20 intimate [1] 25/22	13/13 13/14 13/16 14/2 14/9 14/11	mean [1] 34/3 meet [1] 44/18
into [13] 6/19 10/23 11/4 12/9 12/13	14/19 18/2 18/3 19/8 19/18 19/19 20/10 28/6 38/17 38/17 44/10	meet [1] 44/10 meetings [1] 29/9
13/17 16/20 16/22 18/7 19/2 23/9	light [1] 18/10	members [1] 27/10
26/16 38/7	lighter [1] 18/6	mentioned [4] 10/2 13/1 19/13 21/6
involves [1] 11/18 is [75]	lights [1] 19/5 like [26] 3/6 6/19 16/10 17/13 17/17	menu [1] 37/14 methodology [1] 43/3
issue [4] 34/2 35/1 43/14 43/15	17/20 22/9 22/16 23/5 23/19 24/4	middle [1] 15/6
issued [1] 4/15	24/11 24/22 25/23 27/11 27/15 27/19	Mike [5] 2/4 4/6 9/20 10/2 22/7
issues [6] 4/7 33/2 33/8 41/10 41/15	29/4 29/22 30/2 33/4 33/7 36/21	Minder [1] 39/5
41/21 it [48]	42/17 43/1 43/12 limits [2] 43/1 43/10	mindful [1] 43/11 mini [2] 12/3 19/12
it's [19] 15/15 18/17 21/7 22/4 22/23	line [1] 39/3	miserable [1] 36/13
25/21 25/22 26/3 27/23 28/2 28/3	lines [1] 30/22	misguided [2] 25/18 26/18
31/13 32/17 35/4 35/11 35/12 39/15 43/15 44/11	list [1] 5/5 listed [1] 10/6	mistake [2] 29/17 30/4 modernization [3] 8/17 20/13 20/15
its [3] 39/16 39/16 42/7	little [12] 4/3 8/12 18/17 25/15 30/11	
J	30/13 31/2 31/3 35/2 36/9 38/8 44/7	modification [2] 11/10 11/13
	live [3] 29/13 29/15 30/7	moments [1] 13/1
January [5] 1/11 6/14 6/17 7/3 9/3 January 10th [1] 6/14	lived [1] 28/18 load [2] 19/22 20/1	money [1] 31/16 months [1] 39/9
January 8th [1] 6/17	loading [1] 38/16	more [10] 10/7 10/20 11/4 16/5 21/5
Jill [1] 27/9	local [1] 35/9	31/3 31/13 35/2 36/4 45/4
job [4] 22/6 22/7 24/2 24/3	locals [1] 34/20	Morris [1] 22/2
Joe [1] 39/5 Johnsburg [10] 2/13 7/14 13/7 27/2	location [2] 12/4 16/15 locations [1] 6/4	most [3] 5/1 22/2 24/9 mountain [37] 1/13 6/5 7/5 7/7 7/11
28/11 31/15 32/3 35/11 39/15 39/18	lodge [6] 1/13 7/5 7/23 8/4 8/14	7/20 8/18 11/16 11/19 11/20 12/4
Joseph [2] 46/3 46/10	20/11	12/21 17/7 17/12 19/23 22/4 31/4
Julie [1] 30/7 jump [1] 18/16	long [2] 1/19 30/8 longer [1] 36/5	32/1 32/19 32/22 33/2 33/8 33/10 33/13 33/17 33/18 33/23 34/3 34/18
June [1] 38/5	look [2] 41/21 45/4	34/23 36/12 36/16 39/4 40/7 40/17
just [24] 4/6 6/19 12/6 14/21 15/9	looked [3] 27/15 29/22 41/11	42/11 44/11
17/18 18/16 21/15 23/1 24/5 27/20	looking [10] 11/22 12/8 13/11 13/15	move [2] 29/1 29/6
27/20 28/1 30/22 31/4 31/6 34/4 35/5 35/20 36/20 37/19 41/4 44/20 44/22	15/11 17/19 19/2 19/4 19/10 43/7 looks [1] 30/2	moving [1] 16/14 Moxham [1] 19/4
K	loop [1] 8/11	Mr [1] 37/8
	lose [3] 29/7 29/16 40/20	much [9] 15/1 16/5 16/5 19/6 20/2
Katy [1] 40/1 keep [3] 11/3 16/4 19/17	losing [1] 29/23 lot [21] 16/2 22/15 22/22 27/14 28/1	28/16 29/4 31/5 44/13
keeping [1] 22/8	29/9 29/14 29/18 32/20 33/15 34/11	
Kelly [4] 5/10 31/10 46/3 46/10	36/15 40/4 40/5 40/6 41/6 42/1 42/9	46/7
Kevin [8] 1/18 3/8 3/13 4/5 9/19 10/2 21/6 21/12	42/11 42/14 44/17 lots [1] 12/13	N
		IX
IKEY 2 33/0 33/12		
key [2] 33/8 33/12 kfranke [1] 1/21	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12
kfranke [1] 1/21 kicking [1] 44/18	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17
kfranke [1] 1/21 kicking [1] 44/18	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needs [2] 34/18 44/9
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needs [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needs [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needs [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needs [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 Lake [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needs [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 Lake [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6 17/19 19/15 27/23 40/9 41/7 41/16	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10 manage [1] 38/4	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needs [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17 nice [1] 14/14
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 Lake [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6 17/19 19/15 27/23 40/9 41/7 41/16 lands [4] 2/12 7/13 7/18 13/7	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10 manage [1] 38/4 management [8] 2/10 2/17 4/16 7/7	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needed [1] 15/1 needs [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17 nice [1] 14/14 nicer [1] 20/3
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 Lake [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6 17/19 19/15 27/23 40/9 41/7 41/16	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10 manage [1] 38/4	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needs [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17 nice [1] 14/14
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 LAke [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6 17/19 19/15 27/23 40/9 41/7 41/16 lands [4] 2/12 7/13 7/18 13/7 lane [5] 11/9 12/11 15/17 15/18 16/3 lanes [1] 8/5 larger [1] 33/18	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10 manage [1] 38/4 management [8] 2/10 2/17 4/16 7/7 36/1 42/2 42/7 43/14 manager [2] 2/7 3/14 many [2] 27/17 38/1	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needes [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17 nice [1] 14/14 nicer [1] 20/3 Nightengale [1] 40/2 nighttime [1] 19/6 nine [1] 35/16
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 Lake [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6 17/19 19/15 27/23 40/9 41/7 41/16 lands [4] 2/12 7/13 7/18 13/7 lane [5] 11/9 12/11 15/17 15/18 16/3 lanes [1] 8/5 larger [1] 33/18 lately [1] 24/14	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10 manage [1] 38/4 management [8] 2/10 2/17 4/16 7/7 36/1 42/2 42/7 43/14 manager [2] 2/7 3/14 many [2] 27/17 38/1 map [6] 12/5 23/7 23/10 23/16 23/17	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needes [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17 nice [1] 14/14 nicer [1] 20/3 Nightengale [1] 40/2 nighttime [1] 19/6 nine [1] 35/16 nine-year-old [1] 35/16
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 LAke [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6 17/19 19/15 27/23 40/9 41/7 41/16 lands [4] 2/12 7/13 7/18 13/7 lane [5] 11/9 12/11 15/17 15/18 16/3 lanes [1] 8/5 larger [1] 33/18	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10 manage [1] 38/4 management [8] 2/10 2/17 4/16 7/7 36/1 42/2 42/7 43/14 manager [2] 2/7 3/14 many [2] 27/17 38/1 map [6] 12/5 23/7 23/10 23/16 23/17 44/7	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needes [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17 nice [1] 14/14 nicer [1] 20/3 Nightengale [1] 40/2 nighttime [1] 19/6 nine [1] 35/16 nine-year-old [1] 35/16 no [2] 36/14 37/10
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 Lake [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6 17/19 19/15 27/23 40/9 41/7 41/16 lands [4] 2/12 7/13 7/18 13/7 lane [5] 11/9 12/11 15/17 15/18 16/3 lanes [1] 8/5 larger [1] 33/18 lately [1] 24/14 Law [1] 4/15 least [1] 24/23 leaves [1] 31/18	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10 manage [1] 38/4 management [8] 2/10 2/17 4/16 7/7 36/1 42/2 42/7 43/14 manager [2] 2/7 3/14 many [2] 27/17 38/1 map [6] 12/5 23/7 23/10 23/16 23/17 44/7 maps [2] 29/19 29/20 marketplace [1] 10/15	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needes [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17 nice [1] 14/14 nicer [1] 20/3 Nightengale [1] 40/2 nighttime [1] 19/6 nine [1] 35/16 no [2] 36/14 37/10 North [13] 1/13 2/13 7/15 12/1 20/6 20/23 23/12 23/13 24/20 25/7 26/11
kfranke [1] 1/21 kicking [1] 44/18 kids [1] 35/13 kind [6] 3/9 14/2 15/14 30/18 34/6 34/7 know [13] 13/21 22/2 24/9 24/21 25/15 26/19 27/13 32/11 32/19 32/21 34/22 35/8 44/1 L LA [3] 1/19 3/5 3/9 LA Group [2] 3/5 3/9 Lake [4] 6/9 6/10 7/13 9/11 land [11] 8/23 11/18 12/23 13/2 17/6 17/19 19/15 27/23 40/9 41/7 41/16 lands [4] 2/12 7/13 7/18 13/7 lane [5] 11/9 12/11 15/17 15/18 16/3 lanes [1] 8/5 larger [1] 33/18 lately [1] 24/14 Law [1] 4/15 least [1] 24/23	love [3] 22/4 22/5 35/16 lower [2] 8/4 14/13 M machines [1] 16/19 mail [4] 5/16 5/17 5/18 9/9 main [6] 9/11 15/5 25/12 33/16 40/7 40/16 maintain [1] 22/14 maintenance [2] 8/7 16/18 major [1] 41/10 make [14] 2/16 3/17 10/4 10/7 12/8 14/7 16/5 17/18 20/2 30/17 34/4 34/15 40/7 43/23 making [2] 28/13 32/10 manage [1] 38/4 management [8] 2/10 2/17 4/16 7/7 36/1 42/2 42/7 43/14 manager [2] 2/7 3/14 many [2] 27/17 38/1 map [6] 12/5 23/7 23/10 23/16 23/17 44/7 maps [2] 29/19 29/20	name [3] 5/9 21/17 36/8 National [2] 25/2 26/12 necessarily [1] 3/21 necessary [1] 22/17 need [6] 8/15 31/3 34/4 35/2 41/10 43/11 needed [1] 15/1 needes [2] 34/18 44/9 Nessle [3] 31/11 36/9 37/8 new [21] 1/13 1/20 7/1 7/19 7/22 8/3 11/5 11/11 12/11 12/19 14/11 14/23 15/10 16/9 23/18 23/20 24/4 31/16 33/14 38/17 46/4 news [1] 33/6 next [3] 10/21 18/14 36/17 nice [1] 14/14 nicer [1] 20/3 Nightengale [1] 40/2 nighttime [1] 19/6 nine [1] 35/16 nine-year-old [1] 35/16 no [2] 36/14 37/10 North [13] 1/13 2/13 7/15 12/1 20/6

N	30/9 35/11 36/15 37/1 38/3 39/8	35/23 38/19
not [17] 2/10 3/20 19/16 25/5 26/17	overlay [1] 29/20 overview [4] 11/2 11/3 12/6 18/15	problem [3] 15/22 38/22 39/10 problems [2] 25/1 38/9
28/3 32/12 34/11 34/23 38/19 39/14	P	procedural [2] 4/7 6/18
40/21 41/8 41/19 43/13 44/4 44/15	-	process [3] 2/15 3/11 3/18
Notary [1] 46/4 noted [1] 46/6	p.m [2] 1/12 45/7 pages [1] 27/15	professional [1] 36/18 projects [3] 2/20 2/23 35/23
noted [1] 40/0 notes [2] 27/17 28/6		property [3] 26/20 27/1 27/3
notice [5] 6/11 6/13 6/15 6/20 6/23	park [11] 2/18 8/22 25/3 31/18 37/9	proposal [1] 30/2
now [9] 3/5 13/13 15/16 23/1 36/20	37/16 38/3 39/1 39/14 39/14 39/15	proposed [9] 7/19 11/2 12/11 15/6
38/3 38/8 38/13 40/3 number [1] 6/4	parking [3] 12/13 16/2 20/12 part [12] 3/18 6/18 13/4 15/6 17/11	15/17 18/6 23/8 23/17 26/21 proposing [7] 14/6 14/11 14/22
numbers [3] 28/4 31/2 33/22	26/14 29/23 33/16 33/18 37/15 38/22	17/22 18/11 18/19 18/22
nutshell [1] 21/2	41/19	protect [5] 22/18 23/3 23/4 24/6
ny [2] 7/17 9/12	participants [1] 37/18	41/2
NYS [2] 1/6 9/1 NYSDEC [1] 7/11	parts [1] 31/20 past [2] 22/6 24/3	provide [2] 3/23 39/17 public [28] 1/5 3/10 3/19 4/11 5/13
NYSEF [4] 8/6 11/14 17/1 17/2	patrol [1] 24/12	6/11 6/15 6/20 6/23 7/3 7/5 8/19 9/2
o	patroller [1] 36/18	9/4 9/4 9/6 9/7 9/8 20/19 21/10 21/13
	pavilion [1] 39/6 peaceful [1] 39/20	21/23 22/19 32/5 44/21 44/23 45/6 46/4
39/2	people [15] 3/1 3/7 16/1 19/8 19/22	published [2] 6/12 6/16
offered [1] 44/14	21/16 22/15 24/2 24/9 28/1 34/13	pump [1] 33/4
office [1] 7/14	38/10 38/23 39/8 44/22	purple [1] 18/19
offices [3] 6/7 6/10 7/12 offload [2] 19/23 20/1	percent [2] 27/19 28/23 period [6] 4/20 5/14 9/7 38/7 39/8	purpose [1] 8/15 pursuant [1] 42/21
Okay [4] 13/9 28/21 31/10 36/8	44/23	pursuits [1] 8/21
old [2] 35/15 35/16	permanent [1] 19/12	pushing [1] 37/18
Olympic [5] 1/6 2/6 3/2 7/1 9/10	permits [1] 2/20	put [9] 14/11 16/11 16/16 18/19
on [42] 2/23 4/4 4/9 5/1 5/19 5/20 5/22 6/13 6/17 7/3 7/6 8/16 9/7 11/14	personally [1] 43/22 perspective [1] 36/10	19/10 23/20 29/3 29/5 41/11 puts [1] 19/3
12/20 16/18 18/14 19/3 19/19 20/1	perused [1] 27/16	putting [1] 27/12
21/4 23/16 24/11 25/10 25/11 26/2	Peter [1] 41/1	Q
26/23 29/11 29/20 30/22 32/9 33/4 33/5 34/8 34/22 35/14 35/18 36/17	picnic [1] 34/22 piece [2] 13/2 17/19	quad [1] 8/3
39/3 40/5 44/5 44/7	place [3] 8/7 39/17 46/6	quality [2] 4/13 10/18
on-going [1] 8/16	Placid [4] 6/9 6/10 7/14 9/12	question [5] 3/21 26/19 31/13 31/14
once [2] 39/7 39/12 one [11] 4/4 4/4 6/5 6/6 6/9 25/15	plan [17] 2/10 2/17 4/17 7/8 8/23 10/5 10/22 11/1 27/13 27/19 28/8	36/21 questions [3] 4/4 21/21 27/6
27/10 28/23 33/7 34/13 36/20	32/18 34/15 35/19 36/1 42/10 43/14	quick [1] 30/6
one-on-one [1] 4/4	Plan/Draft [1] 7/8	quite [3] 16/18 23/1 26/2
ones [1] 25/4 online [2] 7/16 21/8	planned [1] 40/12 planning [4] 9/13 19/19 20/7 21/4	R
only [3] 16/13 27/23 44/12	plans [8] 2/9 2/11 3/15 32/12 35/22	Rabbit [17] 22/21 23/4 23/9 23/11
onto [2] 14/17 16/23	42/2 42/5 42/8	25/13 25/17 25/19 26/8 26/15 27/22
open [3] 5/14 31/5 45/1 opened [1] 36/12	please [1] 21/17 plenty [1] 10/3	29// 30/16 41// 41/21 42/15 44/1 44/5
operation [1] 18/12	PM [1] 7/4	race [2] 11/15 34/10
operational [1] 10/13	Poma [2] 12/17 14/9	races [1] 34/8
operations [1] 11/23 opportunities [2] 25/9 30/20	Pond [17] 22/21 23/5 23/9 23/11 25/13 25/17 25/19 26/8 26/15 27/22	Raymond [3] 25/14 26/6 26/14 read [1] 6/19
opportunities [2] 25/5 56/20 opportunity [4] 3/17 10/4 13/21 41/3		real [1] 43/2
or [16] 5/16 8/3 9/6 9/14 13/13 29/3	44/5	realign [1] 17/22
31/6 31/7 32/12 33/17 37/14 37/20 39/3 39/3 39/9 44/5	Ponds [3] 11/21 17/8 24/15 portions [1] 30/15	realigning [1] 19/14 realignment [1] 28/5
Oral [1] 9/2	positive [1] 16/6	realize [1] 33/3
ORDA [6] 6/10 27/2 27/10 39/14 42/5	possible [1] 44/14	really [21] 14/14 25/11 25/21 28/5
43/3 ORDA's [1] 7/13	Post [1] 6/17	28/23 29/3 29/10 30/12 31/11 31/13 33/6 33/14 33/21 34/21 35/1 35/12
orda.org [1] 9/15	Post-Star [1] 6/17 potential [2] 10/15 12/22	35/14 35/20 40/11 43/12 43/14
order [1] 34/19	powerful [1] 2/8	reasons [1] 3/10
originally [1] 29/2 other [10] 8/2 22/15 25/3 27/6 31/1	Pratt [1] 2/5 preface [1] 24/22	receive [4] 4/18 4/20 5/13 7/5 received [1] 31/16
31/20 33/20 34/13 37/9 43/20	premiere [1] 24/22 premiere [2] 10/9 26/8	reclassification [6] 11/18 12/23 17/6
others [1] 30/22	presentation [9] 2/4 2/8 3/15 4/2 4/9	17/21 19/16 27/22
our [27] 2/9 2/10 2/16 2/18 3/4 5/10	6/1 6/22 9/23 21/1	reclassified [3] 17/10 17/13 17/20
10/7 10/15 11/1 11/7 11/15 12/11 12/13 12/16 12/22 13/13 13/19 14/8	preserve [1] 42/2 president [1] 2/5	recognize [1] 3/8 reconfigure [1] 8/7
14/15 15/20 15/22 16/6 16/9 17/16	pretty [1] 44/8	record [6] 5/7 5/11 6/20 21/18 44/20
18/9 24/23 41/11 out [15] 3/7 4/7 8/13 9/16 9/22	previous [3] 16/11 19/13 20/8 previously [4] 14/20 15/8 18/5 18/8	46/5 recreate [1] 39/19
14/21 16/23 30/19 32/22 35/13 37/5	priorities [1] 36/6	recreation [5] 11/23 20/19 24/20
38/6 39/20 44/15 45/3	priority [1] 36/5	30/11 37/14
over [11] 6/21 14/17 15/5 15/13 16/8	probably [5] 27/18 28/20 31/21	recreational [7] 8/20 10/8 10/19

R	served [1] 8/2	36/2 43/6
	Service [1] 25/3	southeastern [1] 37/15
recreational [4] 28/13 30/19 35/10		southern [1] 37/15
37/14 reference [1] 14/19	seven [2] 24/10 35/15 seven-year-old [1] 35/15	speak [2] 5/3 21/17 speakers [1] 5/4
Regional [4] 1/6 2/6 7/1 9/10	sewage [2] 38/19 39/22	speaking [1] 35/14
regular [2] 5/16 25/23	sewer [1] 38/12	speaks [1] 3/13
related [1] 34/16	shaded [4] 14/5 14/19 15/9 18/4	spectacular [1] 20/6
remain [1] 5/14	sheet [1] 5/2	spending [1] 35/16
remember [1] 39/13	sheets [1] 5/19	spent [1] 29/18
remind [2] 21/16 44/22 replace [3] 13/15 16/12 18/3	Shorthand [1] 46/3 should [1] 23/2	spring [2] 22/22 26/10 Springs [1] 1/20
Reporter [1] 46/3	show [3] 18/5 18/6 18/10	
request [2] 11/17 17/5	showing [2] 23/16 23/17	staging [1] 14/4
requesting [1] 17/9	shown [1] 21/2	Star [1] 6/17
require [1] 38/11	shows [5] 12/5 15/16 17/5 17/16	start [2] 5/8 21/13
reservations [1] 27/21	19/15	starting [1] 31/21
reservoir [5] 8/10 11/8 12/22 18/9 18/11	shuttle [7] 8/5 11/9 12/11 15/17 15/18 15/22 16/3	state [8] 4/13 7/1 8/23 21/17 31/16 32/21 35/5 46/4
residents [2] 28/12 39/18	Siamese [3] 11/21 17/8 24/15	statement [4] 4/18 4/23 7/9 31/14
resorts [1] 37/23	side [3] 33/9 33/20 34/13	station [2] 8/8 11/12
resounding [1] 44/2	sides [1] 26/2	stay [1] 45/1
respect [1] 25/6	sign [1] 5/2	stenographer [3] 5/5 5/10 21/18
restate [1] 5/9 revenue [1] 32/20	sign-up [1] 5/2	still [4] 19/18 34/12 36/16 39/11
review [2] 4/13 7/11	signs [1] 26/13 simple [1] 3/23	strategy [1] 34/17 Street [1] 9/11
Rick [3] 22/2 24/14 27/20	simultaneously [3] 2/14 2/21 8/21	
Ridge [8] 7/22 12/20 14/17 14/18	since [2] 36/19 39/16	strongly [1] 44/8
33/11 33/11 33/15 36/23	single [1] 8/11	stuff [4] 29/11 33/5 40/5 44/14
right [12] 3/5 4/5 12/5 13/14 14/23	single-track [1] 8/11	submitted [4] 5/16 5/19 9/5 9/9
15/16 16/22 19/1 23/16 26/7 30/12 36/20	ski [34] 2/13 7/22 12/1 13/5 13/8	successful [1] 44/12
River [2] 30/8 31/19	13/13 17/14 17/16 18/5 18/7 18/13 19/8 20/22 22/10 22/21 24/12 25/10	sudden [1] 32/8 suggest [1] 28/7
road [3] 12/12 16/1 16/20	31/18 33/13 36/12 36/18 37/9 37/22	summer [15] 10/17 11/23 18/12
Robertson [1] 28/18	38/3 39/13 39/14 39/15 40/8 40/17	19/11 19/22 20/4 22/22 30/10 30/19
rock [1] 37/1	40/19 40/22 40/23 44/5 44/10	32/2 37/10 37/11 37/20 37/20 37/22
room [1] 36/11	skied [4] 22/3 28/19 30/9 40/10	Sunday [1] 35/17
ropes [3] 12/2 18/20 19/9 round [1] 10/17	skier [2] 31/1 33/22 skiers [3] 13/22 14/8 14/16	Sunway [8] 8/1 8/4 8/9 12/17 13/13 13/16 13/16 14/13
route [2] 33/14 36/22	skiing [6] 12/18 19/7 25/20 36/21	13/16 13/16 14/13 support [1] 42/14
S	37/21 41/14	supported [1] 3/4
	slide [7] 13/9 15/13 17/5 17/16 18/15	supposed [1] 26/9
safety [1] 8/20	19/13 21/4	supposing [1] 38/4
Sagamore [1] 37/2 said [3] 25/7 27/20 27/20	slides [3] 10/1 12/10 21/3 slopes [1] 38/15	sure [3] 28/3 41/8 41/19
same [4] 23/17 24/14 28/19 46/7	smoother [1] 16/5	swap [2] 40/9 41/7 system [2] 22/19 38/13
Saratoga [1] 1/20	snow [6] 16/17 16/22 16/23 31/7	T
Saturday [1] 35/17	35/18 36/14	•
saw [2] 5/1 33/5	snowmaking [4] 8/10 11/7 12/22	table [1] 5/20
say [3] 24/11 31/8 38/6 saying [1] 24/23	20/13 snowshoe [1] 22/11	take [4] 15/11 30/15 39/6 39/21 taken [1] 46/5
Scenic [1] 26/12	snowshoeing [1] 25/20	takes [2] 27/14 30/18
Schaeffer [1] 25/12	so [38] 2/14 2/19 2/22 3/5 5/7 5/10	talk [1] 43/22
schedule [1] 42/4	10/5 10/21 14/21 16/2 16/13 21/1	talking [1] 15/4
scheduling [1] 41/23	21/11 21/18 24/1 24/18 26/2 27/17	taught [1] 28/19
Schenectady [1] 32/6 school [1] 38/6	28/3 29/6 30/4 30/14 31/8 31/13 34/10 34/23 35/19 38/18 38/21 39/11	teases [1] 26/16 tell [1] 37/6
Scott [1] 28/17	40/4 40/23 41/2 41/20 43/10 43/11	term [1] 36/6
screen [1] 5/23	43/19 44/14	terminate [1] 17/23
season [1] 25/21	Society [1] 24/16	terminates [2] 13/14 18/1
section [3] 2/18 15/9 15/10	solutions [1] 33/20	terrain [2] 31/3 31/7
Section 814 [1] 2/18	solved [1] 38/10	terribly [1] 36/13
see [17] 12/10 14/21 16/8 18/18 23/6 23/23 24/4 26/1 28/6 29/20 39/12	some [18] 12/9 13/11 21/5 21/9 22/5 22/13 23/2 25/1 26/20 27/15 30/20	terrific [1] 35/19 than [3] 27/6 31/14 38/1
40/14 40/18 42/17 43/2 43/12 44/7	33/3 34/7 39/11 39/20 41/10 41/15	thank [10] 3/6 9/19 9/20 24/6 27/8
seemed [1] 44/2	41/20	27/12 28/15 36/7 39/23 43/18
seems [3] 23/19 33/7 34/6	somebody [1] 40/22	thanks [9] 2/3 4/6 9/16 9/21 27/7
seen [4] 23/14 23/16 28/4 31/4	somehow [1] 35/7	31/9 41/2 44/16 45/3
send [1] 21/10 sensitive [1] 27/23	someone [1] 36/2 something [1] 43/10	that [121] that's [29] 4/15 11/9 11/15 12/12
separate [1] 27/23	sometime [1] 31/22	15/8 15/14 17/3 18/14 22/5 23/5 24/1
separates [1] 37/2	sometimes [2] 13/23 37/23	27/5 28/15 29/13 29/14 30/2 30/4
September [1] 38/6	sorry [1] 28/21	31/8 32/5 32/11 34/23 36/7 37/19
SEQRA [5] 1/5 2/15 3/11 3/18 6/23	sort [7] 33/23 34/1 34/3 34/15 35/9	38/21 39/9 40/23 41/8 43/10 43/13

Т	23/19 23/20 23/22 24/17 24/20 25/10	wants [3] 4/4 40/22 43/21
their [7] 14/1 26/8 27/12 32/1 32/3	25/12 25/16 26/21 29/21 30/14 30/14 31/17 32/4 32/4 32/9 34/5 40/10	Warrensburg [2] 6/7 7/12 was [16] 6/12 6/14 6/16 16/12 19/16
32/4 36/3	40/12 40/21 42/12 43/5 43/6 43/17	23/11 33/6 36/1 36/10 36/12 36/14
thelagroup.com [1] 1/21	44/4	36/15 36/17 41/16 42/22 45/6
them [5] 13/20 14/3 22/14 23/21 42/4	trails-based [1] 24/20 training [1] 10/9	wasn't [1] 41/18 way [8] 4/8 5/1 14/12 23/2 28/1
then [9] 6/21 12/9 12/13 13/6 17/1	transcript [1] 46/7	39/20 41/9 44/12
19/17 31/19 33/11 38/7	Trecks [1] 24/18	we [53]
there [23] 5/2 5/17 6/3 6/14 14/12	trees [1] 26/1	we'd [1] 5/7
14/21 18/16 18/20 19/1 19/5 19/15 21/12 23/2 29/20 33/1 36/14 36/15	tremendous [1] 32/18 Trial [1] 13/17	we'll [12] 3/15 4/2 4/19 5/4 6/21 11/3 12/9 20/20 34/21 41/11 43/20
37/4 38/13 40/11 41/16 43/20 44/4	tried [1] 29/19	44/17
there's [22] 3/22 6/5 6/6 6/9 14/10	trip [1] 26/9	we're [32] 2/14 3/12 3/23 10/6 11/22
25/11 27/15 29/10 32/18 32/20 34/1	triple [1] 8/3	12/7 13/10 13/14 14/6 14/11 15/11
34/11 35/18 35/22 37/10 39/11 39/19 41/10 41/15 41/20 42/9 42/14	true [1] 46/6 trying [3] 2/16 10/7 44/15	17/9 17/18 17/22 18/19 18/22 19/1 19/4 19/10 20/7 20/9 20/17 21/3
these [10] 2/23 10/1 12/8 14/19	tubing [1] 19/11	21/11 24/19 25/4 29/22 32/9 41/8
22/13 29/10 30/13 34/16 35/13 35/22	tunnel [2] 34/7 37/3	41/19 42/15 44/14
they [13] 2/11 13/23 14/2 23/23	turn [1] 6/21	we've [4] 2/22 3/3 41/3 43/7
29/15 32/9 32/10 39/1 39/2 39/4 39/5 40/6 40/11	twelve [1] 27/10 Twister [2] 8/1 34/9	Wednesday [1] 7/3 Wegg [2] 46/3 46/10
They'll [1] 16/21	typographical [1] 29/19	well [8] 2/17 5/21 15/15 19/23 22/17
they're [3] 14/2 20/1 40/16	U	26/4 35/10 38/11
thing [2] 37/9 43/6		wellness [1] 28/12
things [4] 29/10 36/4 36/5 42/10 think [32] 23/1 25/4 25/18 26/13	UMP [14] 4/10 4/22 6/2 7/9 7/10 7/15 7/20 8/15 9/15 11/11 11/14	wells [1] 38/14 went [1] 29/21
26/18 28/2 29/17 30/3 30/12 32/17	16/11 21/7 23/15	were [1] 17/21
33/1 33/2 33/15 33/21 34/1 34/17	UMP/DGEIS [3] 7/9 7/10 7/15	West [1] 30/7
34/19 34/20 35/1 35/8 35/19 36/7	UMPs [1] 20/8	wet [1] 36/14
39/19 41/9 41/15 41/20 41/23 42/9 42/23 43/8 43/10 43/15	under [2] 34/7 35/4 understand [1] 28/5	what [19] 3/12 10/6 10/23 14/22 15/17 16/15 21/3 23/5 23/7 23/14
this [62]	unit [8] 2/10 2/16 4/16 7/7 36/1 42/1	
those [12] 5/2 5/18 6/8 10/23 16/19	42/7 43/14	31/22 39/1 40/15
18/7 20/2 25/16 34/9 38/23 40/10 40/20	unless [1] 34/6 unloading [1] 13/19	what's [2] 14/21 40/18
thought [2] 30/23 33/3	until [4] 5/14 9/6 38/6 45/1	whatever [1] 31/6 when [8] 5/8 14/1 15/2 15/3 16/18
three [4] 25/12 38/13 39/9 41/4	up [18] 5/2 5/4 5/22 16/1 17/23 18/2	36/11 38/5 39/2
through [8] 2/15 10/1 12/13 16/2		whenever [1] 35/17
21/22 31/19 37/4 41/4 throughout [1] 4/20	32/8 36/12 38/16 40/22 44/18 updating [2] 2/9 40/3	where [21] 5/18 6/2 12/7 12/10 13/10 14/5 14/10 15/8 15/14 15/15
tie [1] 18/7	upgrades [2] 42/11 43/17	16/9 16/10 17/2 17/3 18/10 21/6
time [10] 13/23 21/11 21/13 27/14	Upper [1] 24/16	23/23 26/1 29/2 29/21 38/23
29/18 30/9 31/12 34/8 35/21 41/17	urgent [1] 36/4	Whereupon [1] 45/6
today [2] 4/16 27/16 together [2] 14/1 27/13	us [10] 3/7 3/20 10/23 13/18 15/13 15/16 16/16 17/16 19/17 40/16	whether [1] 37/19 which [13] 11/12 12/16 13/6 17/14
told [2] 21/3 27/14	use [7] 11/19 13/5 17/7 17/14 22/20	19/3 22/19 23/11 24/15 26/7 26/9
tonight [7] 2/9 3/11 4/19 5/6 5/13	22/22 23/13	34/9 36/4 36/5
9/17 44/22 tonight's [3] 2/4 4/11 9/22	used [1] 42/20 user [1] 8/19	while [5] 8/21 23/1 30/21 40/3 43/21 White [1] 42/19
too [4] 29/4 29/15 41/6 41/16	using [4] 26/6 29/19 33/11 43/3	who [5] 3/9 5/3 6/8 35/16 40/22
top [7] 8/12 14/18 15/9 17/18 20/5	utilize [1] 25/15	whole [2] 34/11 38/18
36/23 40/13	V	wide [1] 25/11
tough [1] 13/23 tourists [1] 35/2	vaguely [1] 36/3	widen [3] 7/23 8/1 14/6 widening [2] 11/6 20/10
towards [1] 15/3	Vanderwhacker [2] 11/20 17/11	width [1] 43/5
town [14] 2/12 6/6 7/14 8/12 13/7	variety [1] 35/3	Wild [2] 11/20 17/12
27/1 28/11 31/15 31/20 32/3 38/13 39/15 39/18 40/3	venues [1] 10/7 Vermont [1] 32/7	wilderness [3] 11/22 13/3 17/8
track [1] 8/11	vertical [1] 25/16	will [18] 3/9 3/14 4/21 5/14 5/22 7/2 8/18 9/3 13/18 14/3 14/23 16/15
tract [2] 41/8 41/22	very [12] 2/22 25/8 27/18 28/16 33/6	16/17 19/6 19/7 25/19 32/22 43/23
tractors [1] 16/16	36/11 38/11 42/8 42/13 42/23 43/9	windy [1] 36/14
tracts [1] 42/3 traditional [1] 2/11	43/11 via [1] 9/9	winter [5] 18/12 19/11 22/23 30/17 37/20
traffic [4] 15/20 15/23 16/4 19/22	views [1] 20/5	wintertime [1] 38/2
trail [40] 7/22 8/9 8/11 8/12 11/5	Village [5] 18/23 18/23 20/23 25/7	wish [1] 5/3
11/6 12/15 12/19 12/20 14/23 15/7 15/12 19/4 20/9 20/10 22/18 22/21	38/15 visitors [2] 10/20 23/13	within [1] 38/14 wobbly [1] 14/3
22/23 23/4 24/16 25/13 25/13 25/14	W	wonder [4] 33/19 34/14 35/6 35/21
25/19 25/22 25/23 25/23 26/7 26/8		wondering [2] 26/23 36/2
26/12 26/14 26/15 29/1 29/3 29/6	walk [1] 9/23 wall [1] 37/1	woods [1] 26/1
29/16 29/23 38/17 43/17 44/6 trails [36] 8/1 8/2 14/6 14/20 18/5	want [3] 21/9 32/5 40/7	word [1] 37/21 work [8] 22/5 24/17 27/4 31/21
18/7 22/10 22/11 22/11 22/13 23/10	wanted [1] 31/8	38/20 38/21 39/11 44/9

W worked [4] 22/12 22/14 24/10 24/12 working [4] 2/22 10/22 36/16 40/2 works [2] 24/15 38/18 worry [1] 31/22 worth [1] 35/23 would [39] 3/6 12/2 13/2 13/3 13/4 14/12 14/14 15/18 15/19 16/10 17/4 17/12 17/17 17/20 18/2 18/3 18/7 19/17 20/2 21/13 21/15 22/16 23/5 23/18 23/22 24/4 24/11 24/21 25/23 26/17 27/11 28/8 29/17 30/3 32/12 42/8 42/17 43/1 43/12 written [7] 5/15 5/18 9/2 9/4 9/8 21/10 44/23 wrong [1] 30/1 **XIV [1]** 9/1 year [5] 10/17 31/22 35/15 35/16 42/5 year-round [1] 10/17 **years [6]** 22/3 24/10 24/13 28/19 35/22 36/10 **York [5]** 1/13 1/20 7/1 31/17 46/4 you [50] you'll [1] 10/3 you're [10] 12/18 13/12 13/21 15/3 23/20 37/3 38/4 39/7 42/23 43/9 You've [1] 24/2 younger [1] 10/20 your [12] 3/20 5/8 5/9 9/17 9/18 21/17 29/20 37/7 43/1 43/9 43/16 43/17 **zip [6]** 12/2 18/14 18/18 30/22 39/2 39/3

Appendix 11 DGEIS Written Public Comments

Law Office of Sterling T. Goodspeed

Mailing Address:
P.O. Box 11
North Creek, NY 12853
scgstg@gmail.com

Sterling T. Goodspeed, Esq.

Susan C. Goodspeed Legal Assistant

January 24, 2018

Mr. Mike Pratt President/CEO ORDA 2634 Main St. Lake Placid, NY 12946

Re: Summer Operations/Public Hearing

Dear Mike:

We will be unable to attend tonight's public hearing due to a scheduling conflict but wanted to write to you to express our strongest possible support for the ORDA summer operation at the Ski Bowl. Between the two of us, dating back to 1991, we have operated four businesses within the North Creek area. These include a law firm, a newspaper, a grocery store and a laundromat. We are well aware of both the potential our region offers and the challenges doing business here can present.

ORDA's commitment to a summer operation builds on the growing partnership between the Authority, Town government and local businesses. Creating this venue during the summer season will add new vitality to our existing businesses and will likely attract other businesses to open shop. The proposal also builds off the important heritage that the Ski Bowl and North Creek have always shared with regards to the ski industry. It is fitting that summer operation at the Ski Bowl should provide such a crucial element of our long sought goal to become a four season destination community. The project also marks a welcome commitment to permit an ORDA operation on the edge of our Main Street business district and builds on the significance of the interconnect of the mountains completed several years ago.

Thank you for your time and attention in reviewing this correspondence.

Sterling P. Goodspeed

Very truly your

Susan C. Goodspeed

Office Location: Pearsall Real Estate Building 2361 State Route 28, Wevertown, NY 12886

From: Bob Hammond <BHammond@orda.org>
Sent: Wednesday, January 31, 2018 6:53 AM

To: Mark Taber; Kevin Franke **Subject:** FW: Rabbit Pond Trail

Follow Up Flag: Follow up Flag Status: Flagged

FYI

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

From: Rick and Anne Morse [mailto:morses2@gmail.com]

Sent: Tuesday, January 30, 2018 9:42 PM

To: Gore 2017 UMP comments < Gore 2017 UMP comments@orda.org>

Subject: Rabbit Pond Trail

I feel that the proposed

Gore Mountain Amendment to the

UMP does not recognize the importance of the Rabbit Pond Trail.

This is a trail which is used by a lot of people during all four seasons. Rabbit Pond is a pristine pond which has not been adversely impacted by human development. I personally worked to build this trail with Steve Ovitt, DEC Forest Ranger. I work to maintain this trail, along with other members of the Siamese Ponds Trail Improvement Society.

Where is there a map in the proposed amendment which shows the location of the Rabbit Pond Trail as well as the location of the proposed Gore ski trails?

Where does the proposed amendment describe how the Rabbit Pond Trail, and Rabbit Pond, will be impacted by the Gore development? What will be the setback of the Gore trail construction from Rabbit Pond?

I oppose the reclassification of the land from wild forest to intensive use unless the Rabbit Pond trail and Rabbit pond are not adversely affected.

Richard Morse

Total Control Panel Login

To: kfranke@thelagroup.com
From: bhammond@orda.org

Remove this sender from my allow list

I would like to echo the comments made by several other speakers at the Public Hearing on the 2018 Gore Mountain UMP update. As a hiker and back country skier, I have a great interest in this area. I am the Siamese Ponds Trail Improvement Society trail steward for the Schaefer Trail on Gore (named after my family), and have spent many days clearing trails in the Siamese Pond Wilderness so that they remain open for year round use. As an aside, my father also built and ran the first rope tow in New York State in the Historic Ski Bowl beginning in December 1935. Thus, all can understand my affinity for this beautiful and unique area affected by the plan.

I fully support the intentions of ORDA to increase recreational opportunities on Gore, and see many positive aspects to the plan. If completed there will be an increase in recreational and (much needed) related economic activity. However, I have are two concerns, mostly related to preserving the historic recreational opportunities that currently exist, and coordinating future ones.

The first is the need to keep development away from Rabbit Pond, the Rabbit Pond Trail, and its environs. Besides its historic value as one of the original "Ride Up, Slide Down" trails from the 1930s, this is a beautiful, quiet and pristine area that needs to be preserved. It is used by many and will continue to be a wonderful recreational resource for the town and all outdoor enthusiasts. I have not seen any topographic maps that show definitively where new facilities and trails will be located in relation to the Rabbit Pond trail. This should be a high priority so we can clearly see the plan, and then keep a **substantial buffer zone** between areas. I urge those involved in the planning to produce such a map as soon as possible.

The second concern is that of overall planning:

- Along with the Gore expansion plan, there are already plans afoot to expand hiking/biking trails in the Historic Ski Bowl. How do these fit in?
- The North Country National Scenic Trail now comes through the Bowl. This trail only passes through two towns in the Adirondack Park, and North Creek is one of them. Impact? How do we maximize benefit? How does it fit in?
- There are ongoing plans for Hut to Hut skiing in the area. Impact?
- Raymond Brook BC skiers frequently end their trips in the Ski Bowl on the Connector Trail. Impact?
- A NYS Museum of Skiing is planned for the Bowl. Has this been considered as part of the overall plan?

I have not seen anywhere this **nexus of recreational activity addressed as a whole**. It is a tremendous opportunity for the Town of Johnsburg and the Greater Gore Mountain Region, but the Gore Mountain UMP must completely address these issues for the benefit of all concerned.

Gregory J. Schaefer North River, NY 518-251-5451

From: Bob Hammond <BHammond@orda.org>
Sent: Thursday, February 01, 2018 4:20 PM

To: Kevin Franke; Mark Taber

Subject: FW: Comment on Gore Mt. Unit Management Plan

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

From: Richard Salz [mailto:rfs54@aol.com]
Sent: Thursday, February 01, 2018 12:47 PM

To: Gore_2017_UMP_comments < Gore_2017_UMP_comments@orda.org >

Subject: Comment on Gore Mt. Unit Management Plan

Dear Sir or Madam:

As an avid cross-country skier and hiker, I am writing to express my concern about the possible adverse impact to the Rabbit Pond Trail as a result of the proposed construction of a new downhill trail adjacent to Rabbit Pond. The draft UMP calling for the reclassification of the Rabbit Pond area from Wild Forest to Intensive Use fails to address the impact that the new downhill trail will have on the Rabbit Pond Trail. In a significant omission, the draft amendment does not even show the Rabbit Pond Trail on any of the maps.

The Cumulative Impact Analysis (Part C, Section III, Subsection K, pp. 6-7) incorrectly states that "[r]ecreational opportunities could be enhanced at both locations with the implementation of the proposed actions. This will result in a positive cumulative impact." No mention is made of the potential negative impact to the Rabbit Pond Trail or to Rabbit Pond itself by a new downhill trail.

Please note my opposition to the proposed reclassification if this will result in harm to the Rabbit Pond Trail or to Rabbit Pond.

Sincerely,

Richard Salz 171 Van Guilder Rd. Chestertown, NY 12817

Total Control Panel Login

To: kfranke@thelagroup.com Remove this sender from my allow list

From: bhammond@orda.org

From: Bob Hammond <BHammond@orda.org>
Sent: Friday, February 02, 2018 2:43 PM

To: Kevin Franke; Mark Taber

Subject: FW: Public Comment on the Gore Mountain UMP Draft Amendments - Rabbit Pond

Trail

Follow Up Flag: Flag for follow up

Flag Status: Flagged

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

From: Roy Keats [mailto:royskipaddle@gmail.com]

Sent: Friday, February 02, 2018 12:59 PM **To:** Bob Hammond < <u>BHammond@orda.org</u>> **Cc:** Keats < royskipaddle@gmail.com>

Subject: Public Comment on the Gore Mountain UMP Draft Amendments - Rabbit Pond Trail

Dear Mr. Hammond,

I feel that the proposed Gore Mountain Amendment to the

UMP does not recognize the importance of the Rabbit Pond Trail.

This is a trail which is used by many people during all four seasons. It is both a backcountry ski trail and a hiking trail. Rabbit Pond is a pristine pond which has not been adversely impacted by human development. I work to maintain this trail, along with other members of the Siamese Ponds Trail Improvement Society.

The proposed amendment does not have a map showing the location of the Rabbit Pond Trail and the location of the proposed Gore ski trails.

Where does the proposed amendment describe how the Rabbit Pond Trail, and Rabbit Pond, will be impacted by the Gore development? What will be the setback of the Gore trail construction from Rabbit Pond?

I oppose the reclassification of the land from wild forest to intensive use unless the Rabbit Pond Trail and Rabbit Pond are not adversely affected.

Sincerely,

Roy Keats 171 Garnet Lake Road Johnsburg, NY 12843

Total Control Panel <u>Login</u>

To: <u>kfranke@thelagroup.com</u> <u>Remove</u> this sender from my allow list

From: bhammond@orda.org

From: Bob Hammond <BHammond@orda.org>
Sent: Tuesday, February 06, 2018 7:28 AM

To: Kevin Franke; Mark Taber

Subject: FW: comment gore mountain unit management plan UMP 2018 Draft

Amendment/DGEIS

Follow Up Flag: Follow up Flag Status: Flagged

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

From: Robin Bell [mailto:robinb@ldeo.columbia.edu]

Sent: Sunday, February 04, 2018 5:37 PM **To:** Bob Hammond BHammond@orda.org>

Subject: comment gore mountain unit management plan UMP 2018 Draft Amendment/DGEIS

Dear Mr. Hammond,

I am writing in regards to the expansion of the gore mountain ski area to the west.

I frequently ski the schaefer trail from the halfway brook trailhead all the way into town along with a growing group of backcountry skiers.

Backcountry skiers of all ages have been enjoying this unique wilderness trail. the land that would be provided in exchange for this is not in anyway comparable.

North Creek is beginning to be known as a destination for backcountry skiers. People's eye light up when I describe this backcountry skiing to them.

It is an attraction to the region. The loss of this trail would be a setback for the town and the region.

In part to the attraction of the backcountry trails I have purchased land close to Gore and built a ski cabin. There are few wilderness backcountry trails in

New York that compare with the Schaefer/Rabbit Pond trails. My children have begun to use this unique resource and I hope my grandchildren will be able to enjoy the North County Wilderness experience.

Sincerely your,

Dr. Robin Elizabeth Bell 37 van houten field

west nyack ny 10994

V 845 - 365 - 8827

F 845 - 365 - 8179

C 845 - 729 - 8697

Total Control Panel <u>Login</u>

To: kfranke@thelagroup.com

Remove this sender from my allow list

From: bhammond@orda.org

From: Bob Hammond <BHammond@orda.org>
Sent: Tuesday, February 06, 2018 7:31 AM

To: Mark Taber; Kevin Franke

Subject: FW: Comment on the Gore Mountain UMP 2018 Draft Amendment/DGEIS

Follow Up Flag: Follow up Flag Status: Flagged

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

From: Coplan, Prof. Karl S. [mailto:kcoplan@law.pace.edu]

Sent: Sunday, February 04, 2018 5:28 PM **To:** Bob Hammond BHammond@orda.org>

Subject: Comment on the Gore Mountain UMP 2018 Draft Amendment/DGEIS

Dear Mr. Hammond:

I submit the following comment on the proposed 2018 Gore Mountain UMP/DGEIS Amendments, specifically in reference to the proposed reclassification of the Rabbit Pond Wild Forest Lands to Intensive Use. As an avid backcountry skier, I oppose the proposed reclassification.

The existing cross country ski trail connecting the Schaefer Trail via Rabbit Pond to the Raymond Brook/ Ski Bowl connector trail is a unique resource, and should be maintained in its current form. The DGEIS improperly discounts the value of this trail by saying that it is merely an "out and back" cross country ski trail. This ignores the potential connections to the Schaefer Trail from the top of the Raymond Brook ski trail. It also ignores the fact that the Rabbit Pond ski trail is not just a typical cross country ski trail - it is one of only a handful of trails in the Southern Adirondacks that has enough pitch to make it a challenging and exhilarating backcountry telemark skiing run. The drops just above Rabbit Pond and below the pond to the intersection with the Raymond Brook trail are the best drops for telemark skiing in the Gore region wild forest area.

Gore Mountain has plenty of groomed downhill trails, and the proposed reclassification would terminate a unique Adirondack wilderness ski opportunity for no apparent reason. A cynic might think that the only purpose of the reclassification seems to be to add monetary value to the private condominium development that would gain a "ski-in, ski-out" lift service. That is not a good reason to destroy a Wild Forest.

I am a regular visitor to the North Creek region, and have recently invested in property in North River specifically because of the backcountry ski opportunities in the region.

My home address is

Karl Coplan 37 Van Houten Fields West Nyack, NY 10994

I assume that e-mail submission of this comment is sufficient so that it will be included in the record. If you require a paper submission, please advise.

Thank you for your consideration,

Karl Coplan

Total Control Panel Login

To: kfranke@thelagroup.com Remove this sender from my allow list

From: bhammond@orda.org

From: Bob Hammond <BHammond@orda.org>
Sent: Tuesday, February 06, 2018 12:40 PM

To: Mark Taber; Kevin Franke **Subject:** FW: Comments - Gore UMP

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

----Original Message----

From: Richard Carlson [mailto:diccarlson@frontiernet.net]

Sent: Tuesday, February 06, 2018 12:30 PM To: Bob Hammond <BHammond@orda.org>

Cc: Johnsburg Supervisor < supervisor@johnsburgny.com>

Subject: Comments - Gore UMP

Greetings: These comments are for:

The 2017 Amendment to the 2002 Gore Mountain Unit Management Plan

My chief concern is the land swap - swapping Vanderwhacker Wild Forest Land for an insignificant portion of Intensive Use Land to become part of the Siamese Ponds Wilderness.

The current uses of this Wild Forest Parcel includes an intimate hiking/skiing/snowshoeing trail near Rabbit Pond. Offering the use of the proposed ski trail in the off season for hiking is of no importance since the nature of hiking on wide alpine ski trails is of limited and mostly shunned value. This area has a long history with backcountry skiers and it's loss would be paramount. The gain for increased trail development is minimal. This has no benefit except for the private development at Front Street. That said - this is the 10 year anniversary of "permits in place" for the Front Street development at the Ski Bowl. To date - 4 duplex units have been build with no additional development on the horizon.

The current Hudson (46er) lift has operated sporadically at best during the ski season in the last 10 years and was still not operating for the

2017-2018 season as of this writing. It did operate for a special "History Weekend" last summer as a scenic chairlift ride. It was well received and it could be a cornerstone of Summer Operations - EVEN WITH IT'S EXISTING PLACEMENT and operating constraints (ie running slow to accommodate loading/unloading).

There is a network of multiple use and mt. bike trails on adjacent Town of Johnsburg property. These trails need to operate as is - currently free to users and not be disrupted or displaced by future construction and structures like the zip coaster. The land ownership and lease/lessee structure is incredibly confusing with some of the land owned by the Town of Johnsburg leased to Gore/ORDA, and additional land is owned by Front Street and pending swap deals between the Town and Front Street makes even the best map reader confused.

Gore has had a non-existent to poor off-season profile with incredibly abbreviated lift schedules (just 10 days for 2017 Summer season). This in an environment that sees other Ski Areas garnering up to 40% of revenues in the off season. The chief summer entertainment is scenic chairlift or gondola rides with hiking and biking options if available.

This poor performance for the last 20 years is even more perplexing with one of the state's largest summer tourist venues just 30 minutes away in Lake George.

Quite frankly Gore's poor off-season activity leaves many workers in seasonal limbo seeking additional summer season employment to dovetail with their employment at Gore or leaving the recreation industry entirely for full time work.

Submitted February 6, 2018

Richard Carlson

--

Richard Carlson PO Box 73 North River, NY 12856 518-251-0829

Total Control Panel Login

To: <u>kfranke@thelagroup.com</u> <u>Remove</u> this sender from my allow list

From: bhammond@orda.org

From: Bob Hammond <BHammond@orda.org>
Sent: Tuesday, February 06, 2018 12:40 PM

To: Mark Taber; Kevin Franke **Subject:** FW: Gore UMP Comments

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

From: Brandon J. Himoff [mailto:brandon@himoff.com]

Sent: Tuesday, February 06, 2018 11:23 AM

To: Gore_2017_UMP_comments < Gore_2017_UMP_comments@orda.org>

Subject: Gore UMP Comments

As a member of the public, a regional business owner, and a member of our local business organizations, I applaud the strong effort that ORDA is making to keep these valuable assets in terrific condition. As times change, these facilities need to adapt and maintain their attraction. Looking carefully at these plans, I feel that they will significantly improve the potential of Gore to attract tourists. Any revenue brought in to the mountain will be accompanied by a significant multiplier in local spending, boosting and supporting many other local businesses and thereby expanding our local employment base. Especially critical are the season expanders such as the improvements in the ski bowl.

I would suggest that ORDA also consider that these capital investments must be accompanied by additional operating spending. By expanding the pumps, Gore will be able to make more snow which of course requires more groomer hours and more support. More lifts and more connectivity mean that more of the mountain can be operating, requiring appropriate staffing. The additional tourists will not only want more and better skiing, but better amenities on the mountain, especially including better and more diverse food offerings. The current food offerings and dining experience are significant detractors to our tourists, and improvements in this area are some of the most necessary but perhaps easiest to address. A change to the current food contractor and exploration of new vendors that are more appropriate to the desired mountain experience and who would be more accountable to ORDA should be considered.

Brandon Himoff

Total Control Panel <u>Login</u>

To: kfranke@thelagroup.com Remove this sender from my allow list

From: bhammond@orda.org

From: Bob Hammond <BHammond@orda.org>
Sent: Thursday, February 08, 2018 8:12 AM

To: Kevin Franke; Mark Taber

Subject: FW: Save the Rabbit Pond Area! Crucial to 4-Season Activities in North Creek

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

From: Judith Harper [mailto:juditheharper@gmail.com]

Sent: Wednesday, February 07, 2018 7:26 PM

To: Gore_2017_UMP_comments < <u>Gore_2017_UMP_comments@orda.org</u>> **Subject:** Save the Rabbit Pond Area! Crucial to 4-Season Activities in North Creek

ORDA's move to reclassify and acquire the Rabbit Pond Trail Area for Gore Mountain use jeopardizes North Creek's four-season use of open spaces for hikers and tourists.

North Creek and the town of Johnsburg depend on tourist dollars 12 months of the year. Ski tourism dollars flow in during a very limited number of weeks, and are solely dependent on frigid weather and natural snowfall. Snowmaking is limited, despite what Gore Mountain claims. The statistics show that the most ski dollars flow in when there is the most natural snow. Facts provided by Gore Mountain. (I'm a former

employee.)

North Creek and the entire region are in desperate need of FOUR-SEASON, LOW-COST tourist activities. We must maintain as much free, open to all open space as possible in the North Creek region. We don't have much hiking space in North Creek, yet it is the hamlet in Johnsburg which draws the most tourists. Take Note!

Last fall 2017 ORDA totally rejected the Town of Johnsburg what it reasonably requested. ORDA, when pressed, said it would offer ski tickets to residents, although most Johnsburg residents do not ski at Gore. Thanks, but no thanks.

This LAND GRAB is totally unacceptable to me, a 12-year resident of Johnsburg and a former owner of a business in Johnsburg, and a former member of the Chamber of Commerce.

The trails at Rabbit Pond--this pristine "wild" area--is worth far more to North Creek businesses and to Johnsburg residents than additional Gore Mountain trails and chairlifts, etc.

If Gore and ORDA wanted to acquire this land, they could have cooperated with the Town of Johnsburg last fall 2017. ORDA and Gore chose to ignore Johnsburg residents. But Gore Mountain and ORDA have never considered the needs of the residents of this area.

Judith E. Harper P.O. Box 122 293 Coulter Rd. Johnsburg, MA 12843 518-251-3006

Total Control Panel Login

To: <u>kfranke@thelagroup.com</u> Remove this sender from my allow list

From: bhammond@orda.org

From: Bob Hammond <BHammond@orda.org>
Sent: Thursday, February 08, 2018 8:12 AM

To: Kevin Franke; Mark Taber **Subject:** FW: Gore MT UMP comments

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

From: Julia West [mailto:juliawest60@gmail.com]
Sent: Wednesday, February 07, 2018 9:59 PM
To: Bob Hammond < BHammond@orda.org >

Subject: Gore MT UMP comments

Dear Mr. Hammond,

I'm writing in regard to the proposed 2018 Gore Mountain UMP/DGEIS Amendments, specifically in reference to the proposed reclassification of the Rabbit Pond Wild Forest Lands to Intensive Use. I am in strong opposition to the "land swap" that is being proposed. A large portion of Wild Forest Land would be added onto Gore for the development of trails, in trade for a much smaller portion near the Gore summit that would become part of the Siamese Ponds Wilderness area.

That small parcel is useless for public use, just as it is not useful for Gore to develop on it. It's a bad trade!

I am an avid backcountry skier, hiker, etc. The trail system near North Creek is unique and special, and many people enjoy the opportunity to ski there. It also gets good use as a hiking trail in summer (I've read the trail registers!).

It would be a shame to lose that to development. Hiking on a developed ski trail is just not fun - it's not the intimate woods experience that hikers want. And skiers would be cut off from some of the best backcountry terrain the southern Adirondacks has to offer.

The Hudson chair at "Little Gore" is rarely open. We just don't get enough snow. It has not been open yet this year (possibly today because of the snow), and we are well into February. Why does Little Gore need more trails? I don't see that it would attract more people. The development of Burnt Ridge, which opened a lot of terrain at Gore several years ago, doesn't even get a lot of skiers. To create those trails, a massive amount of clearing (and burying the trees) had to be done on some very beautiful land, destroying the original Schaefer trail that allowed for an incredible nature experience for hikers before it was lost.

The North Creek Ski Bowl does NOT need new trails! This land swap is extremely concerning to me- it is a BAD idea! It would be a real shame to lose that beautiful wilderness terrain.

I live in North River; this is my home. Please do not carry through with this land swap. The other improvements to the existing trails at the main mountain are all excellent ideas. Please keep the focus on improving what is already there, not adding more terrain and wasting my taxpayer dollars.

Thank you.

Sincerely,

Julia West 429 Harvey Rd North River, NY 12856 518-251-3930

Total Control Panel Login

To: <u>kfranke@thelagroup.com</u> <u>Remove</u> this sender from my allow list

From: bhammond@orda.org





BOARD OF DIRECTORS

February 9, 2018

ROBERT J. KAFIN

Chair

MICHAEL A. BETTMANN, M.D.

Vice-Chair

SARAH C. HATFIELD

Vice-Chair

DANIEL J. RYTERBAND

Treasurer

CHARLES D. CANHAM, Ph.D.

Secretary

EMILY M. BATESON

JILL CHOATE BEIER

DAVID E. BRONSTON

LIZA COWAN

GEORGINA CULLMAN, Ph.D.

THOMAS CURLEY

PHILIP R. FORLENZA ETHAN FRIEDMAN

CHRISTOPHER I GORAYER

KEVIN MCNULTY

SARAH J. MEYLAND. MS. JD

SHERRY NEMMERS

JUSTIN POTTER

MEREDITH M. PRIME

BRIAN RUDER

KATE RUSSELL

DOUGLAS SCHULTZ

LAUREL SKARBINSKI

DOUGLAS STEWART
CURTIS R. WELLING

ETHAN WINTER

EXECUTIVE DIRECTOR
WILLIAM C. JANEWAY



Robert W. Hammond, Director of Planning & Construction NYS Olympic Regional Development Authority Olympic Center, 2634 Main Street

Lake Placid, NY 12946

(Via electronic submission)

RE: Draft Amendments to the Gore Mountain and Whiteface Mountain Unit Management Plans

Dear Mr. Hammond,

On behalf of the Adirondack Council, I would like to thank you for the opportunity to offer the following comments on the *Draft Amendments to the Gore Mountain and Whiteface Mountain Unit Management Plans*. We appreciate the Olympic Regional Development Authority's (ORDA) efforts to conduct meaningful public outreach while taking questions and feedback on technical elements for the proposals. Given the important role these recreational facilities play in the Adirondack Park, the Adirondack Council supports ORDA's efforts to modernize the facilities, increase energy efficiency and improve infrastructure reliability, if the facilities, operations and improvements are legal and environmentally responsible.

In reviewing the detailed amendments for both the Gore Mountain (Gore Mtn.) and Whiteface Mountain (Whiteface Mtn.) Unit Managements Plans (UMPs), the Council believes that most of the proposed actions are warranted and necessary to maintain these Adirondack Park ski centers as world-class facilities. They need to be updated, funded and protected. As a whole the facilities complement our region's world-class wilderness areas and provide for beneficial recreational opportunities for a wide spectrum of users within our mountain communities. When designed and managed properly these facilities thrive in areas designated for intensive recreation in the largest Wilderness Park in the contiguous United States.

The details of these plans are of critical importance in realizing the recreational and economic benefits of the huge investment of taxpayer dollars in these facilities. The Council is concerned with some of the UMPs' important details that are missing, including: compliance with all constitutional requirements, net positive land reclassifications for Wilderness, regional planning, and other environmental considerations. The following comments note our concerns:

Whiteface Mtn. UMP

The Council suggests that select changes be made. Particularly, we request that glades be counted towards the total trail mileage allowed under the constitutional amendment. This would require ORDA to adjust the proposed management actions to adhere to the 25 mile limit. And, we request that an updated, detailed trail mileage calculation be included in the plan to reflect these changes.

Based on Article XIV of the NY Constitution, trail mileage and width requirements are applied to trails that are constructed and maintained. The constitutional amendment language does not exclude glades from the trail mileage calculation as this UMP suggests. Because glade skiing areas are maintained and treated as trails, they should be considered trails and counted towards total trail mileage. Glades are trails for the following reasons:

- 1. There is physical preparation, such as clearing of brush, or grubbing, and/or cutting of down logs or small growth;
- 2. Drawing 3 of the draft amendment illustrates where glades and trails less than 30 feet are located. These downhill routes are also advertised as trails available to the public in the map published for Whiteface visitors, serving as an invitation for public use (see map, below);
- 3. At various times the glades are posted as "open" or "closed;" and,
- 4. They are patrolled by Ski Patrol.

According to the draft UMP, there are 21.30 miles of currently constructed or approved to be constructed trails for this Intensive Use Area, and with this draft amendment, 0.89 miles of trails are proposed to be constructed. These numbers combined bring the total trail mileage to 22.19 – well within the 25 mile cap. However, according to this draft UMP, this number excludes glades from the total trail mileage, thus excluding 2.86 miles of trail; if the glade mileage is counted, the constitutional cap would be (very slightly) exceeded. There must be a modest change to honor the cap.

The Slides are not counted towards the constitutional limit within this draft. However, the Council believes that if the following criteria are met, a reasonable argument could be made that the Slides should count:

- a. Ski area maps and promotional materials show the slides as skiing terrain (as is currently done), and;
- b. They are listed as "open" or "closed," and/or;
- c. They are patrolled (by ski patrol), and/or;
- d. Access to the slides from the top lift and access from the bottom of the slides to other trails is maintained (cleared, etc.).

The constitutional protections of Article XIV are not such that they must be complied with when convenient and easy. They are not a policy, regulation or law. If there are issues with compliance, and therefore issues with the legality of proposed UMP amendments and ORDA plans, either the plans or the constitution (or both) must be changed.

We ask ORDA to be transparent with its methodology in determining ski trail mileage totals and how they relate to the overall mileage cap. A change in almost three miles of trails between the proposed 2018 and approved 2006 amendments is significant. Although these changes can be

reasonably attributed to improved aerial photos and technology, a map showing where the totals were miscalculated should be included for public review. ORDA should include a detailed account of the calculations it used to arrive at the total trail mileage, including which trails were chosen to be counted as one or two trails where two or more trails merge.

Gore Mtn. UMP

The two land reclassifications proposed in this UMP, though conceptual, raise questions over the amount of land requested for re-classification to Intensive Use or Wilderness. Specifically, the 33 acres of proposed Wilderness is insufficient compared to the 159 acres proposed to be classified as Intensive Use. When looking at past land reclassifications, there is a precedent to reclassify or add Wilderness lands to the Forest Preserve at a two to one, or greater, ratio. As a reference point, the NYCO land swap amendment passed with the state suggesting a ratio of seven to one, committing to add 1,500 to 2,000 acres or more of Wilderness to the Forest Preserve in a swap for 200 acres of Wild Forest coming out of the Forest Preserve. As the Council noted at the January 25th public hearing held for Whiteface Mtn. UMP, state land dedicated for Intensive Use should be combined with expanded Wilderness in the same general area for a net positive for Wilderness. If these reclassifications are pursued in a separate UMP process, a net positive for Wilderness approach should be employed.

Lastly, based on the trail mileage information provided within the Draft Generic Environmental Impact Statement, Gore Mtn. is well within its constitutionally allotted 40 miles of trail limit. The Council requests that ORDA clearly outline how it arrived at the listed 32.9 miles of total mileage within this UMP.

Additional Comments

In addition to those above, the Council provides the following comments for both UMPs:

- Compliance with Forever Wild: The facilities on state lands must comply with the strict and not always convenient requirements of the "Forever Wild" clause of the constitution. These requirements include: constitutional amendments that provide for functions and facilities at Whiteface and Gore that would not otherwise be allowed; adherence to the tightly restricted total miles and widths of downhill ski trails; and, no new tree cutting, clearing, disturbance, or expansion to year-round activities beyond what is now allowed without a constitutional amendment. (Under the constitution, all uses must be winter recreation based.)
- Planning Sensitive to other Regional Adirondack Needs: The state lands and operations at Whiteface Mtn. are part of a larger network of state lands, recreational uses, trails, and trailheads within the very popular High Peaks region. As the state looks at making important upgrades to the ORDA facilities, and simultaneously develops plans to manage the overuse of the Rt. 73 corridor and the High Peaks, planning needs to be coordinated. For example, one element of overlap could be relocation of parking for the Cascade and Porter Mountains on popular weekends to the Mt. Van Hoevenberg complex, as was done on an experimental basis on Columbus Day weekend in 2017.

- <u>Climate Smart, Energy Smart Models</u>: Climate change threatens to redefine Adirondack
 winter recreation as we now know it. The ORDA facilities can and should combat
 climate change and be showcases for visitors from across the country and around the
 world for the latest and best in climate smart renewable energy practices. The facilities
 should support the Governor's renewable energy goals and comply with Adirondack Park
 Agency policies.
- Additional Environmental Issues: These upgrades provide an opportunity to:
 - o Improve protections for fish and wildlife, including the rare Bicknell Thrush on Whiteface and Adirondack trout in the Ausable River.
 - o Address light pollution, by protecting rare dark skies and reducing light pollution (at the Mt Van Hoevenberg sliding center, for example).
 - o Protect water quality.
 - o Expand recycling.

As Intensive Use Areas, Whiteface Mtn. and Gore Mtn. ski centers are integral to the identity and vibrancy of the Adirondack Park. Environmental planning and review of these plans should not be "segmented" from other ORDA facilities. Together these facilities support our region's world class wilderness areas, provide for necessary recreational opportunities across a wide spectrum of users close to or within our mountain communities, and continue to be economic staples for many surrounding communities. The proposed management actions will allow these ORDA facilities to remain competitive and attractive to both professional and amateur users. And while we understand and appreciate the unique nature of these ski resorts, we must not forget that these lands are still Forest Preserve and as such are subject to a level of accountability, protection, and process that make the Adirondacks one of America's true conservation success stories and make our ski centers especially appealing to visitors because of the limited on-mountain development and the exceptional beauty of nature that is part of the skiing experience.

In closing, the Adirondack Council supports legal improvements to ORDA facilities and programs that comply with the constitution, the law and the legal protections which are what keep the Adirondacks a national treasure, a legacy we've inherited, and hold in trust for future generations.

Thank you for reviewing our comments. We appreciate the opportunities to meet leading up to this point, and suggest and hope that we can meet again to review these points and your proposed responses.

Sincerely,

William C. Janeway



From: Bob Hammond <BHammond@orda.org>
Sent: Monday, February 12, 2018 6:35 AM

To: Mark Taber; Kevin Franke **Subject:** FW: Rabbit pond trail.

Follow Up Flag: Follow up Flag Status: Flagged

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

----Original Message----

From: Dspzp [mailto:dspzp@aol.com] Sent: Friday, February 09, 2018 9:44 PM

To: Gore_2017_UMP_comments < Gore_2017_UMP_comments@orda.org>

Subject: Rabbit pond trail.

I am writing in response to the proposed changes to the Rabbit Pond trail expansion.

I am sure many others have written to express their concern in this matter an they have most definitely expressed it better.

My comment is that the Adirondack Park was designated to protect and preserve this wonderful wilderness we call the ADK.

We must all understand that growth will always adversely effect this wilderness. And I feel that there is a greater need to protect and preserve than to continually expand when I believe current facilities are under utilized.

Reclassifying and developing this land will remove one of the more pristine wilderness areas that may be accessed year round. Not just for a single purpose of skiing.

Also, without complete documentation and maps to outline what will actually be done, I can only strongly speak against this plan.

Thank you for your consideration.

Edward Cunningham

Total Control Panel <u>Login</u>

To: kfranke@thelagroup.com
From: bhammond@orda.org

Remove this sender from my allow list

Middlebury College Box 2493 14 Old Chapel Road Middlebury, VT 05753 sferguson@middlebury.edu

February 9, 2018

Michael Pratt Olympic Center 2634 Main St. Lake Placid, NY 12946

Dear Mr. Pratt,

Across the country, ski resorts are changing. Lifts are going faster, lodge food is getting better, villages are being developed, and year-round attractions are being built. These changes have helped the ski industry adapt to climate change and maintain corporate profits. As you consider how to develop the Adirondack resorts, I encourage you to also ask the question of to what extent *should* these resorts be developed. Governor Cuomo announced a vast and expensive expansion plan for Whiteface, Gore, and Mt. Van Hoevenberg, and some of these changes, such as updates to base lodge facilities, are long since overdue. Other amenities, however, seem to be unnecessary expansions that have no place within the Adirondacks.

The Adirondack resorts are unique because they are state-owned facilities focused on serving New York residents. They are not private corporations solely focused on increasing profits. In the winter, these resorts attract millions of visitors and are an important part of the Adirondack experience. However, in the summer, these resorts play a secondary role as people come from all over to hike the High Peaks and conquer the 46ers. When considering future developments, it is important that the developments are not seen as an addition to the individual resorts, but as added amenities to Adirondack Park as a whole. Route 73 is already overburdened during the summer months, and adding summer attractions to these ski resorts would increase the strain on the already existent infrastructure.

Specifically, I urge ORDA to consider how the proposed 'mountain coaster' fits within the culture of the Adirondacks. The Whiteface Mountain Unit Management Plan states that "Whiteface development will blend with the Adirondack environment and have minimum adverse impacts on surrounding state lands." The metal track of a mountain coaster would not blend into the Adirondack environment, but instead it would stick out like a sore thumb. The Adirondack environment, and especially publicly owned land, is fundamentally made up of wilderness. Constitutional exceptions already had to be made in order to allow ski resort infrastructure, and adding a mountain coaster would further contradict the 'forever wild' promise. A mountain coaster is a tamed and controlled way to experience nature. Riders would not be exposed to the real Adirondack wilderness, but instead they would glimpse nature from a man-made metal track. Outdoor recreation is an important part of the Adirondacks, but a

mountain coaster is something that belongs in an amusement park, not the Adirondack wilderness.

All this is not to say that Whiteface, Gore, and Van Hoevenberg should ignore profits, but instead of adding unnecessary infrastructure, they should focus on thriving within their ski industry niche. As other resorts continue to develop, Adirondack resorts should fall back on their skiing roots. They are located in a protected wilderness area that will never have the storefronts and commercial villages of Vail and Jackson Hole, yet the ski mountains themselves offer some of the best terrain east of the Mississippi. While a mountain coaster offers tempting profits, I urge you to embrace the ski culture that already exists at these mountains. Keep them as wild mountains nestled in the middle of the Adirondacks, and people will continue to come and enjoy these resorts for what they are—ski resorts where skiing comes first.

Sincerely,

Samuel Ferguson

From: Bob Hammond <BHammond@orda.org>
Sent: Monday, February 12, 2018 6:35 AM

To: Mark Taber; Kevin Franke **Subject:** FW: Rabbit Pond Trail

Follow Up Flag: Follow up Flag Status: Flagged

Robert W. Hammond Director of Environmental, Planning and Construction NYS Olympic Regional Development Authority (518) 302-5332

CONFIDENTIALITY NOTE: This message is intended exclusively for the party or parties to whom it is addressed. This communication may contain information that is proprietary, privileged or confidential, or otherwise legally exempt from disclosure. If you are not one of the named addressees, you are not authorized to read, print, retain, copy or disseminate this message or any part of it. If you have received this message in error, please notify the sender immediately by e-mail and delete/destroy all copies of the message.

----Original Message----

From: Allison St Pierre [mailto:allison1@nycap.rr.com]

Sent: Friday, February 09, 2018 9:31 PM

To: Gore_2017_UMP_comments < Gore_2017_UMP_comments@orda.org>

Subject: Rabbit Pond Trail

Hello,

I am writing in response to the proposal by ORDA to reclassify the Rabbit Pond area from Vanderwacker Mountain Forest Preserve to Gore Mountain Intensive Use. I am in disagreement with this proposal, as it will adversely impact a pristine pond and an area of preserve unnecessarily.

Currently Gore has many underutilized areas, such as trails that do not open for most, or all of the season. Before expanding into lands that should remain protected, Gore Mountain should put those resources into the area's currently delegated for this use.

The public should have access to a map clearly outlining the location of proposed areas to be reclassified. Another concern is how would this expansion be staffed? Additional parking, where would this be? I feel Gore must consider expansion within it's current boundaries, expand existing trails, staff and open all trails, and configure trails to travel around the mountain, prior to impacting protected lands, that are precious to maintaining the integrity of the Adirondack Park Preserve.

Thank you for considering the alternate options.

Kindly, Allison St. Pierre Bakers Mills, NY

Total Control Panel <u>Login</u>

To: <u>kfranke@thelagroup.com</u> <u>Remove</u> this sender from my allow list

From: bhammond@orda.org

Appendix 12 DGEIS Comments and Responses to Comments

Responses to Public Comments Regarding the 2018 Amendment to the 2002 Gore Mountain Unit Management Plan and Draft Generic Environmental Impact Statement

Comment Topics

- 1. Suggested Land Reclassification Including Rabbit Pond Trail
- 2. Planning for Gore Mountain and North Creek Ski Bowl
- 3. Management Actions and Goals
- 4. Constitutional Limits
- 5. Regional Planning
- 6. Renewable Energy
- 7. Project Support

1. SUGGESTED LAND RECLASSIFICATION INCLUDING RABBIT POND TRAIL

(1.A) Richard Morse, January 30, 2018

I feel that the proposed Gore Mountain Amendment to the UMP does not recognize the importance of the Rabbit Pond Trail.

This is a trail which is used by a lot of people during all four seasons. Rabbit Pond is a pristine pond which has not been adversely impacted by human development. I personally worked to build this trail with Steve Ovitt, DEC Forest Ranger. I work to maintain this trail, along with other members of the Siamese Ponds Trail Improvement Society.

Where is there a map in the proposed amendment which shows the location of the Rabbit Pond Trail as well as the location of the proposed Gore ski trails?

Where does the proposed amendment describe how the Rabbit Pond Trail, and Rabbit Pond, will be impacted by the Gore development? What will be the setback of the Gore trail construction from Rabbit Pond?

I oppose the reclassification of the land from wild forest to intensive use unless the Rabbit Pond trail and Rabbit pond are not adversely affected.

Response: The suggested land reclassification cannot take place through the adoption of the proposed Gore Mountain Unit Management Plan Amendment. The following explanation appears on page iii of the Executive Summary of the Draft Unit Management Plan Amendment/DEIS:

"(Note: The Adirondack Park Agency cannot find that a UMP Amendment proposing management actions on lands to be reclassified conforms to the Adirondack Park State Land Master Plan (APSLMP) before the land is reclassified. First, the Agency must receive a request to reclassify, accompanied by a UMP for the proposed Intensive Use lands. The Agency must follow SEQRA regulations regarding public notice and comment and must hold hearings inside and outside the Adirondack Park on the request to reclassify, pursuant to the APSLMP. After notice, comment and hearings, the reclassification proposals would be presented to the Agency for a recommendation to the Governor for approval of the classification. The process culminates in the Governor's action on that recommendation. This UMP Amendment does not assume that a reclassification request will be

approved and does not authorize any actions on lands requested to be reclassified, based on a proposed future classification. The actual request for reclassification and a UMP Amendment for those actions on the lands proposed for reclassification would be presented separately from this UMP Amendment. Discussion of actions on those lands in this UMP is conceptual only, and those actions cannot be authorized by this UMP Amendment.)"

The Rabbit Pond Trail was among the early ski trails created in the North Creek/North River area in the 1930's and 1940's. The circa 1940's map on the following page entitled "Precise Ski Data of North Creek, N.Y., A Stone's Throw from Train to Tow" (Figure 1) shows the intermediate Rabbit Pond Trail located at the "Village Slopes". The trail and Rabbit Pond itself also appear on the 1958 USGS map of the area shown on Figure 2.

Figure 3 shows the current mapping of the Rabbit Pond Trail, the 1958 USGS mapping of the Rabbit Pond Trail and the UMP-proposed ski trail. Mapping of the current Rabbit Pond Trail was produced from GPS data collected by Wilderness Property Management Inc. (Steve Ovitt) and mapped by Warren County GIS Department (Ski Bowl Park 2017 Smart Growth Grant Long Trail to Little Gore Summit). Approximately 600 feet of the existing Rabbit Pond Trail would be within or very near the proposed ski trail.


Figure 4 shows how this section of the existing Rabbit Pond Trail could be easily relocated slightly to the north and away from the proposed ski trail where it would pass over terrain similar to what is currently crossed. Figure 4 shows the area within which the trail could be relocated. ORDA will work with NYSDEC, Steve Ovitt and members of the local hiking and backcountry skiing community to select the best Rabbit Pond Trail location within this area, including a location that provides adequate setbacks from the proposed ski trail.

Creation of the alpine trail and relocation of the section of Rabbit Pond Trail are not anticipated to cause any significant adverse impacts to the ecology of Rabbit Pond. Water quality within the pond will not be impacted. Data in previous UMP's have demonstrated that creation of ski trails in previously wooded areas do not impact nutrient and solids levels in nearby receiving waters. Data in previous UMP's have also demonstrated that snowmaking within a drainage basin does not significantly alter rates of stormwater runoff. The pond itself will not be physically affected. The mapping in Figure 4 shows that both the ski trail and the hiking trail will be no closer to the pond than what currently exists.

(1.B) Richard Salz, February 1, 2018

As an avid cross-country skier and hiker, I am writing to express my concern about the possible adverse impact to the Rabbit Pond Trail as a result of the proposed construction of a new downhill trail adjacent to Rabbit Pond. The draft UMP calling for the reclassification of the Rabbit Pond area from Wild Forest to Intensive Use fails to address the impact that the new downhill trail will have on the Rabbit Pond Trail. In a significant omission, the draft amendment does not even show the Rabbit Pond Trail on any of the maps.

The Cumulative Impact Analysis (Part C, Section III, Subsection K, pp. 6-7) incorrectly states that "[r]ecreational opportunities could be enhanced at both locations with the implementation of the proposed actions. This will result in a positive cumulative impact." No mention is made of the potential negative impact to the Rabbit Pond Trail or to Rabbit Pond itself by a new downhill trail.





Landscape Architecture & Engineering P.C.

O Long Alley
aratoga Springs
IY 12866

Landscape Architecture & Engineering P.C.

People Purpose Place.
p: 518/587-6180
f: 518/587-0180

Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law.

(2) the LA group 2017



Olympic Regional Development Authority

2634 Main Street Lake Placid, New York 12946




Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

Drawing Title

North Creek Ski Map 1940's Date: 02/16/2018 Project No: 201537.01

Figure:

1





© the LA group 2017

DEVELOPMENT AUTHORITY p: 518/587-8100 f: 518/587-0180 Unauthorized alteration or addition to this document is a violation of Section 7209 of the New York State Education Law.

Olympic Regional **Development Authority** 2634 Main Street Lake Placid, New York 12946




Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement

1958 USGS Map Gore Mountain Area 02/16/2018 201537.01

2

Figure:







Olympic Regional **Development Authority**

2634 Main Street Lake Placid, New York 12946




Gore Mountain: 2018 Unit Management Plan Amendment & Final Generic Environmental Impact Statement





Figure 3



Please note my opposition to the proposed reclassification if this will result in harm to the Rabbit Pond Trail or to Rabbit Pond.

Response: See the response to substantively similar comment 1.A.

(1.C) Gregory Schaeffer, February 1, 2018 (via e-mail)

I would like to echo the comments made by several other speakers at the Public Hearing on the 2018 Gore Mountain UMP update. As a hiker and back country skier, I have a great interest in this area. I am the Siamese Ponds Trail Improvement Society trail steward for the Schaefer Trail on Gore (named after my family), and have spent many days clearing trails in the Siamese Pond Wilderness so that they remain open for year round use. As an aside, my father also built and ran the first rope tow in New York State in the Historic Ski Bowl beginning in December 1935. Thus, all can understand my affinity for this beautiful and unique area affected by the plan.

I fully support the intentions of ORDA to increase recreational opportunities on Gore, and see many positive aspects to the plan. If completed there will be an increase in recreational and (much needed) related economic activity. However, I have are two concerns, mostly related to preserving the historic recreational opportunities that currently exist, and coordinating future ones.

The first is the need to keep development away from Rabbit Pond, the Rabbit Pond Trail, and its environs. Besides its historic value as one of the original "Ride Up, Slide Down" trails from the 1930s, this is a beautiful, quiet and pristine area that needs to be preserved. It is used by many and will continue to be a wonderful recreational resource for the town and all outdoor enthusiasts. I have not seen any topographic maps that show definitively where new facilities and trails will be located in relation to the Rabbit Pond trail. This should be a high priority so we can clearly see the plan, and then keep a substantial buffer zone between areas. I urge those involved in the planning to produce such a map as soon as possible.

Response: See the response to substantively similar comment 1.A, including the accompanying mapping.

(1.D) Roy Keats, February 2, 2018

I feel that the proposed Gore Mountain Amendment to the UMP does not recognize the importance of the Rabbit Pond Trail.

This is a trail which is used by many people during all four seasons. It is both a backcountry ski trail and a hiking trail. Rabbit Pond is a pristine pond which has not been adversely impacted by human development. I work to maintain this trail, along with other members of the Siamese Ponds Trail Improvement Society.

The proposed amendment does not have a map showing the location of the Rabbit Pond Trail and the location of the proposed Gore ski trails. Where does the proposed amendment describe how the Rabbit Pond Trail, and Rabbit Pond, will be impacted by the Gore development? What will be the setback of the Gore trail construction from Rabbit Pond?

I oppose the reclassification of the land from wild forest to intensive use unless the Rabbit Pond Trail and Rabbit Pond are not adversely affected.

Response: See the response to substantively similar comment 1.A, including the accompanying mapping.

(1.E) Robin Bell, February 4, 2018

I am writing in regards to the expansion of the gore mountain ski area to the west.

I frequently ski the schaefer trail from the halfway brook trailhead all the way into town along with a growing group of backcountry skiers. Backcountry skiers of all ages have been enjoying this unique wilderness trail. the land that would be provided in exchange for this is not in anyway comparable. North Creek is beginning to be known as a destination for backcountry skiers. People's eye light up when I describe this backcountry skiing to them. It is an attraction to the region. The loss of this trail would be a setback for the town and the region.

In part to the attraction of the backcountry trails I have purchased land close to Gore and built a ski cabin. There are few wilderness backcountry trails in New York that compare with the Schaefer/Rabbit Pond trails. My children have begun to use this unique resource and I hope my grandchildren will be able to enjoy the North County Wilderness experience.

Response: None of the actions proposed in the 2018 UMP Amendment will affect the Schaeffer trail. See the response to substantively similar comment 1.A regarding the Rabbit Pond Trail.

From the overall perspective of the attractiveness of the area's backcountry character and the benefits that are derived therefrom, ORDA believes that the relocation of +/- 600 feet of one trail within a network that consists of miles of interconnected trails will not cause a significant impact

(1.F) Karl Coplan, February 4, 2018

I submit the following comment on the proposed 2018 Gore Mountain UMP/DGEIS Amendments, specifically in reference to the proposed reclassification of the Rabbit Pond Wild Forest Lands to Intensive Use. As an avid backcountry skier, I oppose the proposed reclassification.

The existing cross country ski trail connecting the Schaefer Trail via Rabbit Pond to the Raymond Brook/ Ski Bowl connector trail is a unique resource, and should be maintained in its current form. The DGEIS improperly discounts the value of this trail by saying that it is merely an "out and back" cross country ski trail. This ignores the potential connections to the Schaefer Trail from the top of the Raymond Brook ski trail. It also ignores the fact that the Rabbit Pond ski trail is not just a typical cross country ski trail - it is one of only a handful of trails in the Southern Adirondacks that has enough pitch to make it a challenging and exhilarating backcountry telemark skiing run. The drops just above Rabbit Pond and below the pond to the intersection with the Raymond Brook trail are the best drops for telemark skiing in the Gore region wild forest area.

Gore Mountain has plenty of groomed downhill trails, and the proposed reclassification would terminate a unique Adirondack wilderness ski opportunity for no apparent reason. A cynic might think that the only purpose of the reclassification seems to be to add monetary value to the private

condominium development that would gain a "ski-in, ski-out" lift service. That is not a good reason to destroy a Wild Forest.

I am a regular visitor to the North Creek region, and have recently invested in property in North River specifically because of the backcountry ski opportunities in the region.

Response: See the response to substantively similar comment 1.A that describes the relocation of a small section of the Rabbit Pond Trail. The remainder of the trail would remain unchanged.

Also, see the second part of the previous response regarding the proposed action in the context of the overall area trail network. ORDA believes that the proposed conceptual action will not cause significant economic or experiential issues.

(1.G) Richard Carlson, February 6, 2018

My chief concern is the land swap - swapping Vanderwhacker Wild Forest Land for an insignificant portion of Intensive Use Land to become part of the Siamese Ponds Wilderness.

The current uses of this Wild Forest Parcel includes an intimate hiking/skiing/snowshoeing trail near Rabbit Pond. Offering the use of the proposed ski trail in the off season for hiking is of no importance since the nature of hiking on wide alpine ski trails is of limited and mostly shunned value. This area has a long history with backcountry skiers and it's loss would be paramount. The gain for increased trail development is minimal. This has no benefit except for the private development at Front Street. That said - this is the 10 year anniversary of "permits in place" for the Front Street development at the Ski Bowl. To date - 4 duplex units have been build with no additional development on the horizon.

Response: See the response to substantively similar comment 1.A.

(1.H) Judith Harper, February 7, 2018

ORDA's move to reclassify and acquire the Rabbit Pond Trail Area for Gore Mountain use jeopardizes North Creek's four-season use of open spaces for hikers and tourists.

North Creek and the town of Johnsburg depend on tourist dollars 12 months of the year. Ski tourism dollars flow in during a very limited number of weeks, and are solely dependent on frigid weather and natural snowfall. Snowmaking is limited, despite what Gore Mountain claims. The statistics show that the most ski dollars flow in when there is the most natural snow. Facts provided by Gore Mountain. (I'm a former employee.)

North Creek and the entire region are in desperate need of FOUR-SEASON, LOW-COST tourist activities. We must maintain as much free, open to all open space as possible in the North Creek region. We don't have much hiking space in North Creek, yet it is the hamlet in Johnsburg which draws the most tourists. Take Note!

Last fall 2017 ORDA totally rejected the Town of Johnsburg what it reasonably requested. ORDA, when pressed, said it would offer ski tickets to residents, although most Johnsburg residents do not ski at Gore. Thanks, but no thanks.

This LAND GRAB is totally unacceptable to me, a 12-year resident of Johnsburg and a former owner of a business in Johnsburg, and a former member of the Chamber of Commerce.

The trails at Rabbit Pond--this pristine "wild" area--is worth far more to North Creek businesses and to Johnsburg residents than additional Gore Mountain trails and chairlifts, etc.

If Gore and ORDA wanted to acquire this land, they could have cooperated with the Town of Johnsburg last fall 2017. ORDA and Gore chose to ignore Johnsburg residents. But Gore Mountain and ORDA have never considered the needs of the residents of this area.

Judith E. Harper

Response: See the response to substantively similar comment 1.A.

(1.I) Julia West, February 7, 2018

I'm writing in regard to the proposed 2018 Gore Mountain UMP/DGEIS Amendments, specifically in reference to the proposed reclassification of the Rabbit Pond Wild Forest Lands to Intensive Use. I am in strong opposition to the "land swap" that is being proposed. A large portion of Wild Forest Land would be added onto Gore for the development of trails, in trade for a much smaller portion near the Gore summit that would become part of the Siamese Ponds Wilderness area.

That small parcel is useless for public use, just as it is not useful for Gore to develop on it. It's a bad trade!

I am an avid backcountry skier, hiker, etc. The trail system near North Creek is unique and special, and many people enjoy the opportunity to ski there. It also gets good use as a hiking trail in summer (I've read the trail registers!).

It would be a shame to lose that to development. Hiking on a developed ski trail is just not fun - it's not the intimate woods experience that hikers want. And skiers would be cut off from some of the best backcountry terrain the southern Adirondacks has to offer.

Response: See the response to substantively similar comment 1.A.

Additionally, the land proposed to be added to the Siamese Pond Wilderness Area has high natural resource value with its high elevation spruce fir habitat favored by a number of species including Bicknell's thrush.

(1.J) Edward Cunningham, February 9, 2018

I am writing in response to the proposed changes to the Rabbit Pond trail expansion.

I am sure many others have written to express their concern in this matter an they have most definitely expressed it better.

My comment is that the Adirondack Park was designated to protect and preserve this wonderful wilderness we call the ADK.

We must all understand that growth will always adversely effect this wilderness. And I feel that there is a greater need to protect and preserve than to continually expand when I believe current facilities are under utilized.

Reclassifying and developing this land will remove one of the more pristine wilderness areas that may be accessed year round. Not just for a single purpose of skiing.

Also, without complete documentation and maps to outline what will actually be done, I can only strongly speak against this plan.

Response: See the response to substantively similar comment 1.A including the accompanying mapping.

(1.K) Alison St. Pierre, February 9, 2018

I am writing in response to the proposal by ORDA to reclassify the Rabbit Pond area from Vanderwacker Mountain Forest Preserve to Gore Mountain Intensive Use. I am in disagreement with this proposal, as it will adversely impact a pristine pond and an area of preserve unnecessarily.

Currently Gore has many underutilized areas, such as trails that do not open for most, or all of the season. Before expanding into lands that should remain protected, Gore Mountain should put those resources into the area's currently delegated for this use.

The public should have access to a map clearly outlining the location of proposed areas to be reclassified. Another concern is how would this expansion be staffed? Additional parking, where would this be? I feel Gore must consider expansion within it's current boundaries, expand existing trails, staff and open all trails, and configure trails to travel around the mountain, prior to impacting protected lands, that are precious to maintaining the integrity of the Adirondack Park Preserve.

Thank you for considering the alternate options.

Response: See the response to substantively similar comment 1.A and accompanying mapping regarding the realignment of a small section of the Rabbit Pond Trail. It is not anticipated that the relocation of Lift 12 and the addition of some small sections of ski trail will result in significant increased demands on staffing or for parking.

(1.L) William Janeway (Adirondack Council), February 9, 2018

The two land reclassifications proposed in this UMP, though conceptual, raise questions over the amount of land requested for re-classification to Intensive Use or Wilderness. Specifically, the 33 acres of proposed Wilderness is insufficient compared to the 159 acres proposed to be classified as Intensive Use. When looking at past land reclassifications, there is a precedent to reclassify or add Wilderness lands to the Forest Preserve at a two to one, or greater, ratio. As a reference point, the NYCO land swap amendment passed with the state suggesting a ratio of seven to one, committing to add 1,500 to 2,000 acres or more of Wilderness to the Forest Preserve in a swap for 200 acres of Wild Forest coming out of the Forest Preserve. As the Council noted at the January 25th public hearing held for Whiteface Mtn. UMP, state land dedicated for Intensive Use should be combined with expanded Wilderness in the same

general area for a net positive for Wilderness. If these reclassifications are pursued in a separate UMP process, a net positive for Wilderness approach should be employed.

Response: The referenced past land reclassifications, including the "NYCO land swap", involved amendments to the NYS Constitution. No such constitutional amendment is required for the land reclassification suggested in the UMP. The referenced NYCO land swap also involved taking lands out of the Forest Preserve. Under the suggested land reclassification, no lands would be taken out of the Forest Preserve.

(1.M) Rick Morris, Public Hearing Transcript pp. 22-23

The Rabbit Pond Ski Trail gets a lot of use spring, summer, fall and winter. It's an existing trail for quite a while now. And I just think there should be some way to both expand Gore and to protect the existing trail and to protect Rabbit Pond. And that's what I would like to see. And what I have, I have a map here of the proposed expansion of Gore into the Rabbit Pond area and I have a map of the existing trails in the Rabbit Pond area, which I was able to get from North Creek for visitors to North Creek to use. But what I haven't seen, and maybe this is my fault, in the UMP, I haven't seen a map showing both right on the same map and showing how the proposed new development would impact the existing trails. And it seems like, if you're going to put new trails in and have them coexist with existing trails, it would be important to be able to see where they both lie.

Response: See the response (and accompanying mapping) to substantively similar comment 1.A.

(1.N) Dick Carlson, Public Hearing Transcript pp. 25-27

The Village of North Creek has very few hiking opportunities. And I have to discount hiking on ski trails and hiking on wide areas. There's really three main trails. The Schaeffer Trail, the Rabbit Pond Trail and the Raymond Brook Trail. And to, you know, utilize one little bit of added vertical for those trails that come down from the Rabbit Pond area, I think is misguided, especially if it will eliminate the Rabbit Pond Trail from hiking, snowshoeing and skiing in season. It's really a delightful trail. And it's an intimate hiking trail, like a regular trail you would see in the woods where the trees are quite close to you on both sides. So it's an important consideration, as well. And the Hamlets to Hut Initiative is using the Raymond Brook Trail, which is right adjacent to the Rabbit Pond Trail, for their premiere trip, which is supposed to begin this spring. And, also, the North Country National Scenic Trail is also – I think the signs are up already. The Raymond Brook Trail is part of that. And, again, the Rabbit Pond Trail teases into all this and to have that not be available anymore would be, again, I think misguided. The question I had, and I know that Crikelair property is some of the Alpine Trails that are proposed that are already approved. And I'm wondering, is this development on Crikelair's property? Is it Town of Johnsburg? Is it going to be ORDA property? How is that all going to work?

Response: See the response to substantively similar comment 1.A regarding the continued use of Rabbit Pond Trail.

The involved areas were shown on Draft UMP/GEIS Figure 2, New Management Actions (North), and are as follows:

- Proposed Trail 12-L: currently Wild Forest land connecting to currently Intensive Use land
- Proposed Trail 12-M: currently Wild Forest connecting to currently private land to become Town land

- Proposed Trail 12-A: currently Wild Forest Land
- Proposed Trails 12I-A and 12J-A: currently private land to become Town Land.

(1.0)Jill Broderick, Public Hearing Transcript pp.27-28

I do have my reservations about the Rabbit Pond reclassification of that land, only because it's sensitive. A lot of people enjoy it just the way it is and I don't think it's -- I'm not sure if it's feasible, so – I haven't seen the numbers and I don't really understand the realignment of the lift.

Response: See the response to substantively similar comment 1.A.

(1.P) Scott Robertson, Public Hearing Transcript pp. 28-30

I really hope you guys can move the trail either back to where you originally had it or put in a trail -- I don't really like this idea too much, but if we have to compromise, maybe put in another trail to move around so we don't lose Rabbit Pond. I'd hate to lose this trail. I think it would be a big mistake. What I did, I spent a lot of time using typographical maps and tried to overlay your maps on there to see exactly where the trails went, and it looked to me like we're going to be losing part of the trail. Maybe I'm wrong about that, but if we do the proposal, that's what it looks like to me. And I think that would be a huge mistake.

Response: See the response to substantively similar comment 1.A regarding the continued use of Rabbit Pond Trail including a section of relocated trail.

(1.Q) Julie West, Public Hearing Transcript p. 30

The summer recreation idea at Little Gore I think is really exciting. And right at Little Gore we have these awesome hiking trails and biking trails, so if you take the portions – the Rabbit Pond area that the everyone is concerned about and make it a winter area, it kind of takes the glimmer out of the summer recreational opportunities that maybe some of the family could be doing while the others are on the zip lines.

Response: See the response to substantively similar comment 1.A regarding the continued use of Rabbit Pond Trail.

(1.R) Katy Nightengale, Public Hearing Transcript p. 40

I have concerns about the land swap. I have skied those trails and they are really awesome. And there are already planned trails in existence to come down from the top of the Hudson Chair. I see economic development from both Gore and what they're doing for us at the main mountain and at the Ski Bowl, but I also see what's becoming this huge backcountry draw to ski backcountry. And I hate to lose those backcountry trails to be not accessible anymore for somebody who wants to ski up to ski down.

Response: See the response to substantively similar comment 1.A regarding the continued use of Rabbit Pond Trail.

(1.S) Peter Bauer (Protect the Adirondacks), Public Hearing Transcript p. 41

We, too, have a lot of concerns about the land swap and the Rabbit Pond tract. We're not sure that's the best way to go and we think there's some major issues that need to be looked at that we'll put in our comments. It has to do with backcountry skiing and it has to do with – we think there's some legal issues there, too, with the land that was designated at the time of the constitutional amendment that wasn't part of it. We're not sure it can be added in. So we think there's some issues to look at with the Rabbit Pond tract.

Response: See the response to substantively similar comment 1.A regarding the continued use of Rabbit Pond Trail.

It is not clear from the comment what "legal issues" there may be. Rabbit Pond Trail is located on the east flank of Pete Gay Mountain. Article XIV of the NYS Constitution expressly allows for ski trails "on the slopes of Gore and Pete Gay mountains in Warren County". The attached Figure 5, Mountains Near North Creek, shows Gore Mountain, Pete Gay Mountain and South Mountain.

2. PLANNING FOR GORE MOUNTAIN AND SKI BOWL

(2.A) Gregory Schaeffer February 1, 2018 (via e-mail)

The second concern is that of overall planning:


- Along with the Gore expansion plan, there are already plans afoot to expand hiking/biking trails in the Historic Ski Bowl. How do these fit in?
- The North Country National Scenic Trail now comes through the Bowl. This trail only passes through two towns in the Adirondack Park, and North Creek is one of them. Impact? How do we maximize benefit? How does it fit in?
- There are ongoing plans for Hut to Hut skiing in the area. Impact?
- Raymond Brook BC skiers frequently end their trips in the Ski Bowl on the Connector Trail. Impact?
- A NYS Museum of Skiing is planned for the Bowl. Has this been considered as part of the overall plan?

I have not seen anywhere this nexus of recreational activity addressed as a whole. It is a tremendous opportunity for the Town of Johnsburg and the Greater Gore Mountain Region, but the Gore Mountain UMP must completely address these issues for the benefit of all concerned.

Response: All ORDA improvements in Ski Bowl Park will be constructed in accordance with the 2017 Agreement between the Town of Johnsburg and ORDA, a copy of which is included in Section 4 of Part B of the draft UMP Amendment/GEIS. Other than the short section of Rabbit Pond Trail discussed previously, there does not appear to be any conflicts between the currently proposed ORDA development activities and existing and future Town use of Ski Bowl Park.

(2.B) Richard Carlson, February 6, 2018

The current Hudson (46er) lift has operated sporadically at best during the ski season in the last 10 years and was still not operating for the 2017-2018 season as of this writing. It did operate for a special "History Weekend" last summer as a scenic chairlift ride. It was well received and it could be a cornerstone of Summer Operations - EVEN WITH IT'S EXISTING PLACEMENT and operating constraints



(ie running slow to accommodate loading/unloading).

There is a network of multiple use and mt. bike trails on adjacent Town of Johnsburg property. These trails need to operate as is - currently free to users and not be disrupted or displaced by future construction and structures like the zip coaster. The land ownership and lease/lessee structure is incredibly confusing with some of the land owned by the Town of Johnsburg leased to Gore/ORDA, and additional land is owned by Front Street and pending swap deals between the Town and Front Street makes even the best map reader confused.

Gore has had a non-existent to poor off-season profile with incredibly abbreviated lift schedules (just 10 days for 2017 Summer season). This in an environment that sees other Ski Areas garnering up to 40% of revenues in the off season. The chief summer entertainment is scenic chairlift or gondola rides with hiking and biking options if available. This poor performance for the last 20 years is even more perplexing with one of the state's largest summer tourist venues just 30 minutes away in Lake George.

Quite frankly Gore's poor off-season activity leaves many workers in seasonal limbo seeking additional summer season employment to dovetail with their employment at Gore or leaving the recreation industry entirely for full time work.

Response: The proposed development activities at the Ski Bowl are geared to greatly enhancing summer visitation. The draft UMP Amendment/GEIS Section 2.B, Purpose and Need, in Part B (page 1) states the following:

"The purpose of the project is to enhance existing recreational opportunities at the Ski Bowl. These enhancements will improve winter recreation. These enhancements, perhaps more importantly, will provide recreational opportunities outside of the ski season.

There is a need for increased economic activity in North Creek outside of the ski season that can be stimulated by increased visitation at the nearby Ski Bowl."

Furthermore the continuing cooperative commitment to improving recreational opportunities in North Creek is evidenced by the Johnsburg Town Board's unanimous November 9, 2017 approval of a new Operating Agreement with ORDA for continued development, operation and maintenance of Ski Bowl Town Park facilities for the next 20 years. Included in the Agreement is a condition that ORDA will "make every effort to operate a vibrant year round operation, with a minimum of 100 days of operation at the Ski Bowl Park between the months of June and October".

(2.C) Julia West, February 7, 2018

The Hudson chair at "Little Gore" is rarely open. We just don't get enough snow. It has not been open yet this year (possibly today because of the snow), and we are well into February. Why does Little Gore need more trails? I don't see that it would attract more people. The development of Burnt Ridge, which opened a lot of terrain at Gore several years ago, doesn't even get a lot of skiers. To create those trails, a massive amount of clearing (and burying the trees) had to be done on some very beautiful land, destroying the original Schaefer trail that allowed for an incredible nature experience for hikers before it was lost.

The North Creek Ski Bowl does NOT need new trails! This land swap is extremely concerning to me- it is a BAD idea! It would be a real shame to lose that beautiful wilderness terrain.

I live in North River; this is my home. Please do not carry through with this land swap. The other improvements to the existing trails at the main mountain are all excellent ideas. Please keep the focus on improving what is already there, not adding more terrain and wasting my taxpayer dollars.

Response: See the response to substantively similar comment 1.A.

(2.D) Julie West, Public Hearing Transcript p. 30

My other concern is skier numbers here at Little Gore. Do we need more terrain at Little Gore? I just haven't seen the mountain even open that much because of climate change or whatever. We just don't have the terrain or snow for it.

Response: Gore communicates the North Creek Ski Bowl as its "Original Base Camp." Thousands of visitors are there each winter, and it is a critical hub of Gore for parking and ticketing. The Ski Bowl's usage has been growing for both alpine and Nordic users. The 2016/2017 season recorded the highest number of lift days (91) at the Ski Bowl in Gore's history. A Thursday/Friday night youth program there has increased in attendance exponentially. During the two seasons that the Nordic Center has been open, the Ski Bowl is attracting large premier race events and increased visits by 117% year over year.

Additionally, the snowmaking improvements contained in this UMP Amendment will enable Ski Bowl terrain to be open earlier and more frequently

(2.E) Bob Nessle, Public Hearing Transcript pp. 38-39

Now, over at Ski Bowl Park, supposing you're going to manage 30,000 customers from June, when school is out, until say September, and then into the fall period a little bit. Now, how are the infrastructure problems going to be solved? 30,000 people are going to require a very complex and well -- and an excellently designed sewer system. Now, there are three town wells within 200 feet of the base area of the Village slopes and the leg up -- the loading area for the Hudson Trail Lift and the new lift and the whole works. So depositing sewage in the aquifer is probably not going to work. I hope -- I certainly hope that it doesn't work. So that's part of the problem. Also, where are all those people going to park and what are they going to do when they come back off the zip line or the zip coaster or on the mountain coaster. And are they going to go to Joe Minder? Are they going to take a break in the pavilion? But, once again, you're dealing with 30,000 people over the period of three or four months. That's another problem.

Response: The 30,000 customers comes from Part B, Section 6, page 4. This is based on estimated peak use numbers of 400 people per day in the spring, 600 per day in the summer and 500 per day in the fall.

During larger events at the Ski Bowl such as nordic competitions, Waynestock, etc., portable toilets are brought into the Ski Bowl. ORDA plans on bringing portable restroom trailers to the site for guests to use. These trailers will not discharge wastewater on the site.

Adequate parking currently exists at the Ski Bowl to accommodate the projected use. Based on numbers in Part B, Section 6, page 4, item 12, 200 cars and 4 buses are expected on weekdays between the peak hours of 10:00 AM and 4:00 PM. This is an average of 33 cars and <1 bus per hour. On weekends between 10:00 AM and 6:00 PM there will be an average of 38 cars and <1 bus per hour. It is estimated that there are currently +/- 190 parking spaces at the Ski Bowl (Part B, Section 6, page 8).

3. MANAGEMENT ACTIONS AND GOALS

(3.A) Brandon Himhoff, February 6, 2018

I would suggest that ORDA also consider that these capital investments must be accompanied by additional operating spending. By expanding the pumps, Gore will be able to make more snow which of course requires more groomer hours and more support. More lifts and more connectivity mean that more of the mountain can be operating, requiring appropriate staffing. The additional tourists will not only want more and better skiing, but better amenities on the mountain, especially including better and more diverse food offerings. The current food offerings and dining experience are significant detractors to our tourists, and improvements in this area are some of the most necessary but perhaps easiest to address. A change to the current food contractor and exploration of new vendors that are more appropriate to the desired mountain experience and who would be more accountable to ORDA should be considered.

Response: The comment is correct that with expanded pumping capability Gore Mountain will be able to make more snow, especially during the increasingly shorter weather windows that seem to have become all too common during our Adirondack winters. Gore Mountain believes that we will ultimately also see energy cost savings as we can better take advantage of those weather windows.

The need for better mountain amenities are certainly something Gore Mountain is are aware of. The newly enlarged Saddle Lodge, the new Straight Brook Lodge and Northwoods Lodge expansion are a step in the right direction and have been well received. We are also currently reviewing plans for some renovation and improvements in the base lodge as well. Customer surveys have echoed this comment about food offerings and dining experience. Gore Mountain is working with our food contractor to make improvements in the current food offerings.

(3.B) Samuel Ferguson, February 9, 2018

Across the country, ski resorts are changing. Lifts are going faster, lodge food is getting better, villages are being developed, and year-round attractions are being built. These changes have helped the ski industry adapt to climate change and maintain corporate profits. As you consider how to develop the Adirondack resorts, I encourage you to also ask the question of to what extent should these resorts be developed. Governor Cuomo announced a vast and expensive expansion plan for Whiteface, Gore, and Mt. Van Hoevenberg, and some of these changes, such as updates to base lodge facilities, are long since overdue. Other amenities, however, seem to be unnecessary expansions that have no place within the Adirondacks.

The Adirondack resorts are unique because they are state-owned facilities focused on serving New York residents. They are not private corporations solely focused on increasing profits. In the winter, these resorts attract millions of visitors and are an important part of the Adirondack experience.

However, in the summer, these resorts play a secondary role as people come from all over to hike the High Peaks and conquer the 46ers. When considering future developments, it is important that the developments are not seen as an addition to the individual resorts, but as added amenities to Adirondack Park as a whole. Route 73 is already overburdened during the summer months, and adding summer attractions to these ski resorts would increase the strain on the already existent infrastructure.

Specifically, I urge ORDA to consider how the proposed 'mountain coaster' fits within the culture of the Adirondacks. The Whiteface Mountain Unit Management Plan states that "Whiteface development will blend with the Adirondack environment and have minimum adverse impacts on surrounding state lands." The metal track of a mountain coaster would not blend into the Adirondack environment, but instead it would stick out like a sore thumb. The Adirondack environment, and especially publicly owned land, is fundamentally made up of wilderness. Constitutional exceptions already had to be made in order to allow ski resort infrastructure, and adding a mountain coaster would further contradict the 'forever wild' promise. A mountain coaster is a tamed and controlled way to experience nature. Riders would not be exposed to the real Adirondack wilderness, but instead they would glimpse nature from a man-made metal track. Outdoor recreation is an important part of the Adirondacks, but a mountain coaster is something that belongs in an amusement park, not the Adirondack wilderness.

All this is not to say that Whiteface, Gore, and Van Hoevenberg should ignore profits, but instead of adding unnecessary infrastructure, they should focus on thriving within their ski industry niche. As other resorts continue to develop, Adirondack resorts should fall back on their skiing roots. They are located in a protected wilderness area that will never have the storefronts and commercial villages of Vail and Jackson Hole, yet the ski mountains themselves offer some of the best terrain east of the Mississippi. While a mountain coaster offers tempting profits, I urge you to embrace the ski culture that already exists at these mountains. Keep them as wild mountains nestled in the middle of the Adirondacks, and people will continue to come and enjoy these resorts for what they are—ski resorts where skiing comes first.

Response: Proposed activities at Gore Mountain will not impact NYS Route 73.

There is no mountain coaster proposed.

The proposed zip coaster is proposed in the North Creek Ski Bowl and not on NYS Forest Preserve land.

(3.C) Jill Broderick, Public Hearing Transcript p. 28

If I may suggest adding to the master plan goals, I would include to improve and enhance the economy for the host benefit community of the Town of Johnsburg, and to improve the health and wellness for the residents by making recreational activities affordable and accessible.

Response: The Management Goals and Objectives contained in section III.C of the draft UMP Amendment/GEIS include the following (emphasis added):

Gore Mountain will seek to modernize facilities at Gore in order to enhance the guest experience, improve skier safety, and increase local and regional economic benefits, while maintaining environmental quality.

Gore Mountain will work closely with the North Creek community and Town of Johnsburg to provide information to visitors about the area and to cooperate in the establishment of a shuttle link between the Ski Center and North Creek and a physical ski link to Ski Bowl Park in order that public use may better help promote the economy of the area.

Other local benefits that are included in the 2017 twenty-year ORDA-Town Agreement include the following:

- ORDA will provide a full season pass for skiing privileges for all students from the Johnsburg Central School or residing in the Town of Johnsburg.
- ORDA will also sponsor six tickets for each resident good for winter or summer.
- ORDA will assist with finding grants and funding, provide free access one day per week for the Johnsburg Youth Program, and develop a sliding hill.
- ORDA will own and operate the Joe Minder Lodge and lease it for \$1 to the Johnsburg Youth Commission between May and October.
- ORDA will also include the Town of Johnsburg in marketing and advertising initiatives.
- Individual businesses within the Town of Johnsburg will receive a discounted opportunity to market and purchase advertising in ORDA publications.
- ORDA will add a feature to its website that portrays the Town of Johnsburg as an authentic ski town.

(3.D) Kelly Nessle, Public Hearing Transcript pp. 31-32

The Town of Johnsburg has received money from the State of New York for a design of trails that leaves from Ski Bowl Park and goes up through to North River and then goes to other parts of the town. And that work is probably going to be starting sometime this year. And what I worry about is a collision between the interests of Gore Mountain and their summer activities and the interests of the Town of Johnsburg with their hiking trails and their biking trails. And I don't want the public that's been coming already from Schenectady and Vermont and everything else coming up here to bike, all of the sudden they can't go on trails that we're making because they are going to be charged. And I don't know if that's in the plans or not, but that would be my concern.

Response: ORDA does not have the authority to charge a fee for recreational uses on facilities that they do not control. There would be no day use fees for public trails entering and leaving the Ski Bowl.

(3.E) Brandon Himhoff, Public Hearing Transcript pp. 33-34

One of the key issues of the mountain is the connectivity of this side of the mountain here and getting to Burnt Ridge, and then using Burnt Ridge maybe as the key to getting down the mountain to the Ski Bowl. The new route really helps a lot, I think, to connect Burnt Ridge back to the main part of the mountain -- or historically the larger part of the mountain. And I wonder if maybe we can address solutions to get to the other side, because I don't think you really increase the skier numbers if the mountain is sort of disjointed. And I think that there's a sort of design issue. I mean, the mountain sort of is as it is. We just need to make trails to connect A to B. And it seems that, unless you kind of create some kind of tunnel

going under the races going on at Echo all the time and Twister, which I guess those are certified as race courses and so there's not a whole lot you can do about that, but you still have to get people from one side to the other. I wonder if you could address how the plan can sort of make that happen.

Response: Connectivity from the central part of Gore Mountain to Burnt Ridge and the Ski Bowl already exists, constructed over the last several years as part of a significant improvement effort to reestablish and bolster the connection to the Ski Bowl. Trail connections from the central part of Gore Mountain to Burnt Ridge are available in three general locations. The first is via Twister, over to Echo, then to The Gully and Cedar's Traverse to the base of Burnt Ridge. This is possibly the easiest route from a user's standpoint. However, as noted in the comment, sometimes this route is not available due to ski racing on Twister and/or Echo. A tunnel or a ski bridge to cross over these trails when racing is happening is not a practical alternative. The second route is from the base area to Burnt Ridge via Cedar's Traverse, which is available during days where racing occurs on Twister and Echo. The third route is available from the upper part of Gore Mountain down the North Side via Pipeline Traverse. From the Pipeline trail one can connect to either Burnt Ridge or the Ski Bowl. Given the existing terrain, landform and configuration of the mountain, these are the most viable locations for suitable trail connections from central Gore to Burnt Ridge. Access from the top of Burnt Ridge to the Ski Bowl is currently available via Hedges, then to Pipeline and Peaceful Valley. An additional future ski trail connection is already approved in the vicinity of the Barkeater glade. When constructed, this trail will provide more direct access to the Ski Bowl from Burnt Ridge.

(3.F) Brandon Himhoff, Public Hearing Transcript p. 35

To really attract tourists, you need a little more variety and high-class cuisine, and it's hard to do that under the current state contracts. And I just wonder if that could be addressed somehow.

Response: There is a trend in the ski industry of offering more upscale food options. ORDA regularly renews its concessionaire contracts, including food services. See the response to substantively similar comment 3.A.

(3.G) Brandon Himhoff, Public Hearing Transcript pp. 35-36

I also just wonder about the time frame of all these plans. There's about 20 years worth of projects probably in that Unit Management Plan and I was wondering if someone can sort of vaguely give their impressions of which things are more of an urgent priority and which things are longer term priorities.

Response: See draft UMP Amendment/GEIS section IV.D, Prioritization of Management Actions (p. IV-11), which lists top, moderate and lower priority management actions.

(3.H) Bob Nessle, Public Hearing Transcript pp. 36-37

I like the idea of the escape route off the top of Burnt Ridge. But how are you going to get over that the rock wall that separates Sagamore and Echo? You're going to blast a tunnel through there? How are you going to get out?

Response: The proposed new trail can start a little ways down the Sagamore trail and get around the rock wall referenced. The bottom of the new trail would merge with the last few hundred feet of the Echo trail and continue into the base area. The proposed new trail also shows a slight widening of the

bottom of the Echo trail on skiers right to allow for this trail merger and to accommodate both public skiers on the new trail and still allow for events on Echo.

(3.1) Peter Bauer (Protect the Adirondacks), Public Hearing Transcript pp. 41-42

We think the scheduling is important. A lot of the unit management plans for forest preserve tracts that enumerate a bunch of different activities schedule them in five-year plans. ORDA hasn't always done that with detail. DEC's always done that with its unit management plans and that would be very helpful.

Response: Most DEC UMP's do not include management actions that require the level of capital expenditures required for many of the management actions undertaken at Gore Mountain such as new ski lifts, major building renovations/expansions, etc. The capital expenditures mean that implementation of management actions at Gore, and at other ORDA venues, is dependent on funding from the NYS budget. For this reason, it is difficult to project an implementation schedule. However, per the response above, proposed management actions were prioritized in the draft UMP Amendment/GEIS.

4. CONSTITUTIONAL LIMITS

(4.A) William Janeway (Adirondack Council), February 9, 2018

Based on the trail mileage information provided within the Draft Generic Environmental Impact Statement, Gore Mtn. is well within its constitutionally allotted 40 miles of trail limit. The Council requests that ORDA clearly outline how it arrived at the listed 32.9 miles of total mileage within this UMP.

Response: An accounting of miles is provided on Table 1A in the draft UMP Amendment/GEIS. The methodologies used to calculate mileage is provided in Appendix 5 (Sections 2.0 and 3.2).

(4.B) William Janeway (Adirondack Council), February 9, 2018

Compliance with Forever Wild: The facilities on state lands must comply with the strict and not always convenient requirements of the "Forever Wild" clause of the constitution.
 These requirements include: constitutional amendments that provide for functions and facilities at Whiteface and Gore that would not otherwise be allowed; adherence to the tightly restricted total miles and widths of downhill ski trails; and, no new tree cutting, clearing, disturbance, or expansion to year-round activities beyond what is now allowed without a constitutional amendment. (Under the constitution, all uses must be winter recreation based.)

Response: See the substantively similar comment 4.A and the response thereto.

(4.C) Peter Bauer (Protect the Adirondacks), Public Hearing Transcript p. 42-43

We also would like to see better detail about the amount of acreage here at Gore, and also at White Face, but here at Gore, that has been used pursuant to the constitutional amendment that was approved, because we think you're getting very close to your clearing limits. We would like to see a real good accounting of the methodology that ORDA is using about the cleared areas, the cleared acreage of

trails, the width of trails and that sort of thing. We've been looking at it independently and we think that you're getting very close to your limits. So I think that's something you need to be very mindful about, so we would like to see a really good accounting of that. That's not really a unit management plan issue, but we think it's an important issue going ahead because it affects your trail upgrades and your trails.

Response: See the response to substantively similar comment 4.A.

5. REGIONAL PLANNING

(5.A) William Janeway (Adirondack Council), February 9, 2018

Planning Sensitive to other Regional Adirondack Needs: The state lands and operations at Whiteface Mtn. are part of a larger network of state lands, recreational uses, trails, and trailheads within the very popular High Peaks region. As the state looks at making important upgrades to the ORDA facilities, and simultaneously develops plans to manage the overuse of the Rt. 73 corridor and the High Peaks, planning needs to be coordinated. For example, one element of overlap could be relocation of parking for the Cascade and Porter Mountains on popular weekends to the Mt. Van Hoevenberg complex, as was done on an experimental basis on Columbus Day weekend in 2017.

Response: All ORDA UMP's for their Adirondack venues are prepared in consultation with NYS DEC and in cooperation with NYS APA. This ensures that proper consideration is given to regional planning issues during the preparation of ORDA venue UMP's.

6. RENEWABLE ENERGY

(6.A) William Janeway (Adirondack Council), February 9, 2018

 Climate Smart, Energy Smart Models: Climate change threatens to redefine Adirondack winter recreation as we now know it. The ORDA facilities can and should combat climate change and be showcases for visitors from across the country and around the world for the latest and best in climate smart renewable energy practices. The facilities should support the Governor's renewable energy goals and comply with Adirondack Park Agency policies.

Response: See section X of the draft UMP Amendment/GEIS, Effects on the Use and Conservation of Energy, which states in part:

"Gore is contracting two 25-year solar power purchase agreements, which combine into a massive 5.325 MW system. Using remote net metering, 85% of Gore's electrical is poised to be offset. In cooperation with Borrego Solar, Gore Mountain is efficiently harvesting sunlight for its energy needs, utilizing 14,589 ground-mounted solar panels across 20 acres of otherwise fallow farmland. The electricity generated credits Gore's meter at a rate higher than power that is traditionally produced, while providing a cleaner, more sustainable source of energy to its electric distribution zone. The agreement is projected to save Gore Mountain approximately \$10 million over the life of the contract, while offsetting 113,919 tons of carbon dioxide, 71,634 pounds of nitrogen oxide emissions, and 131,835 pounds of sulfur. Gore's purchase agreement received support from Governor Cuomo's NY-Sun incentive through the New York State Energy Research and Development Authority (NYSERDA)."

7. PROJECT SUPPORT

(7.A) Sterling and Susan Goodspeed, January 24, 2018

We will be unable to attend tonight's public hearing due to a scheduling conflict but wanted to write to you to express our strongest possible support for the ORDA summer operation at the Ski Bowl. Between the two of us, dating back to 1991, we have operated four businesses within the North Creek area. These include a law firm, a newspaper, a grocery store and a laundromat. We are well aware of both the potential our region offers and the challenges doing business here can present.

ORDA's commitment to a summer operation builds on the growing partnership between the Authority, Town government and local businesses. Creating this venue during the summer season will add new vitality to our existing businesses and will likely attract other businesses to open shop. The proposal also builds off the important heritage that the Ski Bowl and North Creek have always shared with regards to the ski industry. It is fitting that summer operation at the Ski Bowl should provide such a crucial element of our long sought goal to become a four season destination community. The project also marks a welcome commitment to permit an ORDA operation on the edge of our Main Street business district and builds on the significance of the interconnect of the mountains completed severalyears ago.

Response: Comment is noted, no response is required.

(7.B) Brandon Himhoff, February 6, 2018

As a member of the public, a regional business owner, and a member of our local business organizations, I applaud the strong effort that ORDA is making to keep these valuable assets in terrific condition. As times change, these facilities need to adapt and maintain their attraction. Looking carefully at these plans, I feel that they will significantly improve the potential of Gore to attract tourists. Any revenue brought in to the mountain will be accompanied by a significant multiplier in local spending, boosting and supporting many other local businesses and thereby expanding our local employment base. Especially critical are the season expanders such as the improvements in the ski bowl.

Response: Comment is noted, no response is required.

(7.C) William Janeway (Adirondack Council), February 9, 2018

In closing, the Adirondack Council supports legal improvements to ORDA facilities and programs that comply with the constitution, the law and the legal protections which are what keep the Adirondacks a national treasure, a legacy we've inherited, and hold in trust for future generations.

Response: Comment is noted, no response is required.

Appendix 13 Errata – Narrative Summary of Changes Made to the DGEIS in the FGEIS

Errata – Narrative Summary of Changes Made to the DGEIS in the FGEIS

- 1. The executive summary and section I.E have both been supplemented with descriptions of the additional steps taken in the SEQRA process following the issuance of the Public Draft UMP/DGEIS and leading up to the issuance of this Proposed Final UMP/FGEIS.
- 2. Section IV.A.8 has been changed to better describe how a new ski trail located in the area of proposed land exchange adjacent to Ski Bowl Park could affect the existing Rabbit Pond Trail. Mapping (figures 27A, 27B, 27C and 27D) is also provided that shows the Rabbit Pond Ski trail history, location and how a +/- 600 feet section of the trail could be rerouted to accommodate the new ski trail while at the same time maintaining the character of the Rabbit Pond Ski Trail and preserving its use for hiking and for backcountry skiing.
- 3. The following appendices have been added; Appendix 10 DGEIS Public Hearing Transcript, Appendix 11 DGEIS Written Public Comments, Appendix 12 DGEIS Comments and Responses to Comments, Appendix 13 Errata Narrative Summary of Changes Made to the DGEIS in the FGEIS.